

RECORD OWNER/SUBDIVIDER:

R.B. ASHLEY CUSTOMS, LLC  
1011 RIDGE ROAD  
POTTSTOWN, PA 19465

SITE DATA

280 BUCHERT RD  
GILBERTSVILLE, PA 19525  
TAX PARCEL 32-00-06983-00-5  
TAX MAP ID 32045 D03

Table with 3 columns: PARCEL, GROSS, NET. Rows for LOT 1 through LOT 5.

ZONING R-1A RESIDENTIAL DISTRICT

Table with 2 columns: REQUIREMENT, PROPOSED. Rows for LOT AREA, LOT WIDTH, BUILDING SETBACK, REAR YARD, SIDE YARD, BUILDING HEIGHT, BUILDING COVERAGE.

SURVEY DATA

- 1. THE BOUNDARY INFORMATION SHOWN WAS TAKEN FROM A FIELD SURVEY PERFORMED BY MICHAEL C. DIPAOLO, PLS DATED AUGUST 2020, BEING LOT 2 OF THE KELLY MINOR SUBDIVISION
- 2. TOPOGRAPHY INFORMATION SHOWN WAS TAKEN FROM LIDAR AND A FIELD SURVEY PERFORMED BY MICHAEL C. DIPAOLO, PLS DATED AUGUST 2020, AND JUNE 2021.
- 3. ELEVATIONS ARE BASED UPON STATE PLANE COORDINATES AND LIDAR.
- 4. BEARING BASE IS BASED UPON DEEDS OF RECORD.
- 5. THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY AND HAVE NOT BEEN INDEPENDENTLY VERIFIED BY THE OWNER OR ITS REPRESENTATIVE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK, AND AGREES TO BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES, WHICH MIGHT BE OCCASIONED BY THE CONTRACTOR'S FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UNDERGROUND UTILITIES.
- 6. PENNSYLVANIA ONE CALL SYSTEM ACT 38 SERIAL NUMBER FOR THIS PROJECT IS 20211613280.
- 7. EXISTING RIGHT-OF-WAY FOR BUCHERT ROAD WAS TAKEN FROM INFORMATION PROVIDED BY PLANS OF RECORD.
- 8. REFERENCE PLANS: "TWIN PONDS" Plan Book A53, Page 74. "MANGO" Plan Book A42, Page 69. "MANGO, Sect. II" Plan Book A45, Page 64. "MEGA" Plan Book A28, Page 79. "KELLY" Plan Book A54, Page 235. PLANS TITLED "KELLY MINOR SUBDIVISION" PREPARED BY BOYER ENGINEERING, DATED 2020-09-04.
- 9. SITE FALLS IN ZONE (X) BASED ON FEMA MAP NUMBER 42091C00676 REVISED DATE: MARCH 2, 2016.
- 10. NO STEEP SLOPES EXIST ON SITE.

GENERAL NOTES

- 1. LOTS 1-5 TO BE SERVED BY PUBLIC SEWER AND WATER.
- 2. SHEET 1 OF 12 IS TO BE RECORDED.
- 3. ON APPROVAL OF THIS PLAN BY DOUGLASS TOWNSHIP, AND RECORDING OF THE PLAN WITH THE MONTGOMERY COUNTY RECORDER OF DEEDS, THE DEVELOPER SHALL PROVIDE A CERTIFIED COPY OF THE PLAN AND A COPY OF THE PLAN IN ELECTRONIC FORMAT TO DOUGLASS TOWNSHIP.
- 4. INTENDED USE: FIVE SINGLE FAMILY DWELLINGS.
- 5. THERE ARE NO WETLANDS OR HYDRIC SOILS LOCATED ON THIS PARCEL.
- 6. PROVIDE WATER SERVICE TO LOTS 2 AND 3. LOTS 1, 4, AND 5 MAY BE 3".
- 7. ALL PROPOSED UTILITIES SHALL BE INSTALLED UNDERGROUND.
- 8. NO ADDITIONAL DEVELOPMENT RESTRICTIONS REGARDING THE UTILITIES ARE REQUIRED BY THE RESPECTIVE UTILITY COMPANIES.
- 9. BUYER ACKNOWLEDGES THAT THERE WILL BE AN EASEMENT ESTABLISHED GRANTING HUGH AND JUDITH KELLY AND ALL FUTURE OWNERS, HEIRS, AND ASSIGNS TO UTILIZE THE PORTION OF THE SUBJECT PROPERTY THAT IS ON THE NORTH AND EAST SIDE OF BUCHERT ROAD. THIS AREA CAN BE UTILIZED BY GRANTEES AS FUTURE DRIVEWAY OR ROAD ACCESS OR FOR ANY OTHER PURPOSE GRANTEE ELECTS.
- 10. EXISTING VEGETATION TO REMAIN SHALL BE PROTECTED BY ORANGE CONSTRUCTION FENCE.
- 11. REQUIRED PLANT MATERIAL SHALL BE MAINTAINED FOR THE LIFE OF THE PROJECT TO ACHIEVE THE REQUIRED VISUAL EFFECT OF THE BUFFER OR SCREEN. IT SHALL BE THE ULTIMATE RESPONSIBILITY OF THE SUCCESSIVE PROPERTY OWNERS TO INSURE THAT THE REQUIRED PLANTINGS ARE PROPERLY MAINTAINED, DEAD OR DISEASED PLANT MATERIAL SHALL BE REMOVED OR TREATED PROMPTLY BY THE PROPERTY OWNER AND REPLACED AT THE NEXT PLANTING SEASON.
- 12. ALL CLEAR SIGHT TRIANGLES ARE TO REMAIN CLEAR AND ARE THE RESPONSIBILITY OF THE PROPERTY OWNER TO MAINTAIN PLANTINGS WITHIN THE TRIANGLES.
- 13. ANY TREE OR SHRUB THAT DIES WITHIN 18 MONTHS OF PLANTING SHALL BE REPLACED BY THE DEVELOPER. ANY TREE OR SHRUB THAT WITHIN 18 MONTHS OF PLANTING OR REPLANTING IS DEEMED, IN THE OPINION OF THE MUNICIPALITY, NOT TO HAVE SURVIVED OR NOT TO HAVE GROWN IN A MANNER CHARACTERISTIC OF ITS TYPE, SHALL BE REPLACED. SUBSTITUTIONS FOR CERTAIN SPECIES OF PLANTS MAY ONLY BE MADE ONLY WHEN APPROVED BY THE MUNICIPALITY.
- 14. INSPECTIONS, OPERATION, AND MAINTENANCE OF THE PROPOSED STORMWATER FACILITIES ARE THE RESPONSIBILITY OF THE PROPERTY OWNER. NO ALTERATIONS OR DEVIATIONS OF THESE FACILITIES ARE PERMITTED WITHOUT PRIOR TOWNSHIP WRITTEN APPROVAL.
- 15. THE TOWNSHIP AND THEIR REPRESENTATIVES SHALL BE GRANTED A "BLANKET EASEMENT" TO ACCESS STORMWATER FACILITIES FOR INSPECTION PURPOSES.
- 16. EXISTING TREES TO BE USED TO COMPLY WITH THE ADDITIONAL PLANTING REQUIREMENTS OF SECTION 420-6.B.
- 17. THE PROPOSED SANITARY MAIN WILL BE DEDICATED TO BERKS-MONTGOMERY MUNICIPAL AUTHORITY. THE PROPOSED SEWER LATERALS, PUMPS, AND SERVICES SHALL BE OWNED AND MAINTAINED BY THE INDIVIDUAL LOT OWNERS.

SANITARY NOTES

- 1. ALL SANITARY SEWER MANHOLES COVERS SHALL HAVE INSERTS EXCEPT WHERE COVERS ARE WATERIGHT.
- 2. ALL SANITARY SEWER LINES SHALL HAVE A MINIMUM COVER OF FOUR (4) FEET.
- 3. LATERALS SHALL HAVE A MINIMUM COVER OF FOUR (4) FEET AND A MINIMUM SLOPE OF 1" PER FOOT.
- 4. DEVELOPER IS RESPONSIBLE TO SECURE ALL NECESSARY PERMITS AND PAY APPLICABLE FEES.
- 5. ALL WORK TO BE IN ACCORDANCE WITH BMMR RULES AND REGULATIONS.
- 6. DEVELOPER SHALL COMPLY WITH ALL PERMIT REQUIREMENTS AND CONDITIONS SET FORTH BY BMMR.
- 7. BUILDING SEWERS AND GRINDER PUMP DISCHARGE SHALL BE TESTED IN ACCORDANCE WITH UCC AND PLUMBING CODE REQUIREMENTS.
- 8. A SEWAGE SERVICE/IMPROVEMENTS AGREEMENT BETWEEN THE DEVELOPER AND BMMR WILL NEED TO BE EXECUTED AND IN PLACE PRIOR TO CONSTRUCTION.
- 9. EASEMENT AGREEMENTS WILL ALSO NEED TO BE EXECUTED FOR SEWER LINES LOCATED WITHIN EXISTING AND PROPOSED EASEMENTS.

APPROVED AS NOTED  
BMMR BOARD OF STANDARDS

GEORGE M. MOSER, AUTHORITY CHAIRMAN  
DATE: \_\_\_\_\_

WAVER REQUESTS:

- AT A MEETING HELD ON 14 DAY OF APRIL, 2022, THE BOARD OF SUPERVISORS GRANTED WAIVERS OF THE FOLLOWING SECTIONS OF THE TOWNSHIP'S SUBDIVISION AND LAND DEVELOPMENT ORDINANCE FOR THIS PLAN.
- 1. SECTION 405.1 - TO NOT REQUIRE CARTWAY WIDENING.
- 2. SECTION 407.1.A (3) & (4) - TO NOT REQUIRE A HORIZONTAL CURVE RADIUS OF 150' FOR THE EXISTING ROAD.
- 3. SECTION 424.1.A - TO NOT REQUIRE A SIDEWALK ALONG THE EXISTING ROAD.
- 4. SECTION 425.1 - TO NOT REQUIRE CURBS ALONG THE EXISTING ROAD.
- 5. SECTION 416.4.E - TO NOT REQUIRE A SHARED DRIVEWAY OF LOTS 2 AND 3.
- 6. SECTION 305.4.I - TO ONLY LOCATE TREES GREATER THAN 12".
- 7. SECTION 420-1.B.3.c - TO NOT REQUIRE A LANDSCAPE ARCHITECT'S SEAL AND SIGNATURE.
- 8. SECTION 410.M - TO ALLOW THE USE OF 12" HDPE PIPE TO OUTLET RAIN GARDENS.
- 9. SECTION 410.B - TO NOT REQUIRE A 2 FOOT EMERGENCY SPILLWAY.
- 10. SECTION 410.I.3 - TO ALLOW SIDE SLOPES OF 3:1 ON THE RAIN GARDENS.
- 11. SECTION 407.B - TO ALLOW AN ORIFICE LESS THAN 3" IN DIAMETER.

AT A MEETING HELD ON \_\_\_\_ DAY OF \_\_\_\_\_, 2023, THE BOARD OF SUPERVISORS GRANTED WAIVERS OF THE FOLLOWING SECTIONS OF THE TOWNSHIP'S ACT 167 ORDINANCE FOR THIS PLAN.

- 1. SECTION 405.1.a - TO NOT REQUIRE A TWO-FOOT SEPARATION OF THE LIMITING ZONE FOR RAIN GARDENS 3 AND 4.
- 2. SECTION 407 - TO NOT REQUIRE THE USE OF THE SCS METHOD FOR STREAM BANK EROSION.
- 3. SECTION 408 - TO NOT REQUIRE 50% RATE REDUCTION FOR THE 100-YR STORM.

PLAN LIST

- 1. FINAL PLAN
- 2. GRADING AND UTILITY/LANDSCAPING PLAN
- 3. DETAILS SHEET
- 4. DETAILS SHEET
- 5. SEWER UTILITY PROFILE SHEET
- 6. WATER UTILITY PROFILE SHEET
- 7. EXISTING FEATURES/ENVIRONMENTAL RESOURCES PLAN
- 8. EXISTING FEATURES/AERIAL PLAN
- 9. EROSION AND SEDIMENTATION CONTROL PLAN
- 10. EROSION AND SEDIMENTATION CONTROL DETAILS
- 11. EROSION AND SEDIMENTATION CONTROL NARRATIVE
- 12. POST CONSTRUCTION STORMWATER MANAGEMENT PLAN
- 13. POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS
- 14. POST CONSTRUCTION STORMWATER MANAGEMENT NARRATIVE
- 15. POST CONSTRUCTION STORMWATER MANAGEMENT SEQUENCE
- 16. PREDEVELOPED DRAINAGE PLAN - RATE
- 17. POSTDEVELOPED DRAINAGE PLAN - RATE
- 18. PREDEVELOPED DRAINAGE PLAN - VOLUME
- 19. POSTDEVELOPED DRAINAGE PLAN - VOLUME

EXISTING LINE EASEMENT TABLE

Table with 3 columns: Line #, Length, Direction. Rows L1, L2, L3, L4.

PROPOSED EASEMENT LINE TABLE

Table with 3 columns: Line #, Length, Direction. Rows L5, L6, L7, L8.

EXISTING CURVE EASEMENT TABLE

Table with 4 columns: Curve #, Length, Radius, Delta. Row C2.

CERTIFICATION OF OWNERSHIP

COMMONWEALTH OF PENNSYLVANIA  
COUNTY OF MONTGOMERY  
ON THIS \_\_\_\_ DAY OF \_\_\_\_\_, 20\_\_\_\_, BEFORE ME, THE SUBSCRIBER, A NOTARY PUBLIC OF THE COMMONWEALTH OF PENNSYLVANIA, RESIDING IN \_\_\_\_\_, PERSONALLY APPEARED \_\_\_\_\_, AGENT FOR R.B. ASHLEY CUSTOMS, LLC, WHO ACKNOWLEDGE THEMSELVES TO BE THE OWNERS OF THE LAND SHOWN HEREON. ALL NECESSARY APPROVALS OF THIS PLAN HAVE BEEN OBTAINED AND ARE ENDORSED THEREON AND THAT WE DESIRE THIS PLAN TO BE DULY RECORDED.

OWNER \_\_\_\_\_ OWNER \_\_\_\_\_

SURVEYOR'S CERTIFICATION

I HEREBY CERTIFY THAT THE PLAN SHOWN AND DESCRIBED HEREON, AS WELL AS ALL OTHER DRAWINGS WHICH ARE PART OF THE PLAN SET, ARE TRUE AND CORRECT BEARING MY SEAL, ARE TRUE AND CORRECT TO THE ACCURACY REQUIRED BY THE DOUGLASS TOWNSHIP SUBDIVISION AND LAND DEVELOPMENT ORDINANCE, AND WERE PREPARED BY ME OR UNDER MY DIRECTION FOR WHICH I ACCEPT FULL RESPONSIBILITY, AND REPRESENTS A FIELD SURVEY PERFORMED BY ME OR UNDER MY DIRECTION. THE EXISTING PERIMETER MONUMENTS SHOWN HEREON HAVE BEEN LOCATED AS PART OF THE SURVEY AND ALL OTHER PROPOSED PERIMETER MONUMENTS SHALL BE SET.

MICHAEL DIPAOLO, PLS  
DATE \_\_\_\_\_

TOWNSHIP SUPERVISOR'S CERTIFICATION

THIS PLAN HAS BEEN APPROVED BY THE DOUGLASS TOWNSHIP BOARD OF SUPERVISORS THIS \_\_\_\_ DAY OF \_\_\_\_\_, 20\_\_\_\_.

CHAIRMAN \_\_\_\_\_  
ATTESTED: SECRETARY \_\_\_\_\_

TOWNSHIP PLANNING AGENCY CERTIFICATION



THIS PLAN HAS BEEN APPROVED BY THE DOUGLASS TOWNSHIP PLANNING AGENCY THIS \_\_\_\_ DAY OF \_\_\_\_\_, 20\_\_\_\_.

CHAIRMAN \_\_\_\_\_  
ATTESTED: SECRETARY \_\_\_\_\_

TOWNSHIP ENGINEER'S CERTIFICATION

REVIEWED THIS \_\_\_\_ DAY OF 20\_\_\_\_ BY THE TOWNSHIP ENGINEER FOR DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PA.

ENGINEERS SIGNATURE \_\_\_\_\_



LEGEND  
EX. TRACT LINE  
EX. BOUNDARY  
EX. RIGHT-OF-WAY  
SETBACKS  
EX. SANITARY  
EX. MONUMENTATION  
EX. UTILITY POLE & GUY WIRE  
EX. OVERHEAD WIRES  
EX. FIRE HYDRANT  
EX. SANITARY MANHOLE  
EX. TREELINE  
EX. SOILS  
PR. EDGE OF PAVING  
PR. BUILDING  
PR. WATER SERVICE  
PR. SEWER LATERAL  
PR. LOW PRESSURE SEWER  
PR. SANITARY SEWER  
PR. SEWER MANHOLE  
PR. SEWER CLEANOUT  
PR. SEWER SHUTOFF  
PR. WATER VALVE  
PR. GRINDER PUMP  
PR. PROPERTY CORNER (STEEL PIN)  
PR. PROPERTY CORNER (CONCRETE MON.)

CERTIFICATION OF THE COUNTY RECORDER OF DEEDS AND THE COUNTY PLANNING COMMISSION

RECORDED IN THE OFFICE OF RECORDER OF DEEDS FOR MONTGOMERY COUNTY, AT NORRISTOWN, PENNSYLVANIA, THIS \_\_\_\_ DAY OF \_\_\_\_\_, 20\_\_\_\_.

BY: \_\_\_\_\_ RECORDER OF DEEDS

MCPC No. 20-0206-001  
PROCESSED AND REVIEWED. REPORT PREPARED BY MONTGOMERY COUNTY PLANNING COMMISSION IN ACCORDANCE WITH THE MUNICIPALITIES PLANNING CODE.

CERTIFIED THIS DATE \_\_\_\_\_

FOR THE DIRECTOR  
MONTGOMERY COUNTY PLANNING COMMISSION

Table with 4 columns: NO., REVISION, DATE, BY, APP. Rows 1 through 13.

CLIENT: R.B. ASHLEY CUSTOMS, LLC  
1011 RIDGE ROAD  
POTTSTOWN, PA 19465



SUBJECT: SUBDIVISION AND LAND DEVELOPMENT FINAL PLAN  
**KELLY ACRES**  
DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA

1860 WEAVERTOWN ROAD, SUITE 100  
DOUGLASSVILLE, PA 19518  
PHONE: 610-689-8021  
FAX: 610-689-8538

PROJECT NO. 20-374A  
DWG. NO. FP120374A  
SHEET NO. 1 OF 23

DESIGN: BDB  
CHKD. BY: BDB  
DRAWN BY: WJD  
CHKD. BY: BDB  
DATE: 2021-06-17  
SCALE: 1"=50'

P:\PROJECTS\20-374A\_Kelly Acres\Drawings\20210617\20210617.dwg, 18-May-23 09:34:53



**LEGEND**

- EX. TRACT LINE
- EX. BOUNDARY
- EX. RIGHT-OF-WAY
- EX. SETBACKS
- EX. SANITARY
- EX. WATER LINE
- EX. MONUMENTATION
- EX. UTILITY POLE & GUY WIRE
- EX. OVERHEAD WIRES
- EX. SANITARY MANHOLE
- EX. FIRE HYDRANT
- EX. TREELINE
- EX. SOILS
- EX. CONTOURS
- PR. CONTOURS
- INFILTRATION TEST PIT
- PR. EDGE OF PAVING
- PR. BUILDING
- PR. WATER SERVICE
- PR. SEWER LATERAL
- PR. FORCE MAIN
- PR. SANITARY SEWER
- PR. TREELINE
- PR. STORMWATER PIPE
- PR. SPILLWAY/CHANNEL LINING
- PR. RIP RAP
- PR. SEWER MANHOLE
- PR. SEWER CLEANOUT
- PR. SEWER SHUTOFF
- PR. WATER VALVE
- PR. TREES

TEST PIT #	LIMITING ZONE ELEVATION	LIMITING ZONE SEPARATION (FT)
1	351.25	2.00
2	368.83	2.17
3	364.00	2.00
4	354.17	1.08
5	357.75	1.00

**LANDSCAPE SCHEDULE**

SYMBOL	NAME	QUANTITY	NATIVE	ROOT	SIZE
	RED MAPLE, ACER RUBRUM*	23	Y	B&B	MIN 2.5" CAL
	RED OAK, QUERCUS RUBRA**	23	Y	B&B	MIN 2.5" CAL
	EASTERN WHITE PINE, PINUS STROBUS*	23	Y	B&B	MIN 2.5" CAL
	PIN OAK, QUERCUS PALUSTRIS*	23	Y	B&B	MIN 2.5" CAL
	RIVER BIRCH, BETULA NIGRA	23	Y	B&B	MIN 2.5" CAL
	INKBERRY HOLLY, ILEX GLABRA*	15	Y	HT	MIN 18"

**RAIN GARDEN SCHEDULE**

SYMBOL	SPECIES	QUANTITY	SIZE	RC1	RC2	RC3	RC4	RC5
	EASTERN REDBUD, CERCIS CANADENSIS	68	MIN 2.5" CAL / B&B	24	11	10	11	12
	FLOWERING DOGWOOD, CORNUS FLORIDA	68	MIN 2.5" CAL / B&B	24	11	10	11	12
	INKBERRY HOLLY, ILEX GLABRA	319	HT	112	51	47	52	56

**STREET TREE REQUIREMENTS:**  
 1 TREE PER 35FT OF STREET FRONTAGE  
 855.18 FT STREET FRONTAGE  
 855.18 / 35 = 24.4 = 25 TREES REQUIRED  
 25 TREES PROVIDED

**BUFFER TREE REQUIREMENTS:**  
 BUFFER LENGTH = 300 FEET  
 3 CANOPY TREES  
 6 UNDERSTORY TREES  
 2 EVERGREEN TREES

**BUFFER TREES PROVIDED:**  
 3 CANOPY TREES  
 6 UNDERSTORY TREES  
 2 EVERGREEN TREES

**RAIN GARDEN PLANTING CALCULATIONS:**  
 300 TREES PER ACRE OF BMP BOTTOM AREA  
 700 SHRUBS PER ACRE OF BMP BOTTOM AREA

**SOILS TABLE**

SYMBOL	NAME/DESC
P&B	PENN SILT LOAM, 3 TO 6 PERCENT SLOPES
KIB	KILNVILLE CHANNERY SILT LOAM, 3 TO 6 PERCENT SLOPES

**LANDSCAPING CERTIFICATION**

I HEREBY CERTIFY THAT THE TREE SURVEY AND LANDSCAPING PLAN SHOWN AND DESCRIBED HEREON HAVE BEEN COMPLETED PER REQUIREMENTS SET FORTH IN THE DOUGLASS TOWNSHIP SUBDIVISION AND LAND DEVELOPMENT ORDINANCE.

BRIAN D. BOYER, PE  
 DATE \_\_\_\_\_

**REVISION**

NO.	REVISION	DATE	BY	APP.
13	REVISED PER OHMA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BOB
12	REVISED PER PENNDOT REVIEW LETTER DATED APRIL 21, 2023 AND MDCP LETTER DATED APRIL 16, 2023	2023-05-03	SSR	BOB
11	REVISED PER PENNDOT REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN	2023-03-07	SSR	BOB
10	REVISED PER MDCP EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BOB
9	REVISED PER MDCP REVIEW LETTER DATED JANUARY 19, 2023	2023-02-28	SSR	BOB
8	REVISED PER MDCP REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BOB
7	REVISED PER MDCP REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BOB
6	REVISED PER MDCP EMAIL DATED JULY 28, 2022	2022-07-29	JLK	BOB
5	REVISED PER MDCP REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	BOB
4	REVISED PER MDCP REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BOB
3	REVISED PER MDCP REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BOB
2	REVISED PER SITE REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BOB
1	REVISED PER PENNDOT REVIEW LETTER DATED NOVEMBER 9, 2021 AND MDCP REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BOB

**CLIENT**  
 R.B. ASHLEY CUSTOMS, LLC  
 1011 RIDGE ROAD  
 POTTSVILLE, PA 19465

**SUBJECT**  
 GRADING AND UTILITY PLAN  
 LANDSCAPING PLAN  
 KELLY ACRES  
 DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA

**PROJECT NO.**  
 20-374A


**DWG. NO.**  
 GR120374A

**SHEET NO.**  
 2 OF 23

**SCALE**  
 1"=40'

**DATE**  
 2020-09-04

**SEAL**



RAIN GARDEN	TEST PIT	A	B	C	D	E	F	G	H	I	J	K	L	M	N	P	Q	R	S	T	U	V	
1	1	354.75	355.25	355.75	356.25	356.75	45	13.9	346.50	18	N/A	N/A	355.35	351.25	N/A	10	8	355.17	N/A	N/A	N/A	N/A	
2	2	372.50	372.50	373.50	374.00	375.00	40	6.3	368.00	18	N/A	N/A	372.67	368.83	N/A	10	8	372.61	N/A	N/A	N/A	N/A	
3	4	357.25	357.75	358.25	358.75	359.25	20	3.9	352.65	24	355.25	354.17	357.33	354.17	356.25	10	8	356.88	356.18	356.00	5	352.05	
4	5	360.75	361.15	361.75	362.25	368.75	40	6.8	356.03	24	358.75	357.00	359.80	357.75	359.75	10	8	359.61	359.62	358.00	15	355.15	
5	3	367.50	368.00	368.50	369.00	365.00	25	8.3	363.43	18	N/A	N/A	365.00	367.81	364.00	N/A	10	8	367.69	N/A	365.00	5	363.05



**NOTES FOR RAIN GARDEN:**

- ALL BASIN EMBANKMENTS SHALL BE PLACED AT A MAXIMUM OF EIGHT (8) LIFTS TO A MINIMUM OF 95% OF MAXIMUM DRY DENSITY AS ESTABLISHED BY ASTM D-1557, PRIOR TO PROCEEDING TO THE NEXT LIFT. THE COMPACTION SHALL BE CHECKED BY THE TOWNSHIP ENGINEER. THE DEVELOPER'S CONTRACTOR SHALL OBTAIN THE SERVICES OF A QUALIFIED LABORATORY TECHNICIAN TO CONDUCT COMPACTION TESTS ON THE LEADING AND TRAILING EDGE OF THE TRENCH ALONG WITH THE TOP OF THE BERM. ALL TEST SHALL BE FURNISHED TO THE TOWNSHIP FOR REVIEW.
- A CLAY CORE SHALL BE PROVIDED FOR THE BERM WITH A TOP ELEVATION AT THE PRINCIPAL SPILLWAY ELEVATION. MINIMUM TOP WIDTH OF 2' AND SIDE SLOPE OF 1:1.
- A KEY TRENCH SHALL BE PROVIDED UNDER FILL EMBANKMENTS. THE KEY TRENCH SHALL BE A MINIMUM OF 8" WIDE, 2' BELOW EXISTING GRADE, WITH SIDE SLOPES OF 1:1.
- ALL JOINTS SHALL BE WATER TIGHT.

**MAINTENANCE:**

- THE OVERLYING VEGETATION OF SUBSURFACE INFILTRATION FEATURES SHOULD BE MAINTAINED IN GOOD CONDITION, AND ANY BARE SPOTS RE-VEGETATED AS SOON AS POSSIBLE.
- VEHICULAR ACCESS ON SUBSURFACE INFILTRATION AREAS SHOULD BE PROHIBITED, AND CARE SHOULD BE TAKEN TO AVOID EXCESSIVE COMPACTION BY MOWERS. IF ACCESS IS NEEDED, USE OF PERMEABLE, TURF REINFORCEMENT SHOULD BE CONSIDERED.

**LEVEL SPREADER SPECIFIC OUTLET**



**NOTES**

- SPREADER IS TO BE 30' IN LENGTH.
- OUTFALL PIPE IS TO BE TERMINATED IN "TEE" COUPLING.
- YARD DRAIN BASIN OR INLINE COUPLINGS SHALL BE USED WITH SURFACE GRATES AT EACH OF THE PERFORATED PIPE TO THE SURFACE.

BMP	A	B
RAIN GARDEN 3	354.00	352.00
RAIN GARDEN 4	357.00	355.00
RAIN GARDEN 5	365.00	363.00

**LEVEL SPREADER DETAIL (LS3, LS4, LS5)**

NO SCALE

**NOTES**

- PREPARE BEDDING; BEDDING MATERIAL AROUND THE END SECTION MAY BE THE SAME AS THE MATERIAL AROUND THE PIPE. PLACE A FEW INCHES OF BEDDING MATERIAL IN THE TRENCH OR DITCH WHERE THE END SECTION WILL BE PLACED. COMPACT AND CONTOUR THIS MATERIAL TO GENERALLY MATCH THE END SECTION. EXCAVATE AN AREA IN THE BEDDING WHERE THE TOE TROUGH WILL SEAT SO THAT THE END SECTION WILL ALIGN TO PROPER GRADE IN THE FINISHED INSTALLATION.
- PLACE END SECTION ON PIPE; OPEN THE END SECTION COLLAR AND SEAT IT OVER THE LAST TWO PIPE CORRUGATIONS. ONCE THE END SECTION IS POSITIONED, CHECK TO MAKE SURE THE INVERT OF THE END SECTION MATCHES THE INVERT OF THE PIPE AND THAT THE END SECTION IS ALIGNED TO THE PROPER GRADE.
- SECURE THE END SECTION; SLIP THE STAINLESS STEEL ROD THROUGH THE PRE-DRILLED HOLES AT THE TOP OF THE COLLAR. THE ROD SHOULD BE BETWEEN THE CROWNS OF THE TWO CORRUGATIONS AT THE END OF THE PIPE. PLACE A WASHER ON EITHER END OF THE ROD; PLACE A NUT ON EITHER END OF THE ROD AND HAND TIGHTEN WITH A WRENCH UNTIL THE COLLAR IS TIGHT AROUND THE PIPE. DO NOT OVER-TIGHTEN.
- SECURE TOE TROUGH; TO PREVENT WASHOUTS FROM HIGH VELOCITY FLOW, IT IS RECOMMENDED THAT THE TOE TROUGH BE SECURED WITH CONCRETE. POUR CONCRETE IN THE TROUGH UP TO THE LEVEL OF THE TRENCH OR DITCH BOTTOM AND ALONG THE ENTIRE LENGTH OF THE TROUGH.
- FINISH BACKFILL; SHOVEL BACKFILL AROUND THE END SECTION IN 6-TO 9-INCH LAYERS EQUALLY ON BOTH SIDES. KNIFE IT IN TO ELIMINATE VOIDS. TAMP WITH A SMALL-FACED COMPACTOR OR OTHER EQUIPMENT SUITABLE FOR SMALL AREAS. CONTINUE PLACING, KNIFING AND COMPACTING BACKFILL MATERIAL IN LAYERS TO THE TOP OF THE END SECTION TO SEAT IT WELL INTO THE BACKFILL.

**NYLOPLAST 18" INLINE DRAIN: 2718AG \_\_ X**

**GRATE OPTIONS**


GRATE OPTIONS	LOAD RATING	PART #	DRAWING #
PERFORATED	MEETS H10	1899CGP	7001-110-212
2\"/>			

**NOTES:**

- GRATED COVER SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05.
- FRAMES SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05.
- DRAINAGE CONNECTION SUB JOINT TIGHTNESS SHALL CONFORM TO ASTM D2217 FOR CORRUGATED HDPE (ADS N-12 HANCOR DUAL WALL, N-12 HP, & PVC SEWER).
- DIMENSIONS ARE FOR REFERENCE ONLY. ACTUAL DIMENSIONS MAY VARY.
- DIMENSIONS ARE IN INCHES.
- SEE DRAWING NO. 7001-110-275 FOR ADS N-12 & HANCOR DUAL WALL BELL INFORMATION & DRAWING NO. 7001-110-364 FOR N-12 HP BELL INFORMATION.


**THIS PRINT DISCLOSES SUBJECT MATTER IN WHICH NYLOPLAST HAS PROPRIETARY RIGHTS. THE RECEIPT OR POSSESSION OF THIS PRINT DOES NOT CONFER, TRANSFER, OR LICENSE THE USE OF THE DESIGN OR TECHNICAL INFORMATION SHOWN HEREIN. REPRODUCTION OF THIS PRINT OR ANY INFORMATION CONTAINED HEREIN, OR MANUFACTURE OF ANY ARTICLE HEREFROM FOR THE DISCLOSURE TO OTHERS IS FORBIDDEN, EXCEPT BY SPECIFIC WRITTEN PERMISSION FROM NYLOPLAST.**

**3130 WARD AVE  
BURLINGTON, GA 30018  
PH: (770) 932-2449  
FAX: (770) 932-2499  
www.nyloplast.com**




**STORM SEWER TRENCH - TYP. BACKFILL DETAIL**

NO SCALE




**SOIL AMENDMENT**

NO SCALE




**DECIDUOUS TREE PLANTING DETAIL**

NO SCALE



**VEGETATED SWALE CROSS SECTION**

NO SCALE




**TYPICAL DRIVEWAY PAVEMENT SECTION DETAIL**

NO SCALE


**8\"/>**

NO SCALE




**SHRUB PLANTING DETAIL**

BALLED OR BARE SHRUB-NO SCALE



**TREE PROTECTION DETAIL**

NO SCALE



**CONIFEROUS TREE PLANTING DETAIL**

NO SCALE




**Know what's below  
Call Before You Dig!**
















BEFORE YOU DIG ANYWHERE IN PENNSYLVANIA CALL 1-800-242-1776  
PA LAW REQUIRES THREE WORKING DAYS NOTICE TO UTILITIES BEFORE YOU EXCAVATE, DRILL, BLAST OR DEMOLISH

**SERIAL NO. 20211613280 (DOUGLASS TWP)**

NO.	REVISION	DATE	BY	APP.
13.	REVISED PER BMM EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BBB
12.	REVISED PER PENNDOT REVIEW LETTER DATED APRIL 21, 2023 AND MDCP LETTER DATED APRIL 18, 2023	2023-05-03	SSR	BBB
11.	REVISED PER PENNDOT REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN	2023-03-07	SSR	BBB
10.	REVISED PER MDCD EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BBB
9.	REVISED PER MDCD REVIEW LETTER DATED JANUARY 18, 2023	2023-01-20	SSR	BBB
8.	REVISED PER MDCD REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BBB
7.	REVISED PER MDCD REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BBB
6.	REVISED PER MDCD EMAIL DATED JULY 28, 2022	2022-07-29	JLK	BBB
5.	REVISED PER MDCD REVIEW LETTER DATED JUNE 28, 2022	2022-06-30	SSR	BBB
4.	REVISED PER MDCD REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BBB
3.	REVISED PER MDCD REVIEW LETTER DATED JANUARY 16, 2022	2022-03-03	SSR	BBB
2.	REVISED PER SDE REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BBB
1.	REVISED PER PENNDOT REVIEW LETTER DATED NOVEMBER 5, 2021 AND MDCD REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BBB

CLIENT	R.B. ASHLEY CUSTOMS, LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465	SUBJECT	KELLY ACRES DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA
DESIGN	BBB	CHKD. BY	BBB
DRAWN BY	WJD	CHKD. BY	BBB
DATE	2020-09-04	SCALE	NOT TO SCALE
PROJECT NO.	1860 WEAVERTOWN ROAD, SUITE 100 DOUGLASSVILLE, PA 19518 PHONE: 610-689-8021 FAX: 610-689-4538	DWG. NO.	20-374A
			DE120374A
			3 OF 23





PROJECTS: 20-274A, 20-274B, 20-274C, 20-274D, 20-274E, 20-274F, 20-274G, 20-274H, 20-274I, 20-274J, 20-274K, 20-274L, 20-274M, 20-274N, 20-274O, 20-274P, 20-274Q, 20-274R, 20-274S, 20-274T, 20-274U, 20-274V, 20-274W, 20-274X, 20-274Y, 20-274Z, 20-274AA, 20-274AB, 20-274AC, 20-274AD, 20-274AE, 20-274AF, 20-274AG, 20-274AH, 20-274AI, 20-274AJ, 20-274AK, 20-274AL, 20-274AM, 20-274AN, 20-274AO, 20-274AP, 20-274AQ, 20-274AR, 20-274AS, 20-274AT, 20-274AU, 20-274AV, 20-274AW, 20-274AX, 20-274AY, 20-274AZ, 20-274BA, 20-274BB, 20-274BC, 20-274BD, 20-274BE, 20-274BF, 20-274BG, 20-274BH, 20-274BI, 20-274BJ, 20-274BK, 20-274BL, 20-274BM, 20-274BN, 20-274BO, 20-274BP, 20-274BQ, 20-274BR, 20-274BS, 20-274BT, 20-274BU, 20-274BV, 20-274BW, 20-274BX, 20-274BY, 20-274BZ, 20-274CA, 20-274CB, 20-274CC, 20-274CD, 20-274CE, 20-274CF, 20-274CG, 20-274CH, 20-274CI, 20-274CJ, 20-274CK, 20-274CL, 20-274CM, 20-274CN, 20-274CO, 20-274CP, 20-274CQ, 20-274CR, 20-274CS, 20-274CT, 20-274CU, 20-274CV, 20-274CW, 20-274CX, 20-274CY, 20-274CZ, 20-274DA, 20-274DB, 20-274DC, 20-274DD, 20-274DE, 20-274DF, 20-274DG, 20-274DH, 20-274DI, 20-274DJ, 20-274DK, 20-274DL, 20-274DM, 20-274DN, 20-274DO, 20-274DP, 20-274DQ, 20-274DR, 20-274DS, 20-274DT, 20-274DU, 20-274DV, 20-274DW, 20-274DX, 20-274DY, 20-274DZ, 20-274EA, 20-274EB, 20-274EC, 20-274ED, 20-274EE, 20-274EF, 20-274EG, 20-274EH, 20-274EI, 20-274EJ, 20-274EK, 20-274EL, 20-274EM, 20-274EN, 20-274EO, 20-274EP, 20-274EQ, 20-274ER, 20-274ES, 20-274ET, 20-274EU, 20-274EV, 20-274EW, 20-274EX, 20-274EY, 20-274EZ, 20-274FA, 20-274FB, 20-274FC, 20-274FD, 20-274FE, 20-274FF, 20-274FG, 20-274FH, 20-274FI, 20-274FJ, 20-274FK, 20-274FL, 20-274FM, 20-274FN, 20-274FO, 20-274FP, 20-274FQ, 20-274FR, 20-274FS, 20-274FT, 20-274FU, 20-274FV, 20-274FW, 20-274FX, 20-274FY, 20-274FZ, 20-274GA, 20-274GB, 20-274GC, 20-274GD, 20-274GE, 20-274GF, 20-274GG, 20-274GH, 20-274GI, 20-274GJ, 20-274GK, 20-274GL, 20-274GM, 20-274GN, 20-274GO, 20-274GP, 20-274GQ, 20-274GR, 20-274GS, 20-274GT, 20-274GU, 20-274GV, 20-274GW, 20-274GX, 20-274GY, 20-274GZ, 20-274HA, 20-274HB, 20-274HC, 20-274HD, 20-274HE, 20-274HF, 20-274HG, 20-274HH, 20-274HI, 20-274HJ, 20-274HK, 20-274HL, 20-274HM, 20-274HN, 20-274HO, 20-274HP, 20-274HQ, 20-274HR, 20-274HS, 20-274HT, 20-274HU, 20-274HV, 20-274HW, 20-274HX, 20-274HY, 20-274HZ, 20-274IA, 20-274IB, 20-274IC, 20-274ID, 20-274IE, 20-274IF, 20-274IG, 20-274IH, 20-274II, 20-274IJ, 20-274IK, 20-274IL, 20-274IM, 20-274IN, 20-274IO, 20-274IP, 20-274IQ, 20-274IR, 20-274IS, 20-274IT, 20-274IU, 20-274IV, 20-274IW, 20-274IX, 20-274IY, 20-274IZ, 20-274JA, 20-274JB, 20-274JC, 20-274JD, 20-274JE, 20-274JF, 20-274JG, 20-274JH, 20-274JI, 20-274JJ, 20-274JK, 20-274JL, 20-274JM, 20-274JN, 20-274JO, 20-274JP, 20-274JQ, 20-274JR, 20-274JS, 20-274JT, 20-274JU, 20-274JV, 20-274JW, 20-274JX, 20-274JY, 20-274JZ, 20-274KA, 20-274KB, 20-274KC, 20-274KD, 20-274KE, 20-274KF, 20-274KG, 20-274KH, 20-274KI, 20-274KJ, 20-274KL, 20-274KM, 20-274KN, 20-274KO, 20-274KP, 20-274KQ, 20-274KR, 20-274KS, 20-274KT, 20-274KU, 20-274KV, 20-274KW, 20-274KX, 20-274KY, 20-274KZ, 20-274LA, 20-274LB, 20-274LC, 20-274LD, 20-274LE, 20-274LF, 20-274LG, 20-274LH, 20-274LI, 20-274LJ, 20-274LK, 20-274LL, 20-274LM, 20-274LN, 20-274LO, 20-274LP, 20-274LQ, 20-274LR, 20-274LS, 20-274LT, 20-274LU, 20-274LV, 20-274LW, 20-274LX, 20-274LY, 20-274LZ, 20-274MA, 20-274MB, 20-274MC, 20-274MD, 20-274ME, 20-274MF, 20-274MG, 20-274MH, 20-274MI, 20-274MJ, 20-274MK, 20-274ML, 20-274MM, 20-274MN, 20-274MO, 20-274MP, 20-274MQ, 20-274MR, 20-274MS, 20-274MT, 20-274MU, 20-274MV, 20-274MW, 20-274MX, 20-274MY, 20-274MZ, 20-274NA, 20-274NB, 20-274NC, 20-274ND, 20-274NE, 20-274NF, 20-274NG, 20-274NH, 20-274NI, 20-274NJ, 20-274NK, 20-274NL, 20-274NM, 20-274NN, 20-274NO, 20-274NP, 20-274NQ, 20-274NR, 20-274NS, 20-274NT, 20-274NU, 20-274NV, 20-274NW, 20-274NX, 20-274NY, 20-274NZ, 20-274OA, 20-274OB, 20-274OC, 20-274OD, 20-274OE, 20-274OF, 20-274OG, 20-274OH, 20-274OI, 20-274OJ, 20-274OK, 20-274OL, 20-274OM, 20-274ON, 20-274OO, 20-274OP, 20-274OQ, 20-274OR, 20-274OS, 20-274OT, 20-274OU, 20-274OV, 20-274OW, 20-274OX, 20-274OY, 20-274OZ, 20-274PA, 20-274PB, 20-274PC, 20-274PD, 20-274PE, 20-274PF, 20-274PG, 20-274PH, 20-274PI, 20-274PJ, 20-274PK, 20-274PL, 20-274PM, 20-274PN, 20-274PO, 20-274PP, 20-274PQ, 20-274PR, 20-274PS, 20-274PT, 20-274PU, 20-274PV, 20-274PW, 20-274PX, 20-274PY, 20-274PZ, 20-274QA, 20-274QB, 20-274QC, 20-274QD, 20-274QE, 20-274QF, 20-274QG, 20-274QH, 20-274QI, 20-274QJ, 20-274QK, 20-274QL, 20-274QM, 20-274QN, 20-274QO, 20-274QP, 20-274QQ, 20-274QR, 20-274QS, 20-274QT, 20-274QU, 20-274QV, 20-274QW, 20-274QX, 20-274QY, 20-274QZ, 20-274RA, 20-274RB, 20-274RC, 20-274RD, 20-274RE, 20-274RF, 20-274RG, 20-274RH, 20-274RI, 20-274RJ, 20-274RK, 20-274RL, 20-274RM, 20-274RN, 20-274RO, 20-274RP, 20-274RQ, 20-274RR, 20-274RS, 20-274RT, 20-274RU, 20-274RV, 20-274RW, 20-274RX, 20-274RY, 20-274RZ, 20-274SA, 20-274SB, 20-274SC, 20-274SD, 20-274SE, 20-274SF, 20-274SG, 20-274SH, 20-274SI, 20-274SJ, 20-274SK, 20-274SL, 20-274SM, 20-274SN, 20-274SO, 20-274SP, 20-274SQ, 20-274SR, 20-274SS, 20-274ST, 20-274SU, 20-274SV, 20-274SW, 20-274SX, 20-274SY, 20-274SZ, 20-274TA, 20-274TB, 20-274TC, 20-274TD, 20-274TE, 20-274TF, 20-274TG, 20-274TH, 20-274TI, 20-274TJ, 20-274TK, 20-274TL, 20-274TM, 20-274TN, 20-274TO, 20-274TP, 20-274TQ, 20-274TR, 20-274TS, 20-274TT, 20-274TU, 20-274TV, 20-274TW, 20-274TX, 20-274TY, 20-274TZ, 20-274UA, 20-274UB, 20-274UC, 20-274UD, 20-274UE, 20-274UF, 20-274UG, 20-274UH, 20-274UI, 20-274UJ, 20-274UK, 20-274UL, 20-274UM, 20-274UN, 20-274UO, 20-274UP, 20-274UQ, 20-274UR, 20-274US, 20-274UT, 20-274UU, 20-274UV, 20-274UW, 20-274UX, 20-274UY, 20-274UZ, 20-274VA, 20-274VB, 20-274VC, 20-274VD, 20-274VE, 20-274VF, 20-274VG, 20-274VH, 20-274VI, 20-274VJ, 20-274VK, 20-274VL, 20-274VM, 20-274VN, 20-274VO, 20-274VP, 20-274VQ, 20-274VR, 20-274VS, 20-274VT, 20-274VU, 20-274VV, 20-274VW, 20-274VX, 20-274VY, 20-274VZ, 20-274WA, 20-274WB, 20-274WC, 20-274WD, 20-274WE, 20-274WF, 20-274WG, 20-274WH, 20-274WI, 20-274WJ, 20-274WK, 20-274WL, 20-274WM, 20-274WN, 20-274WO, 20-274WP, 20-274WQ, 20-274WR, 20-274WS, 20-274WT, 20-274WU, 20-274WV, 20-274WW, 20-274WX, 20-274WY, 20-274WZ, 20-274XA, 20-274XB, 20-274XC, 20-274XD, 20-274XE, 20-274XF, 20-274XG, 20-274XH, 20-274XI, 20-274XJ, 20-274XK, 20-274XL, 20-274XM, 20-274XN, 20-274XO, 20-274XP, 20-274XQ, 20-274XR, 20-274XS, 20-274XT, 20-274XU, 20-274XV, 20-274XW, 20-274XX, 20-274XY, 20-274XZ, 20-274YA, 20-274YB, 20-274YC, 20-274YD, 20-274YE, 20-274YF, 20-274YG, 20-274YH, 20-274YI, 20-274YJ, 20-274YK, 20-274YL, 20-274YM, 20-274YN, 20-274YO, 20-274YP, 20-274YQ, 20-274YR, 20-274YS, 20-274YT, 20-274YU, 20-274YV, 20-274YW, 20-274YX, 20-274YY, 20-274YZ, 20-274ZA, 20-274ZB, 20-274ZC, 20-274ZD, 20-274ZE, 20-274ZF, 20-274ZG, 20-274ZH, 20-274ZI, 20-274ZJ, 20-274ZK, 20-274ZL, 20-274ZM, 20-274ZN, 20-274ZO, 20-274ZP, 20-274ZQ, 20-274ZR, 20-274ZS, 20-274ZT, 20-274ZU, 20-274ZV, 20-274ZW, 20-274ZX, 20-274ZY, 20-274ZZ

REVISIONS: 1. REVISED PER MHMA EMAIL DATED MAY 17, 2023. 2. REVISED PER PENNING REVIEW LETTER DATED APRIL 21, 2023 AND MCP LETTER DATED APRIL 18, 2023. 3. REVISED PER PENNING REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN. 4. REVISED PER MCOO EMAIL DATED MARCH 2, 2023. 5. REVISED PER MCOO REVIEW LETTER DATED JUNE 29, 2022. 6. REVISED PER MCOO REVIEW LETTER DATED NOVEMBER 15, 2022. 7. REVISED PER MCOO REVIEW LETTER DATED SEPTEMBER 9, 2022. 8. REVISED PER MCOO REVIEW LETTER DATED JULY 28, 2022. 9. REVISED PER MCOO REVIEW LETTER DATED JUNE 29, 2022. 10. REVISED PER MCOO REVIEW LETTER DATED APRIL 14, 2022. 11. REVISED PER MCOO REVIEW LETTER DATED JANUARY 18, 2022. 12. REVISED PER MCOO REVIEW LETTER DATED OCTOBER 19, 2021. 13. REVISED PER MCOO REVIEW LETTER DATED NOVEMBER 5, 2021 AND MCOO REVIEW LETTER DATED OCTOBER 19, 2021.

REVISIONS: 1. REVISED PER MHMA EMAIL DATED MAY 17, 2023. 2. REVISED PER PENNING REVIEW LETTER DATED APRIL 21, 2023 AND MCP LETTER DATED APRIL 18, 2023. 3. REVISED PER PENNING REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN. 4. REVISED PER MCOO EMAIL DATED MARCH 2, 2023. 5. REVISED PER MCOO REVIEW LETTER DATED JUNE 29, 2022. 6. REVISED PER MCOO REVIEW LETTER DATED NOVEMBER 15, 2022. 7. REVISED PER MCOO REVIEW LETTER DATED SEPTEMBER 9, 2022. 8. REVISED PER MCOO REVIEW LETTER DATED JULY 28, 2022. 9. REVISED PER MCOO REVIEW LETTER DATED JUNE 29, 2022. 10. REVISED PER MCOO REVIEW LETTER DATED APRIL 14, 2022. 11. REVISED PER MCOO REVIEW LETTER DATED JANUARY 18, 2022. 12. REVISED PER MCOO REVIEW LETTER DATED OCTOBER 19, 2021. 13. REVISED PER MCOO REVIEW LETTER DATED NOVEMBER 5, 2021 AND MCOO REVIEW LETTER DATED OCTOBER 19, 2021.

REVISIONS: 1. REVISED PER MHMA EMAIL DATED MAY 17, 2023. 2. REVISED PER PENNING REVIEW LETTER DATED APRIL 21, 2023 AND MCP LETTER DATED APRIL 18, 2023. 3. REVISED PER PENNING REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN. 4. REVISED PER MCOO EMAIL DATED MARCH 2, 2023. 5. REVISED PER MCOO REVIEW LETTER DATED JUNE 29, 2022. 6. REVISED PER MCOO REVIEW LETTER DATED NOVEMBER 15, 2022. 7. REVISED PER MCOO REVIEW LETTER DATED SEPTEMBER 9, 2022. 8. REVISED PER MCOO REVIEW LETTER DATED JULY 28, 2022. 9. REVISED PER MCOO REVIEW LETTER DATED JUNE 29, 2022. 10. REVISED PER MCOO REVIEW LETTER DATED APRIL 14, 2022. 11. REVISED PER MCOO REVIEW LETTER DATED JANUARY 18, 2022. 12. REVISED PER MCOO REVIEW LETTER DATED OCTOBER 19, 2021. 13. REVISED PER MCOO REVIEW LETTER DATED NOVEMBER 5, 2021 AND MCOO REVIEW LETTER DATED OCTOBER 19, 2021.

REVISIONS: 1. REVISED PER MHMA EMAIL DATED MAY 17, 2023. 2. REVISED PER PENNING REVIEW LETTER DATED APRIL 21, 2023 AND MCP LETTER DATED APRIL 18, 2023. 3. REVISED PER PENNING REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN. 4. REVISED PER MCOO EMAIL DATED MARCH 2, 2023. 5. REVISED PER MCOO REVIEW LETTER DATED JUNE 29, 2022. 6. REVISED PER MCOO REVIEW LETTER DATED NOVEMBER 15, 2022. 7. REVISED PER MCOO REVIEW LETTER DATED SEPTEMBER 9, 2022. 8. REVISED PER MCOO REVIEW LETTER DATED JULY 28, 2022. 9. REVISED PER MCOO REVIEW LETTER DATED JUNE 29, 2022. 10. REVISED PER MCOO REVIEW LETTER DATED APRIL 14, 2022. 11. REVISED PER MCOO REVIEW LETTER DATED JANUARY 18, 2022. 12. REVISED PER MCOO REVIEW LETTER DATED OCTOBER 19, 2021. 13. REVISED PER MCOO REVIEW LETTER DATED NOVEMBER 5, 2021 AND MCOO REVIEW LETTER DATED OCTOBER 19, 2021.

CLIENT: R.B. ASHLEY CUSTOMS, LLC  
 1011 RIDGE ROAD  
 POTTSTOWN, PA 19465

SUBJECT: UTILITY DETAILS SHEET  
**KELLY ACRES**  
 DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA

PROJECT NO.: 20-374A  
 DWG. NO.: DE220374A  
 SHEET NO.: 4 OF 23


DESIGN: BDB  
 CHKD. BY: BDB

DRAWN BY: WJD  
 CHKD. BY: BDB


DATE: 2020-09-04  
 SCALE: 1" = 50'

1860 WEAVER TOWN ROAD, SUITE 100  
 DOUGLASSVILLE, PA 19518  
 PHONE: 610-688-8021  
 FAX: 610-688-4538


Boyer ENGINEERING LLC




PROFILE: PR. SANITARY SEWER MAIN  
SCALE: 1" = 50' (HORIZ.) 1" = 5' (VERT.)




PROFILE: Lot 1 Force Main  
SCALE: 1" = 50' (HORIZ.) 1" = 5' (VERT.)




PROFILE: Lot 2 Lateral  
SCALE: 1" = 50' (HORIZ.) 1" = 5' (VERT.)






PROFILE: Lot 3 Lateral  
SCALE: 1" = 50' (HORIZ.) 1" = 5' (VERT.)



PROFILE: Lot 4 Force Main  
SCALE: 1" = 50' (HORIZ.) 1" = 5' (VERT.)




PROFILE: Lot 5 Lateral  
SCALE: 1" = 50' (HORIZ.) 1" = 5' (VERT.)




CLIENT		SUBJECT	
R.B. ASHLEY CUSTOMS, LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465		SEWER PROFILE PLAN	
SEAL		KELLY ACRES	
DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA		PROJECT NO. 20-374A	
DESIGN BDB		CHKD. BY BDB	DWG. NO. PR120374A
DRAWN BY WJD		CHKD. BY	SHEET NO. 5 OF 23
DATE 2020-09-04	SCALE 1" = 50'		


NO.	REVISION	DATE	BY	APP.
13	REVISED PER PHVA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BDB
12	REVISED PER PENNING REVIEW LETTER DATED APRIL 21, 2023 AND MCPC LETTER DATED APRIL 18, 2023	2023-05-03	SSR	BDB
11	REVISED PER PENNING REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN	2023-03-07	SSR	BDB
10	REVISED PER MCOO EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BDB
9	REVISED PER MCOO REVIEW LETTER DATED JANUARY 19, 2023	2023-01-20	SSR	BDB
8	REVISED PER MCOO REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BDB
7	REVISED PER MCOO REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BDB
6	REVISED PER MCOO EMAIL DATED JULY 28, 2022	2022-07-29	JKL	BDB
5	REVISED PER MCOO REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	BDB
4	REVISED PER MCOO REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BDB
3	REVISED PER MCOO REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BDB
2	REVISED PER SIDE REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BDB
1	REVISED PER PENNING REVIEW LETTER DATED NOVEMBER 9, 2021 AND MCOO REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BDB




P:\PROJECTS\20-374A\_Roadside - Kelly Acres\Drawings\1210374A.dwg 18-May-23 09:24:18




**PROFILE: Lot 1 Water Service**  
SCALE: 1" = 50' (HORIZ.) 1" = 5' (VERT.)




**PROFILE: Lot 2 Water Service**  
SCALE: 1" = 50' (HORIZ.) 1" = 5' (VERT.)




**PROFILE: Lot 3 Water Service**  
SCALE: 1" = 50' (HORIZ.) 1" = 5' (VERT.)




**PROFILE: Lot 4 Water Service**  
SCALE: 1" = 50' (HORIZ.) 1" = 5' (VERT.)



**PROFILE: Lot 5 Water Service**  
SCALE: 1" = 50' (HORIZ.) 1" = 5' (VERT.)



**PROFILE: PR. STORM SEWER PIPE**  
SCALE: 1" = 50' (HORIZ.) 1" = 5' (VERT.)





CLIENT <b>R.B. ASHLEY CUSTOMS, LLC</b> 1011 RIDGE ROAD POTTSTOWN, PA 19465		SUBJECT WATER PROFILE PLAN  <b>KELLY ACRES</b>  DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA	
SEAL		PROJECT NO. <b>20-374A</b>	PROJECT NO. <b>20-374A</b>
		DWG. NO. <b>PR220374A</b>	DWG. NO. <b>PR220374A</b>
		SHEET NO. <b>6 OF 23</b>	SHEET NO. <b>6 OF 23</b>
DATE 2020-09-04	SCALE 1" = 50'		

NO.	REVISION	DATE	BY	APP.
13	REVISED PER BHMA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BDB
12	REVISED PER PENNING REVIEW LETTER DATED APRIL 21, 2023 AND MCPC LETTER DATED APRIL 18, 2023	2023-05-03	SSR	BDB
11	REVISED PER PENNING REVIEW LETTER DATED MARCH 9, 2023 AND FOR FINAL PLAN	2023-03-07	SSR	BDB
10	REVISED PER MCOD EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BDB
9	REVISED PER MCOD REVIEW LETTER DATED JANUARY 19, 2023	2023-01-20	SSR	BDB
8	REVISED PER MCOD REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BDB
7	REVISED PER MCOD REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BDB
6	REVISED PER MCOD EMAIL DATED JULY 28, 2022	2022-07-29	JLK	BDB
5	REVISED PER MCOD REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	BDB
4	REVISED PER MCOD REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BDB
3	REVISED PER MCOD REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BDB
2	REVISED PER SDC REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BDB
1	REVISED PER PENNING REVIEW LETTER DATED NOVEMBER 3, 2021 AND MCOD REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BDB

P:\PROJECTS\20-374A Review - Kelly Lot 1\Drawings\2023\11.dwg, 18-May-23 09:34:22

TREE#	COMMON NAME(SCIENTIFIC NAME)	DBH/CONDITION	INVASIVE	NATIVE(PA)	TO BE REMOVED	REPLACED
1	LITTLE LEAF LINDEN(TILIA CORDATA)	14	NO	NO	YES	NO
2	LITTLE LEAF LINDEN(TILIA CORDATA)	14	NO	NO	YES	NO
3	LITTLE LEAF LINDEN(TILIA CORDATA)	16	NO	NO	YES	NO
4	LITTLE LEAF LINDEN(TILIA CORDATA)	16	NO	NO	YES	NO
5	LITTLE LEAF LINDEN(TILIA CORDATA)	13	NO	NO	YES	NO
6	LITTLE LEAF LINDEN(TILIA CORDATA)	14	NO	NO	YES	NO
7	TULIP POPLE(LIRIODENDRON TULIPIFERA)	16	NO	YES	YES	YES
8	LITTLE LEAF LINDEN(TILIA CORDATA)	13	NO	NO	YES	NO
10	LITTLE LEAF LINDEN(TILIA CORDATA)	17	NO	NO	YES	NO
12	LITTLE LEAF LINDEN(TILIA CORDATA)	13	NO	NO	YES	NO
13	SILVER MAPLE(ACER SACCHARINUM)	12	NO	YES	YES	YES
14	LITTLE LEAF LINDEN(TILIA CORDATA)	20	NO	NO	YES	NO
15	LITTLE LEAF LINDEN(TILIA CORDATA)	13	NO	NO	YES	NO
16	LITTLE LEAF LINDEN(TILIA CORDATA)	15	NO	NO	YES	NO
17	LITTLE LEAF LINDEN(TILIA CORDATA)	12	NO	NO	YES	NO
18	LITTLE LEAF LINDEN(TILIA CORDATA)	15	NO	NO	YES	NO
19	LITTLE LEAF LINDEN(TILIA CORDATA)	13	NO	NO	YES	NO
20	LITTLE LEAF LINDEN(TILIA CORDATA)	17	NO	NO	YES	NO
21	LITTLE LEAF LINDEN(TILIA CORDATA)	13	NO	NO	YES	NO
22	LITTLE LEAF LINDEN(TILIA CORDATA)	12	NO	NO	YES	NO
23	LITTLE LEAF LINDEN(TILIA CORDATA)	13	NO	NO	YES	NO
24	LITTLE LEAF LINDEN(TILIA CORDATA)	13	NO	NO	YES	NO
25	LITTLE LEAF LINDEN(TILIA CORDATA)	12	NO	NO	YES	NO
26	LITTLE LEAF LINDEN(TILIA CORDATA)	12	NO	NO	YES	NO
27	LITTLE LEAF LINDEN(TILIA CORDATA)	12	NO	NO	YES	NO
29	LITTLE LEAF LINDEN(TILIA CORDATA)	13	NO	NO	YES	NO
30	LITTLE LEAF LINDEN(TILIA CORDATA)	12	NO	NO	YES	NO
31	LITTLE LEAF LINDEN(TILIA CORDATA)	13	NO	NO	YES	NO
32	NORWAY MAPLE (ACER PLATANOIDES)	13	YES	NO	YES	NO
33	SILVER MAPLE(ACER SACCHARINUM)	16	NO	YES	YES	YES
35	SILVER MAPLE(ACER SACCHARINUM)	17	NO	YES	YES	YES
36	SILVER MAPLE(ACER SACCHARINUM)	12X14X12	NO	YES	YES	YES
37	NORWAY MAPLE (ACER PLATANOIDES)	14	YES	NO	YES	NO
38	NORWAY MAPLE (ACER PLATANOIDES)	12	YES	NO	YES	NO
39	NORWAY MAPLE (ACER PLATANOIDES)	14	YES	NO	YES	NO
40	NORWAY MAPLE (ACER PLATANOIDES)	17	YES	NO	YES	NO
41	NORWAY MAPLE (ACER PLATANOIDES)	12	YES	NO	YES	NO
43	NORWAY MAPLE (ACER PLATANOIDES)	14	YES	NO	YES	NO
74	SCOTCH PINE(PINUS SYLVESTRIS)	12	NO	NO	NO	YES
75	SCOTCH PINE(PINUS SYLVESTRIS)	13	NO	NO	NO	YES
76	BLACK CHERRY (PRUNUS SEROTINA)	12	NO	NO	NO	YES
77	NORWAY SPRUCE(PICEA ABIES)	16	NO	NO	NO	NO
78	EASTERN WHITE PINE(PINUS STROBUS)	23	NO	NO	NO	YES
79	EASTERN WHITE PINE(PINUS STROBUS)	20	NO	YES	YES	YES*
80	EASTERN WHITE PINE(PINUS STROBUS)	15	NO	YES	YES	YES
81	EASTERN WHITE PINE(PINUS STROBUS)	18	NO	YES	YES	YES*
82	EASTERN WHITE PINE(PINUS STROBUS)	15	NO	YES	YES	YES
83	EASTERN WHITE PINE(PINUS STROBUS)	13	NO	YES	YES	YES
84	EASTERN WHITE PINE(PINUS STROBUS)	15	NO	YES	YES	YES
85	EASTERN WHITE PINE(PINUS STROBUS)	15	NO	YES	YES	YES
87	EASTERN WHITE PINE(PINUS STROBUS)	15	NO	YES	YES	YES
88	EASTERN WHITE PINE(PINUS STROBUS)	17	NO	YES	YES	YES
89	EASTERN WHITE PINE(PINUS STROBUS)	18	NO	YES	YES	YES
90	EASTERN WHITE PINE(PINUS STROBUS)	18	NO	YES	YES	YES
91	EASTERN WHITE PINE(PINUS STROBUS)	17	NO	YES	YES	YES
92	EASTERN WHITE PINE(PINUS STROBUS)	15	NO	YES	YES	YES
93	EASTERN WHITE PINE(PINUS STROBUS)	18	NO	YES	YES	YES*
94	EASTERN WHITE PINE(PINUS STROBUS)	18	NO	YES	YES	YES*
95	EASTERN WHITE PINE(PINUS STROBUS)	16	NO	YES	YES	YES
96	EASTERN WHITE PINE(PINUS STROBUS)	16	NO	YES	YES	YES
97	EASTERN WHITE PINE(PINUS STROBUS)	20	NO	YES	YES	YES*
98	EASTERN WHITE PINE(PINUS STROBUS)	19	NO	YES	YES	YES*
99	EASTERN WHITE PINE(PINUS STROBUS)	20	NO	YES	YES	YES*
100	EASTERN WHITE PINE(PINUS STROBUS)	20	NO	YES	YES	YES*
101	EASTERN WHITE PINE(PINUS STROBUS)	19	NO	YES	YES	YES*
102	EASTERN WHITE PINE(PINUS STROBUS)	22	NO	YES	YES	YES*
103	EASTERN WHITE PINE(PINUS STROBUS)	15	NO	YES	YES	YES
104	EASTERN WHITE PINE(PINUS STROBUS)	15	NO	YES	YES	YES
105	EASTERN WHITE PINE(PINUS STROBUS)	19	NO	YES	YES	YES*
109	NORWAY SPRUCE(PICEA ABIES)	13	NO	NO	YES	NO
110	KENTUCKY COFFEETREE(GYMNOCLADUS DIOICUS)	16	NO	NO	YES	NO
111	KENTUCKY COFFEETREE(GYMNOCLADUS DIOICUS)	12	NO	NO	YES	NO
112	KENTUCKY COFFEETREE(GYMNOCLADUS DIOICUS)	12	NO	NO	YES	NO
113	KENTUCKY COFFEETREE(GYMNOCLADUS DIOICUS)	12	NO	NO	YES	NO
115	KENTUCKY COFFEETREE(GYMNOCLADUS DIOICUS)	12	NO	NO	YES	NO
117	SILVER MAPLE(ACER SACCHARINUM)	16X6X6	NO	YES	YES	YES
119	PIN OAK(QUERCUS PALUSTRIS)	16	NO	YES	YES	YES
120	BLACK CHERRY (PRUNUS SEROTINA)	12X9X9	NO	YES	YES	YES
123	BLACK CHERRY (PRUNUS SEROTINA)	14(DYING)	NO	YES	YES	YES
124	GREEN ASH (FRAXINUM PENNSYLVANICA)	12(DYING)	NO	YES	YES	NO
125	BLACK CHERRY (PRUNUS SEROTINA)	11X13	NO	YES	YES	YES
126	KENTUCKY COFFEETREE(GYMNOCLADUS DIOICUS)	12	NO	NO	YES	NO
127	KENTUCKY COFFEETREE(GYMNOCLADUS DIOICUS)	13	NO	NO	YES	NO
129	SILVER MAPLE(ACER SACCHARINUM)	12X10X13	NO	YES	YES	YES
130	EASTERN BLACK WALNUT(JUGLANS NIGRA)	12	NO	YES	YES	YES
131	EASTERN BLACK WALNUT(JUGLANS NIGRA)	11	NO	YES	YES	NO
133	SCOTCH PINE(PINUS SYLVESTRIS)	14	NO	NO	YES	NO
135	LITTLE LEAF LINDEN(TILIA CORDATA)	11	NO	NO	YES	NO
136	EASTERN WHITE PINE(PINUS STROBUS)	16	NO	YES	YES	YES
138	EASTERN WHITE PINE(PINUS STROBUS)	12	NO	YES	YES	YES
139	EASTERN WHITE PINE(PINUS STROBUS)	16	NO	YES	YES	YES
140	EASTERN WHITE PINE(PINUS STROBUS)	19	NO	YES	YES	YES
141	EASTERN WHITE PINE(PINUS STROBUS)	13	NO	YES	YES	YES
142	EASTERN WHITE PINE(PINUS STROBUS)	13	NO	YES	YES	YES

OMMITTED TREE NUMBERS REPRESENT TREES LESS THAN 12" IN DIAMETER AND ARE NOT SHOWN.  
\*TREES REPLACED AT A 2:1 RATIO.




**LEGEND**

- EX. TRACT LINE
- EX. BOUNDARY
- EX. RIGHT-OF-WAY
- SETBACKS
- EX. SANITARY
- EX. WATER
- EX. MONUMENTATION
- EX. UTILITY POLE & GUY WIRE
- EX. OVERHEAD WIRES
- EX. SANITARY MANHOLE
- EX. FIRE HYDRANT
- EXISTING TREELINE
- EX. SOILS
- STEEL PIN (5/8" DIA., 24" LONG)
- EX. EASEMENT
- EX. CONTOURS
- EX. WELL
- EX. TRANSFORMER
- EX. TREE TO REMAIN >12"
- EX. NATIVE TREE TO REPLACE (12"-18")
- EX. NATIVE TREE TO REPLACE (18"+)
- EX. TREE TO REMOVE >12"

CLIENT	R.B. ASHLEY CUSTOMS, LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465	SUBJECT	EXISTING FEATURES/ENVIRONMENTAL RESOURCES PLAN  <b>KELLY ACRES</b>  DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA	
SEAL		PROJECT NO.	20-374A	
DESIGN		BOB	CHKD. BY	BOB
DRAWN BY		WJD	CHKD. BY	BOB
DATE	2020-09-04	SCALE	1"=40'	
			DWG. NO.	EX120374A
			SHEET NO.	7 OF 23


NO.	REVISION	DATE	BY	APP.
13	REVISED PER BHMA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BOB
12	REVISED PER PENNDOT REVIEW LETTER DATED APRIL 21, 2023 AND MCPC LETTER DATED APRIL 18, 2023	2023-05-03	SSR	BOB
11	REVISED PER PENNDOT REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN	2023-03-07	SSR	BOB
10	REVISED PER MCOD EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BOB
9	REVISED PER MCOD REVIEW LETTER DATED JANUARY 18, 2023	2023-01-20	SSR	BOB
8	REVISED PER MCOD REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BOB
7	REVISED PER MCOD REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BOB
6	REVISED PER MCOD EMAIL DATED JULY 28, 2022	2022-07-29	JLK	BOB
5	REVISED PER MCOD REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	BOB
4	REVISED PER MCOD REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BOB
3	REVISED PER MCOD REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BOB
2	REVISED PER SDC REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BOB
1	REVISED PER PENNDOT REVIEW LETTER DATED NOVEMBER 3, 2021 AND MCOD REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BOB

P:\PROJECTS\20-374A\_Kelly Acres - R.B. Ashley\2023\10-23-23.dwg, 18-May-23 09:34:24



**LEGEND**



- EX. TRACT LINE
- EX. BOUNDARY
- EX. RIGHT-OF-WAY
- SETBACKS
- EX. STORMWATER PIPE
- EX. SANITARY
- EX. WATER
- EX. MONUMENTATION
- EX. UTILITY POLE & GUY WIRE
- EX. OVERHEAD WIRES
- EX. SANITARY MANHOLE
- EX. FIRE HYDRANT
- EXISTING TREELINE
- EX. SOILS
- STEEL PIN (5/8\"/>



CLIENT	R.B. ASHLEY CUSTOMS, LLC 1011 RIDGE ROAD POITSTOWN, PA 19465	
	SUBJECT EXISTING FEATURES/ENVIRONMENTAL RESOURCES PLAN AERIAL PLAN	
SEAL	KELLY ACRES DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA	
	PROJECT NO. 20-374A	DWG. NO. EX220374A
DESIGN	CHKD. BY	SHEET NO.
BDB	BDB	8 OF 23
DRAWN BY	CHKD. BY	DATE
WJD		2020-09-04
DATE	SCALE	
	1"=40'	

NO.	REVISION	DATE	BY	APP.
13.	REVISED PER IBMA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	808
12.	REVISED PER PENNING REVIEW LETTER DATED APRIL 21, 2023 AND MCPC LETTER DATED APRIL 18, 2023	2023-05-03	SSR	808
11.	REVISED PER PENNING REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN	2023-03-07	SSR	808
10.	REVISED PER MCOD EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	808
9.	REVISED PER MCOD REVIEW LETTER DATED JANUARY 19, 2023	2023-01-20	SSR	808
8.	REVISED PER MCOD REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	808
7.	REVISED PER MCOD REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	808
6.	REVISED PER MCOD EMAIL DATED JULY 28, 2022	2022-07-29	JJK	808
5.	REVISED PER MCOD REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	808
4.	REVISED PER MCOD REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	808
3.	REVISED PER MCOD REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	808
2.	REVISED PER SDE REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	808
1.	REVISED PER PENNING REVIEW LETTER DATED NOVEMBER 9, 2021 AND MCOD REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	808


PROJECT: 20-374A, Revision - Kelly Ashley Customs, LLC, 1011 Ridge Road, Pottstown, PA 19465, 18-Aug-23 09:34:27



**LEGEND**

- EX. TRACT LINE
- EX. BOUNDARY
- EX. RIGHT-OF-WAY
- SETBACKS
- EX. STORMWATER PIPE
- EX. SANITARY
- EX. WATERLINE
- EX. MONUMENTATION
- EX. UTILITY POLE & GUY WIRE
- EX. OVERHEAD WIRES
- EX. SANITARY MANHOLE
- EX. FIRE HYDRANT
- EX. TREELINE
- EX. SOILS
- EX. CONTOURS
- PR. CONTOURS
- INFILTRATION TEST PIT
- PR. EDGE OF PAVING
- PR. BUILDING
- PR. WATER SERVICE
- PR. SEWER LATERAL
- PR. FORCE MAIN
- PR. SANITARY SEWER
- PR. STORMWATER PIPE
- PR. ROOF DRAINS
- PR. UNDERGROUND UTILITY
- PR. OVERHEAD UTILITY
- PR. TREELINE
- PR. SPILLWAY/CHANNEL LINING
- PR. RIP RAP
- PR. SEWER MANHOLE
- PR. SEWER CLEANOUT
- PR. SEWER SHUTOFF
- PR. WATER VALVE
- PR. TREES
- PR. COMPOST FILTER SOCK
- PR. PROTECTION FENCE
- PR. SEDIMENT TRAP BAFFLE
- PR. LIMIT OF DISTURBANCE
- NPDES BOUNDARY
- WATERSHED
- CONCRETE WASHOUT
- TOPSOIL STOCKPILE
- ROCK CONSTRUCTION ENTRANCE
- AMENDED SOILS

LIMIT OF DISTURBANCE 4.23 ACRES





SOILS TABLE	
SYMBOL	NAME/DESC
PeB	PENN SILT LOAM, 3 TO 8 PERCENT SLOPES
KiB	KILNESVILLE CHANNELRY SILT LOAM, 3 TO 8 PERCENT SLOPES

NO.	REVISION	DATE	BY	APP.
13.	REVISED PER DIMA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BOB
12.	REVISED PER PENNOM REVIEW LETTER DATED APRIL 21, 2023 AND MCOE LETTER DATED APRIL 18, 2023	2023-05-03	SSR	BOB
11.	REVISED PER PENNOM REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN	2023-03-07	SSR	BOB
10.	REVISED PER MCOE EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BOB
9.	REVISED PER MCOE REVIEW LETTER DATED JANUARY 18, 2023	2023-01-20	SSR	BOB
8.	REVISED PER MCOE REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BOB
7.	REVISED PER MCOE REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BOB
6.	REVISED PER MCOE EMAIL DATED JULY 28, 2022	2022-07-29	JK	BOB
5.	REVISED PER MCOE REVIEW LETTER DATED JUNE 29, 2022	2022-09-30	SSR	BOB
4.	REVISED PER MCOE REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BOB
3.	REVISED PER MCOE REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BOB
2.	REVISED PER MCOE REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BOB
1.	REVISED PER PENNOM REVIEW LETTER DATED NOVEMBER 5, 2021 AND MCOE REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BOB

CLIENT	R.B. ASHLEY CUSTOMS, LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465	SUBJECT	EROSION AND SEDIMENTATION CONTROL PLAN  <b>KELLY ACRES</b>  DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA
SEAL		PROJECT NO.	20-374A
		DWG. NO.	ES120374A
		SHEET NO.	9 OF 23
	DATE	SCALE	2020-09-04 1"=40'

PROJECT NO. 20-374A, Rev. 04  
 18-May-23 09:24:30  
 K. Kelly, L.A. Kelly, T. Kelly, J. Kelly, S. Kelly, M. Kelly, R. Kelly, D. Kelly, B. Kelly, C. Kelly, E. Kelly, F. Kelly, G. Kelly, H. Kelly, I. Kelly, J. Kelly, K. Kelly, L. Kelly, M. Kelly, N. Kelly, O. Kelly, P. Kelly, Q. Kelly, R. Kelly, S. Kelly, T. Kelly, U. Kelly, V. Kelly, W. Kelly, X. Kelly, Y. Kelly, Z. Kelly





**LEGEND**

EX. TRACT LINE	---
EX. BOUNDARY	---
EX. RIGHT-OF-WAY	---
EX. SETBACKS	---
EX. STORMWATER PIPE	---
EX. SANITARY	---
EX. WATERLINE	---
EX. MONUMENTATION	---
EX. UTILITY POLE & GUY WIRE	---
EX. OVERHEAD WIRES	---
EX. SANITARY MANHOLE	---
EX. FIRE HYDRANT	---
EX. TREELINE	---
EX. SOILS	---
EX. CONTOURS	---
PR. CONTOURS	---
INFILTRATION TEST PIT	---
PR. EDGE OF PAVING	---
PR. BUILDING	---
PR. WATER SERVICE	---
PR. SEWER LATERAL	---
PR. FORCE MAIN	---
PR. SANITARY SEWER	---
PR. STORMWATER PIPE	---
PR. ROOF DRAINS	---
PR. UNDERGROUND UTILITY	---
PR. OVERHEAD UTILITY	---
PR. TREELINE	---
PR. SPILLWAY/CHANNEL LINING	---
PR. RIP RAP	---
PR. SEWER MANHOLE	---
PR. SEWER CLEANOUT	---
PR. SEWER SHUTOFF	---
PR. WATER VALVE	---
PR. TREES	---
PR. COMPOST FILTER SOCK	---
PR. PROTECTION FENCE	---
PR. SEDIMENT TRAP BAFFLE	---
PR. LIMIT OF DISTURBANCE	---
NPDES BOUNDARY	---
WATERSHED	---
CONCRETE WASHOUT	---
TOPSOIL STOCKPILE	---
ROCK CONSTRUCTION ENTRANCE	---
AMENDED SOILS	---



CLIENT	R.B. ASHLEY CUSTOMS, LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465	SUBJECT	EROSION AND SEDIMENTATION CONTROL DRAINAGE AREA PLAN  <b>KELLY ACRES</b>  DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA
SEAL		PROJECT NO.	20-374A
DESIGN		CHKD. BY	ES220374A
DRAWN BY		CHKD. BY	SHEET NO.
DATE	2020-09-04	SCALE	1"=40'

NO.	REVISION	DATE	BY	APP.
13	REVISED PER BMAA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BBB
12	REVISED PER PENNSION REVIEW LETTER DATED APRIL 21, 2023 AND MCEP LETTER DATED APRIL 18, 2023	2023-05-03	SSR	BBB
11	REVISED PER PENNSION REVIEW LETTER DATED MARCH 9, 2023 AND FOR FINAL PLAN	2023-03-07	SSR	BBB
10	REVISED PER MCOO EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BBB
9	REVISED PER MCOO REVIEW LETTER DATED JANUARY 19, 2023	2023-01-20	SSR	BBB
8	REVISED PER MCOO REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BBB
7	REVISED PER MCOO REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BBB
6	REVISED PER MCOO EMAIL DATED JULY 28, 2022	2022-07-29	JLK	BBB
5	REVISED PER MCOO REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	BBB
4	REVISED PER MCOO REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BBB
3	REVISED PER MCOO REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BBB
2	REVISED PER SIDE REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BBB
1	REVISED PER PENNSION REVIEW LETTER DATED NOVEMBER 5, 2021 AND MCOO REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BBB



P:\PROJECTS\20-374A\_Roads - Kelly LA\Drawings\2023\10-23-23.dwg, 18-Aug-23 09:24:34  
 BOYER ENGINEERING LLC  
 1860 WEAVER TOWN ROAD, SUITE 100  
 DOUGLASSVILLE, PA 19518  
 PHONE: 610-689-8021  
 FAX: 610-689-4538





**STANDARD CONSTRUCTION DETAIL #3-1  
ALTERNATIVE ROCK CONSTRUCTION ENTRANCE**  
NOT TO SCALE




**STANDARD CONSTRUCTION DETAIL #3-16  
PUMPED WATER FILTER BAG**  
NOT TO SCALE



**STANDARD CONSTRUCTION DETAIL #11-1  
EROSION CONTROL BLANKET INSTALLATION**  
NOT TO SCALE




**STANDARD CONSTRUCTION DETAIL #11-1  
EROSION CONTROL BLANKET INSTALLATION**  
NOT TO SCALE



Basin or Trap No.	Baffle Length (ft)	Baffle Height (ft)	Temporary Riser Crest Elev. (ft)	Bottom Elev. (ft)
1	9.3	2	355.75	353.75

**NOTES:**  
SEE APPROPRIATE BASIN DETAIL FOR PROPER LOCATION AND ORIENTATION.  
AN ACCEPTABLE ALTERNATIVE IS TO INSTALL A SUPER SILT FENCE AT THE BAFFLE LOCATION  
IN POOLS WITH DEPTHS EXCEEDING 7', THE TOP OF THE PLYWOOD BAFFLE DOES NOT NEED TO EXTEND TO THE TEMPORARY RISER CREST. SUPER SILT FENCE BAFFLES NEED NOT EXTEND TO TRICE ELEVATION.  
BAFFLES SHALL BE TIED INTO ONE SIDE OF THE BASIN UNLESS OTHERWISE SHOWN ON THE PLAN DRAWINGS.  
SUBSTITUTION OF MATERIALS NOT SPECIFIED IN THIS DETAIL SHALL BE APPROVED BY THE DEPARTMENT OR THE LOCAL CONSERVATION DISTRICT BEFORE INSTALLATION.  
DAMAGED OR WARPED BAFFLES SHALL BE REPLACED WITHIN 7 DAYS OF INSPECTION.  
BAFFLES REQUIRING SUPPORT POSTS SHALL NOT BE INSTALLED IN BASINS REQUIRING IMPERVIOUS LINERS.



**STANDARD CONSTRUCTION DETAIL #7-14  
BAFFLE**  
NOT TO SCALE



Trap No.	Z1 (ft)	Z2 (ft)	H (ft)	h (ft)	EMBANK TOP ELEV. (FT)	SPILLWAY CREST ELEV. (FT)	CLEAN OUT ELEV. (FT)	BOTTOM ELEV. (FT)	SPILLWAY WIDTH (FT)
1	3	3	3	1	356.75	355.75	354.75	353.75	10
2	3	3	3	1	358.75	357.75	356.75	355.75	10
3	3	3	3	1	367.25	367.25	366.25	359.25	10



**NOTES:**  
EMBANKMENT OUTLET SHALL BE COMPOSED ENTIRELY OF ROCK ABOVE CLEAN OUT ELEVATION (COE); MAIN BODY R-3 OR LARGER - R-4 TO BE USED FOR DRAINAGE AREAS GREATER THAN 3.0 ACRES. INSIDE FACE AASHTO # 57 STONE OR SMALLER, A 6 IN. THICK LAYER OF COMPOST, COMPOST SOCK, OR CLEAN SAND SHALL BE INSTALLED ON TOP OF THE AASHTO #57 STONE AND SECURELY ANCHORED IN HQ WATERSHEDS. 24 IN. DIAMETER COMPOST SOCK(S) SHALL BE USED IN PLACE OF FILTER FABRIC AND AASHTO #57 STONE IN ELY WATERSHEDS.  
FILL MATERIAL FOR THE EMBANKMENTS SHALL BE FREE OF ROOTS, OR OTHER WOODY VEGETATION, ORGANIC MATERIAL, LARGE STONES, AND OTHER OBJECTIONABLE MATERIALS. THE EMBANKMENT SHALL BE COMPACTED IN LAYERED LIFTS OF NOT MORE THAN 9 IN. THE MAXIMUM ROCK SIZE SHALL BE NO GREATER THAN 6 IN.  
UPON COMPLETION, THE EMBANKMENT SHALL BE SEEDED AND MULCHED OR OTHERWISE STABILIZED ACCORDING TO THE SPECIFICATIONS OF THE E&S PLAN DRAWINGS.  
ALL SEDIMENT TRAPS SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RUNOFF EVENT.  
ACCESS FOR SEDIMENT REMOVAL AND OTHER REQUIRED MAINTENANCE ACTIVITIES SHALL BE PROVIDED.  
A CLEAN OUT STAKE SHALL BE PLACED NEAR THE CENTER OF EACH TRAP. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT HAS REACHED THE CLEAN OUT ELEVATION ON THE STAKE AND THE TRAP RESTORED TO ITS ORIGINAL DIMENSIONS. DISPOSE OF MATERIALS REMOVED FROM THE TRAP IN THE MANNER DESCRIBED IN THE E&S PLAN.  
CHECK EMBANKMENTS, SPILLWAYS, AND OUTLETS FOR EROSION, PIPING AND SETTLEMENT. CLOGGED OR DAMAGED SPILLWAYS AND/OR EMBANKMENTS SHALL BE IMMEDIATELY RESTORED TO THE DESIGN SPECIFICATIONS.  
DISPLACED RIPRAP WITHIN THE SPILLWAY OR OUTLET PROTECTION SHALL BE REPLACED IMMEDIATELY.  
ACCUMULATED SEDIMENT SHALL BE REMOVED AND DISTURBED AREAS INSIDE THE TRAP SHALL BE STABILIZED BEFORE CONNECTION TO A STORMWATER MANAGEMENT FACILITY. TO ASSIST IN REMOVING SEDIMENT WHICH MAY BE SATURATED, A DEVICE SUCH AS IS SHOWN IN STANDARD CONSTRUCTION DETAIL #7-18 MAY BE USED TO DEWATER THE SEDIMENT PRIOR TO ITS REMOVAL.

**STANDARD CONSTRUCTION DETAIL #7-17  
EMBANKMENT SEDIMENT TRAP**  
NOT TO SCALE



**NOTES:**  
A CONCRETE CRADLE MAY BE USED IN CONJUNCTION WITH ANTI-SEEP COLLARS AND/OR FILTER DIAPHRAGM.  
ANTI-SEEP COLLAR NUMBER, SIZE AND SPACING SHALL BE AS SHOWN ELSEWHERE IN PLAN.  
FILTER DIAPHRAGM LOCATION (L4) SHALL BE AS SHOWN IN FIGURE 7.8 OF THE PA DEP EROSION CONTROL MANUAL.


**STANDARD CONSTRUCTION DETAIL #7-17  
CONCRETE CRADLE FOR BASIN OR TRAP OUTLET BARREL**  
NOT TO SCALE




**NOTES:**  
1. SPREADER IS TO BE 30' IN LENGTH.  
2. OUTLET PIPE IS TO BE TERMINATED IN "TEE" COUPLING.  
3. YARD DRAIN BASINS OR INLINE COUPLINGS SHALL BE USED WITH SURFACE GRATES AT EACH OF THE PERFORATED PIPE TO THE SURFACE.

BMP	A	B
RAIN GARDEN 3	354.00	352.00
RAIN GARDEN 4	357.00	355.00
RAIN GARDEN 5	365.00	363.00


**LEVEL SPREADER DETAIL (LS3, LS4, LS5)**  
NOT TO SCALE




**STANDARD CONSTRUCTION DETAIL #7-14  
BAFFLE**  
NOT TO SCALE



**STANDARD CONSTRUCTION DETAIL #7-17  
EMBANKMENT SEDIMENT TRAP**  
NOT TO SCALE



**STANDARD CONSTRUCTION DETAIL #7-17  
EMBANKMENT SEDIMENT TRAP**  
NOT TO SCALE



**STANDARD CONSTRUCTION DETAIL #7-17  
EMBANKMENT SEDIMENT TRAP**  
NOT TO SCALE

**CONCRETE WASHOUT**  
383-2134-008 / March 31, 2012 / Page 58

**TOPSOIL STOCKPILE DETAIL**  
N.T.S.

**TOPSOIL STOCKPILE DETAIL**  
N.T.S.

**TOPSOIL STOCKPILE DETAIL**  
N.T.S.

**ROLLMAX**  
ROLLED EROSION CONTROL

**EroNet™ P300® Permanent Erosion Control Blanket**

**DESCRIPTION**  
The permanent erosion control blanket shall be a machine-produced mat of 100% UV stable polypropylene fiber. The matting shall be of consistent thickness with the synthetic fibers evenly distributed over the entire area of the mat. The matting shall be covered on the top side with black heavyweight UV stabilized polypropylene matting having ultraviolet additives to delay breakdown and an approximate 0.50 x 0.50 inch (1.27 x 1.27 cm) mesh. The bottom mat shall also be UV-stabilized polypropylene with a 0.83 x 0.83 inch (2.13 x 2.13 cm) mesh size. The blanket shall be woven together on 1.5 inch (3.81 cm) centers with non-degradable thread. All mats shall be manufactured with a colored thread stitched along both outer edges as an overlap guide for adjacent mats. The P300 shall meet Type SA, LS, specifications requirements established by the Erosion Control Technology Council (ECTC) and Federal Highway Administration's (FHWA) PFP-03 Section 713.18.

**INDEX PROPERTY**

Index Property	Test Method	Typical
Thickness	ASTM D6625	0.47 in. (12.0 mm)
Resiliency	ASTM D6624	91.5%
Density	ASTM D792	0.96 g/cm <sup>3</sup>
Mass/Unit Area	ASTM D556	12.02 oz/yd <sup>2</sup> (64.8 g/m <sup>2</sup> )
UV Stability	ASTM D4855	90%
UV Stability	ISO 100	95.88%
Porosity	ECTC Guidelines	12.9%
Stiffness	ASTM D1938	4.88 lb/ft (0.02278 mg/cm)
Light Penetration	ASTM D6627	0.5%
Tensile Strength - MD	ASTM D6876	4.88 lb/ft (6.49 kN/m)
Elongation - MD	ASTM D6876	28.1%
Tensile Strength - TD	ASTM D6876	4.82 lb/ft (6.42 kN/m)
Elongation - TD	ASTM D6876	26.7%
Burnout Improvement	ASTM D7322	437%

**PERMISSIBLE STRESS**

Phase	Unvegetated	Partially Veg.	Fully Veg.
Short Duration	3.0 psf (144 Pa)	8.0 psf (383 Pa)	8.0 psf (383 Pa)
Long Duration	2.0 psf (95 Pa)	6.0 psf (283 Pa)	6.0 psf (283 Pa)

**PERMISSIBLE SLOPES**

Slope Length (L)	± 3%	3% - 21%	≥ 21%
≤ 20 ft (6 m)	0.003	0.029	0.082
20-50 ft	0.036	0.060	0.086
≥ 50 ft (15.2 m)	0.070	0.090	0.100

**Flow Depth**

Flow Depth	Maintenance
≤ 0.50 ft (0.15 m)	0.034
0.50 - 2.0 ft	0.034-0.020
≥ 2.0 ft (0.60 m)	0.020

**Manufacture:** 1500 E. Eisenhower Hwy, Harrisburg, PA 17125  
800-772-0400

**NORTH AMERICAN GREEN**

P:\PROJECTS\2012-2013\2012-09-24-383-2134-008.dwg 18-Aug-23 09:24:38

NO.	REVISION	DATE	BY	APP.
13	REVISED PER RWMA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BOB
12	REVISED PER PENNON REVIEW LETTER DATED APRIL 21, 2023 AND MCPC LETTER DATED APRIL 16, 2023	2023-05-03	SSR	BOB
11	REVISED PER PENNON REVIEW LETTER DATED MARCH 9, 2023 AND FOR FINAL PLAN	2023-03-07	SSR	BOB
10	REVISED PER MCPC EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BOB
9	REVISED PER MCPC REVIEW LETTER DATED JANUARY 19, 2023	2023-01-20	SSR	BOB
8	REVISED PER MCPC REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BOB
7	REVISED PER MCPC REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BOB
6	REVISED PER MCPC EMAIL DATED JULY 28, 2022	2022-07-29	JKL	BOB
5	REVISED PER MCPC REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	BOB
4	REVISED PER MCPC REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BOB
3	REVISED PER MCPC REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BOB
2	REVISED PER SDE REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BOB
1	REVISED PER PENNON REVIEW LETTER DATED NOVEMBER 3, 2021 AND MCPC REVIEW LETTER DATED OCTOBER 18, 2021	2021-12-11	SSR	BOB

CLIENT: R.B. ASHLEY CUSTOMS, LLC  
1011 RIDGE ROAD  
POTTSTOWN, PA 19465

SUBJECT: EROSION AND SEDIMENTATION CONTROL DETAILS

KELLY ACRES

DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA

PROJECT NO.: 20-374A


DWG. NO.: ES320374A

SHEET NO.: 11 OF 23

DATE: 2020-09-04

SCALE: NOT TO SCALE

SEAL: Boyer ENGINEERING LLC



**STANDARD WORKSHEET #1**  
Channel Design Data

PROJECT NAME: Kelly Acres  
LOCATION: Douglass Township, Montgomery County  
PREPARED BY: SSR DATE: 20-Jan-2023  
CHECKED BY: BOB

CHANNEL OR CHANNEL SECTION	Swale 1		Swale 2	
	TEMP	PERM	TEMP	PERM
Design Storm	N/A	N/A	N/A	N/A
Area	0.49	0.49	0.25	0.25
Multiplier (1.6, 2.25, or 7.75) <sup>1</sup>	1.60	2.75	1.60	2.75
Q (REQUIRED CAPACITY) CFS	0.78	1.35	0.40	0.69
Q (CALCULATED AT FLOW DEPTH @ CFS)	1.16	1.16	0.57	0.57
PROTECTIVE LINING <sup>2</sup>	575	GRASS	575	GRASS
MANNING'S COEFFICIENT <sup>3</sup>	0.013	0.080	0.036	0.080
V (ALLOWABLE VELOCITY) FPS	1.00	3.00	3.00	3.00
V (CALCULATED AT FLOW DEPTH @ FPS)	1.85	1.72	1.59	1.57
T <sub>1</sub> (MAX ALLOWABLE SHEAR STRESS LB/FT <sup>2</sup> )	2.00	2.00	2.00	2.00
T <sub>2</sub> (CALCD SHEAR STRESS AT FLOW DEPTH @ LB/FT <sup>2</sup> )	0.56	0.94	0.40	0.62
CHANNEL BOTTOM WIDTH (FT)	2.00	2.00	1.25	1.25
CHANNEL SIDE SLOPES (H:V)	2:00	2:00	2:00	2:00
D (TOTAL DEPTH) FT	2.00	2.00	2.00	2.00
CHANNEL TOP WIDTH @ D (FT)	10.00	10.00	9.25	9.25
W (CALCULATED FLOW DEPTH) FT	0.18	0.30	0.16	0.25
CHANNEL TOP WIDTH @ FLOW DEPTH FT	2.72	3.20	1.89	2.25
BOTTOM WIDTH @ FLOW DEPTH (FT)	11.13	0.67	7.81	3.00
BOTTOM WIDTH @ FLOW DEPTH RATED (12.1 MAX)	N/A	N/A	N/A	N/A
Q <sub>5</sub> STONE SIZE (IN)	N/A	N/A	N/A	N/A
A (CROSS-SECTIONAL AREA IN SQ. FT.)	0.42	0.78	0.25	0.44
R (HYDRAULIC RADIUS)	0.15	0.23	0.13	0.18
S (BED SLOPE) (FT/FT)	0.05	0.05	0.04	0.04
S (CRITICAL SLOPE)	0.03	0.16	0.04	0.17
D <sub>50</sub>	0.02	0.11	0.03	0.12
L <sub>50</sub>	0.08	0.21	0.05	0.22
STABLE FLOW? (Y/N)	YES	YES	YES	YES
FREE BOARD BASED ON UNSTABLE FLOW FT	N/A	N/A	N/A	N/A
FREE BOARD BASED ON STABLE FLOW FT	1.92	1.70	1.84	1.75
MINIMUM REQUIRED FREEBOARD FT <sup>4</sup>	0.50	0.50	0.50	0.50
DESIGN METHOD FOR PROTECTIVE LINING <sup>5</sup> PERMISSIBLE VELOCITY (LV) OR SHEAR STRESS (S)	V	V	V	V

\* SEE MANUFACTURER'S LINING INSTALLATION DETAIL FOR STAPLE PATTERNS, VEGETATIVE STABILIZATION FOR SOIL AMENDMENTS, SEED MIXTURES AND MULCHING INFORMATION

CHANNEL NO.	STATIONS	BOTTOM WIDTH B (FT)	DEPTH D (FT)	TOP WIDTH W (FT)	Z1 (FT)	Z2 (FT)	LINING *
1	N/A	2	2	10	2	2	N.A.G. 575
2	N/A	1.25	2	9.25	2	2	N.A.G. 575

ANCHOR TRENCHES SHALL BE INSTALLED AT BEGINNING AND END OF CHANNEL IN THE SAME MANNER AS LONGITUDINAL ANCHOR TRENCHES.

CHANNEL DIMENSIONS SHALL BE CONSTANTLY MAINTAINED. CHANNEL SHALL BE CLEANED WHENEVER TOTAL CHANNEL DEPTH IS REDUCED BY 25% AT ANY LOCATION.

SEDIMENT DEPOSITS SHALL BE REMOVED WITHIN 24 HOURS OF DISCOVERY OR AS SOON AS SOIL CONDITIONS PERMIT ACCESS TO CHANNEL WITHOUT FURTHER DAMAGE. DAMAGED LINING SHALL BE REPAIRED OR REPLACED WITHIN 48 HOURS OF DISCOVERY.


NO MORE THAN ONE THIRD OF THE SHOOT (GRASS LEAF) SHALL BE REMOVED IN ANY MOWING. GRASS HEIGHT SHALL BE MAINTAINED BETWEEN 2 AND 3 INCHES UNLESS OTHERWISE SPECIFIED. EXCESS VEGETATION SHALL BE REMOVED FROM PERMANENT CHANNELS TO ENSURE SUFFICIENT CHANNEL CAPACITY.

**STANDARD CONSTRUCTION DETAIL #6-1**  
VEGETATED CHANNEL

NOT TO SCALE

**STANDARD WORKSHEET #1**  
Compost Filter Socks

PROJECT NAME: Kelly Acres  
LOCATION: Douglass Township, Montgomery County  
PREPARED BY: SSR DATE: 6-Dec-2022  
CHECKED BY: BOB



SOCK NO.	Dia. In.	LOCATION	SLOPE PERCENT	SLOPE LENGTH ABOVE BARRIER (FT)
1	24	Northeast of Sediment Trap 1	3	650
2	12	East of Proposed Dwelling on Lot 2	2.1	140
3	12	Southwest of Rain Garden 5	2.4	167
4	12	South of Rain Garden 5	1.8	219
5	12	East of Rain Garden 5	1.9	214
6	24	North of Sediment Trap 2	3	390
7	24	Northeast of Sediment Trap 2	3	390
8	12	East of Proposed Driveway on Lot 4	4	50
9	18	East of Proposed Driveway on Lot 4	4.2	286
10	24	North of Sediment Trap 3	3	395
11	24	Northeast of Sediment Trap 3	3	395
12	18	Southwest of Proposed Dwelling on Lot 5	2.2	368
13	12	Northeast of Proposed Driveway on Lot 5	3.7	54
14	12	South of Proposed Driveway on Lot 5	3.3	60
15	18	Southwest of Proposed Dwelling on Lot 5	3.3	239
16	12	Northeast of Proposed Dwelling on Lot 5	4	50
17	12	Northwest of Dwelling on Lot 5	4	50
18	12	Northwest of Rain Garden 2	1.5	325
19	18	Downslope from Topsoil Stockpile on Lot 2	1.6	250
20	18	Downslope from Topsoil Stockpile on Lot 3	2.2	360
21	18	Downslope from Topsoil Stockpile on Lot 5	4.2	240
22	18	Downslope from Topsoil Stockpile on Lot 4	4.7	190
23	18	Downslope from Topsoil Stockpile on Lot 1	1.2	325

**STANDARD CONSTRUCTION DETAIL #4-1**  
COMPOST FILTER SOCK

NOT TO SCALE

**ROLLMAX™**  
ROLLED EROSION CONTROL

Specification Sheet  
**EroNet® 575° Erosion Control Blanket**

**DESCRIPTION**  
This short length single layer erosion control blanket shall be a machine produced mat of 100% agricultural straw with a functional longevity of up to 12 months. (NOTE: functional longevity may vary depending upon climatic conditions, soil, geographical location, and elevation.) The blanket shall be of consistent thickness with the straw evenly distributed over the entire area of the mat. The blanket shall be covered on the top side with a lightweight photodegradable polypropylene netting having an approximate 5.0 x 0.50 in. (1.27 x 1.27 cm) mesh. The blanket shall be sewn together on 1.50 inch (3.81 cm) centers with degradable thread. The blanket shall be manufactured with a colored thread stitched along both outer edges approx. 2-3 inches (5-7.62 cm) from the edges as an overlap guide for adjacent mats.

The 575 shall meet Type 2 specification requirements established by the Erosion Control Technology Council (ECTC) and Federal Highway Administration's (FHWA) FP-33 Section 713.7.

Material Content	Weight	Volume
Matrix	100% Straw Fiber	0.5 lbs/sq yd (0.37 kg/m²)
Netting	Top side only, lightweight polypropylene	1.5 lb/1000 sq ft (0.73 kg/100 sq m)
Thread	Dependable	


Design Permissible Shear Stress	Unvegetated Shear Stress
Unvegetated Shear Stress	1.55 psf (0.04 Pa)
Unvegetated Velocity	5.00 fps (1.52 m/s)

Slope Design Data - Factor	Slope Gradient (S)
Slope Length (L)	3:1 - 31:1
≤ 20 ft (6 m)	0.029 N/A N/A
20-50 ft	0.31 N/A N/A
≥ 50 ft (15.2 m)	0.19 N/A N/A

Flow Depth	Manning's n
≤ 0.50 ft (0.15 m)	0.055
0.50 - 2.0 ft	0.055-0.021
≥ 2.0 ft (0.60 m)	0.021

**NORTH AMERICAN GREEN**

NOT TO SCALE



**STANDARD CONSTRUCTION DETAIL #4-6**  
ROCK FILTER OUTLET

NOT TO SCALE


ROCK FILTER NO.	LOCATION	D (FT)	RIPRAP SIZE (IN.)	APRON WIDTH AW (FT)	TERMINAL WIDTH ATW (FT)
1	VEGETATED SWALE 1	2	3		
2	VEGETATED SWALE 2	2	3		

FOR D ≥ 3 FT. - USE R-4  
FOR D ≥ 2 FT. TO D < 3 FT. - USE R-3  
NOT APPLICABLE FOR D < 2 FT.

SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH 1/3 THE HEIGHT OF THE FILTERS. IMMEDIATELY UPON STABILIZATION OF EACH CHANNEL, REMOVE ACCUMULATED SEDIMENT, REMOVE ROCK FILTER, AND STABILIZE DISTURBED AREAS.

**STANDARD CONSTRUCTION DETAIL #4-14**  
ROCK FILTER

NOT TO SCALE



PA DEP EROSION CONTROL MANUAL TABLE 13.1  
MAXIMUM SPACING AND MATERIALS FOR TRENCH PLUGS

TRENCH SLOPE (%)	SPACING L (FT)	PLUG MATERIAL
≤ 5	1000	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
5 - 15	500	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
15 - 25	300	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
25 - 35	200	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
35 - 100†	100	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
> 100	50	CEMENT BAGS (NETTED) OR MORTARED STONE

\* TOPSOIL MAY NOT BE USED TO FILL SACKS

IMPERVIOUS TRENCH PLUGS ARE REQUIRED FOR ALL STREAM, RIVER, WETLAND, OR OTHER WATER BODY CROSSINGS.

**STANDARD CONSTRUCTION DETAIL #13-4**  
TRENCH PLUG INSTALLATION

NOT TO SCALE

CLIENT		SUBJECT	
R.B. ASHLEY CUSTOMS, LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465		EROSION AND SEDIMENTATION CONTROL DETAILS  <b>KELLY ACRES</b>  DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA	
SEAL	PROJECT NO.	1660 WEAVERTOWN ROAD, SUITE 100 DOUGLASSVILLE, PA 19518 PHONE: 610-689-6021 FAX: 610-689-4538	
	DWG. NO.	20-374A	
	DESIGN	CHKD. BY	ES420374A
DRAWN BY	CHKD. BY	SHEET NO.	
WJD	BDB	12 OF 23	
DATE	SCALE	NOT TO SCALE	
2020-09-04			

NO.	REVISION	DATE	BY	APP.
13	REVISED PER DIMA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BOB
12	REVISED PER PENNOM REVIEW LETTER DATED APRIL 21, 2023 AND MDCP LETTER DATED APRIL 18, 2023	2023-05-03	SSR	BOB
11	REVISED PER PENNOM REVIEW LETTER DATED MARCH 9, 2023 AND FOR FINAL PLAN	2023-03-07	SSR	BOB
10	REVISED PER MDCD EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BOB
9	REVISED PER MDCD REVIEW LETTER DATED JANUARY 19, 2023	2023-01-20	SSR	BOB
8	REVISED PER MDCD REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BOB
7	REVISED PER MDCD REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BOB
6	REVISED PER MDCD EMAIL DATED JULY 26, 2022	2022-07-29	JKL	BOB
5	REVISED PER MDCD REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	BOB
4	REVISED PER MDCD REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BOB
3	REVISED PER MDCD REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BOB
2	REVISED PER SSC REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BOB
1	REVISED PER PENNOM REVIEW LETTER DATED NOVEMBER 5, 2021 AND MDCD REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BOB

I. 102.4(b)(4) - Site disturbance will be minimized by protecting existing woodlands and vegetation outside of the required area for construction. A construction fence will be installed to protect the area. Rain Gardens will capture post construction stormwater flows from the dwellings and the driveway. Sediment traps and compost filter socks will minimize erosion impacted by construction. The socks will allow for undisturbed site and BMP construction as well as protecting compaction and sediment storage in the areas of the BMP areas.

II. 102.4(b)(5)(i) - The existing topographic features of the project site and the immediate surrounding area.

The site contains two distinct watersheds. Watershed 1 to the UNT to Minister Creek slopes towards Buchert Road to the northeast at an average 3-8% slope. Watershed 2 to the UNT to Minister Creek slopes towards Buchert Road to the southeast at an average 3-8% slope. The proposed construction will disturb 4.23 acres. The undisturbed acreage will remain as meadow and wooded. A USGS map is included in Appendix A.

III. 102.4(b)(5)(ii) - The types, depth, slope, locations and limitations of the soils.

The soils boundaries, types, depth are shown on the Erosion Control Plan. The soils mapping and information has been taken from the United States Department of Agriculture National Cooperative Soil Survey for Montgomery County, PA. The soils are not classified as hydric and/or having hydric inclusions. A copy of the soil report is included in Appendix B.

Table with 3 columns: Soil Name, Penn channery silt loam, 3 to 8 percent slopes, Klinesville channery silt loam, 3 to 8 percent slopes. Rows include Depth to Seasonal Water Table (ft), pH, Susceptibility to Frost Action, etc.

Table with 3 columns: Soil Name, Penn channery silt loam, 3 to 8 percent slopes, Klinesville channery silt loam, 3 to 8 percent slopes. Rows include Cutbanks Cave, Corrosive to Concrete/Steel, Droughty, etc.

Soil Limitations and Resolutions

Cutbacks Cave - Cutbacks have potential to cave and have low strength. All applicable OSHA standards and regulations must be implemented at all times, especially during trenching and excavation. Corrosive to Concrete/Steel - Soils are corrosive to concrete and steel.

4. Erosion and sediment BMPs must be constructed, stabilized, and functional before site disturbance begins within the tributary areas of these BMPs. 5. After final site stabilization has been achieved, temporary erosion and sedimentation BMPs must be removed. Areas disturbed during removal of the BMPs must be stabilized immediately.

Temporary Control Measures and Facilities for Use During Earthmoving

1. Compost filter sock and/or silt fence shall be installed at locations noted on the plan prior to any disturbance of the existing ground cover. During the construction phase, the O/RP shall be responsible for cleaning or replacing compost filter socks and/or silt fence after each rainfall event to insure continued operation.

Stabilization Notes

1. Topsoil required for the establishment of vegetation shall be stockpiled at the location shown on the plan in the amount necessary to complete the finish grading of all exposed areas that are to be stabilized by vegetation.

Permanent Control Measures and Facilities for Long Term Protection

The following activities shall be undertaken to achieve permanent stabilization of all exposed and disturbed soil areas as required or directed.

Permanent Vegetative Surface Stabilization

Site Preparation - Incorporate lime and fertilizer (rate based upon soil testing) as deeply into the soil as possible. If soil tests are not available, apply four tons per acre of agricultural limestone and 10-20-20 fertilizer at a rate of 500 pounds per acre.

Temporary and Permanent Stabilization Specifications

Temporary Seeding Species: Annual Ryegrass, Pure Live Seed: 89%, Application Rate: 40 lbs. per acre, Fertilizer Type: 10-10-20, Limiting Application Rate: 1000 lbs. per acre.

Permanent Seeding

Species: Tall Fescue (39%), Fine Fescue (38%), Alsike Clover (20%), Redtop (3%) Application Rate: 20, 10, 20 and 12 lbs. per acre, respectively Fertilizer Type: 10-20-20, Limiting Application Rate: 1000 lbs. per acre.

Permanent Steep Slope Seeding Species: Tall Fescue Alsike Pure Live Seed: 89% Application Rate: 20 and 10 lbs. per acre, respectively Fertilizer Type: Refer to Permanent Control Measures Section

Channel Notes

1. All channels must be kept free of obstructions such as fill ground, fallen leaves & woody debris, accumulated sediment, and construction materials/wastes. Channels should be kept mowed and/or free of weeds, brushy or woody growth.

Utility Line Trench Excavation

1. Limit advanced clearing and grubbing operations to a distance equal to two times the length of pipe installation that can be completed in one day. 2. Work crews and equipment for trenching, placement of pipe, plug construction and backfilling will be self-contained and separate from clearing and grubbing and site restoration and stabilization operations.

Soil Amendment Notes

1. Compost shall be added to topsoil at a rate of 60-80 (soil:compost). The compost shall have a pH between 5.0 and 8.5, have a moisture content between 30% and 60% and an organic content between 25% and 65%.

NPDES Permit Notes

1. Upon reduction, loss or failure of the BMP, the permittee and co-permittee shall take immediate action to restore the BMPs or provide an alternative method of treatment. 2. Where E&S BMPs are found to be inoperative or ineffective during an inspection, or any other time, the permittee and co-permittee shall immediately contact the Montgomery County Conservation District, by phone or personal contact, following the submission of a written report within 5 days of the initial contact.

Construction Sequence Notes

1. All earth disturbances, including clearing and grubbing as well as cuts and fills, be done in accordance with the approved E&S plan. A copy of the approved drawings (stamped, signed, and dated by the Montgomery County Conservation District) must be available at the project site at all times.

9. Before disposing of soil or receiving borrow for the site, the operator must assure that each spoil or borrow area has an erosion and sediment control plan approved by the local County Conservation District or the Department of Environmental Protection, and which is fully implemented and maintained according to Chapter 102 regulations prior to being activated.

The general sequence of construction is as follows. If any modifications are necessary or desired by the O/RP, they must be approved by the Montgomery County Conservation District prior to implementing the changes.

1. The limit of disturbance (LOD) and extent of protected sensitive features including woods, steep slopes, floodplain, fenitized disturbance and reduced grading shall be marked with survey stakes, posts and rebar, construction fence or some other acceptable material prior to disturbance activities. The protected sensitive feature areas shown on the PCSM plans shall not be disturbed during construction except for temporary impacts for mitigation and restoration efforts.

Upon the installation or stabilization of all perimeter sediment control BMP's and at least 3 days prior to proceeding with the bulk earth disturbance activities, the permittee or co-permittee shall provide notification to the Montgomery County Conservation District.

7. Install the sewer line using the following procedure: Limit advanced clearing and grubbing operations to a distance equal to two times the length of pipe installation that can be completed in one day. Work crews and equipment for trenching, placement of pipe, plug construction and backfilling will be self-contained and separate from clearing and grubbing and site restoration and stabilization operations.

Begin construction of the Sediment Trap 1 using the following procedure:

Install Compost Filter Socks Grub the Sediment Trap area. The topsoil shall be stripped and placed in the areas designated on the plan. Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.

Begin construction of the Sediment Trap 2 using the following procedure:

Install Compost Filter Socks Grub the Sediment Trap area. The topsoil shall be stripped and placed in the areas designated on the plan. Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.

Let 1

10. Install the Compost Filter Sock 1 in the location shown on the plan. 11. Clear and grub for all disturbed areas. 12. Install the concrete washout area where shown on the Erosion Control Plans per the details for the Filtrax® Filter Ring prior to starting any concrete work on the site.

CLIENT: R.B. ASHLEY CUSTOMS, LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465 SUBJECT: EROSION AND SEDIMENTATION CONTROL NARRATIVE KELLY ACRES DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA PROJECT NO. 20-374A DWG. NO. ES520374A SHEET NO. 13 OF 23

Vertical text on the left margin: P:\PROJECTS\20-374A\_Roadway... 18-May-23 09:24:30

27. CRITICAL STAGE. After upslope areas are stabilized (a minimum of 70% uniform perennial vegetative cover), install Rain Garden 2. A Licensed Professional Engineer shall be present for this step.
- o CRITICAL STAGE. Any sediment entering the BMP shall be removed with light equipment. The underlying soil shall be scarified a minimum of twelve inches with a york rake, rototiller or other suitable equipment. A licensed professional shall provide oversight during the scarifying of the subgrade.
  - o The topsoil shall be stripped and be placed where shown on the plan.
  - o Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
  - o CRITICAL STAGE. Install the outlet structure, concrete cradle, and outlet pipe. A licensed Professional shall provide oversight during the backfilling of the outlet pipe.
  - o Stabilize the entire outside of the berm and on the inside of the berm with topsoil.
  - o Immediately apply the permanent seeding and mulch for the entire area. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
  - o Install amended topsoil, per the procedure outlined on the plans, on the inside of the rain garden, permanently seeded and mulched. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
  - o Install rain garden plantings.

**Lot 3**

28. Install the Rock Construction Entrance, clear and grub as needed.
29. Install the Compost Filter Socks 3, 4, 5, 16, and 17 in the locations shown on the plan.
30. Clear and grub for all disturbed areas.
31. Install the concrete washout area where shown on the Erosion Control Plans per the details for the Filtrrexx® Filter Ring prior to starting any concrete work on the site.
32. Install Vegetated Swale 2 and permanently stabilize. Rock filter and rip rap apron shall be installed during sediment trap operation.
33. The house, driveway, and site grading may begin using the following procedure:

- The contractor shall ensure that the runoff from all possible earth disturbance activities shall constantly be directed towards compost filter socks.
- Place the topsoil where shown on the plan and seed and mulch the area.
- Place fill and compact to proposed grades starting downhill working uphill.
- The subgrade shall be rolled and the stone placed where shown on the plan for the driveway.
- Begin house construction. Excavated material shall be placed on the subsoil stockpile, seeded, and mulched.
- Begin installing the utilities using the following procedure. The utility lines may be installed simultaneously if desired by the O/RP:
  - o The sewer laterals.
  - o The water service line.
  - o The gas, electric, telephone and cable lines, if proposed, shall be installed. The open trenches shall be backfilled and stabilized at the end of each day.

34. Stabilize the disturbed areas on the site with a minimum of six inches of topsoil, permanently seed and mulch. A slope protection blanket shall be installed where shown on the plan.
35. No more than 15,000 square feet of disturbed area shall reach final grade before initiating seeding and mulching operations on areas proposed to be lawn areas.
36. Pavement areas shown on the plans and stabilize any disturbed areas any time after this step.

37. CRITICAL STAGE. After upslope areas are stabilized (a minimum of 70% uniform perennial vegetative cover), install Rain Garden 5. A Licensed Professional Engineer shall be present for this step.
- o CRITICAL STAGE. Any sediment entering the BMP shall be removed with light equipment. The underlying soil shall be scarified a minimum of twelve inches with a york rake, rototiller or other suitable equipment. A licensed professional shall provide oversight during the scarifying of the subgrade.
  - o The topsoil shall be stripped and be placed where shown on the plan.
  - o Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
  - o CRITICAL STAGE. Install the outlet structure, outlet pipe, and concrete cradle. A licensed Professional shall provide oversight during the backfilling of the outlet pipe.
  - o Stabilize the entire outside of the berm and on the inside of the berm with topsoil.
  - o Immediately apply the permanent seeding and mulch for the entire area. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
  - o Install amended topsoil, per the procedure outlined on the plans, on the inside of the rain garden, permanently seeded and mulched. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
  - o Install rain garden plantings.

**Lot 4**

38. Install the Compost Filter Socks 6-9 in the locations shown on the plan.
39. Clear and grub for all disturbed areas.
40. Install the concrete washout area where shown on the Erosion Control Plans per the details for the Filtrrexx® Filter Ring prior to starting any concrete work on the site.
41. The house, driveway, and site grading may begin using the following procedure:
- The contractor shall ensure that the runoff from all possible earth disturbance activities shall constantly be directed towards compost filter socks.
  - Place the topsoil where shown on the plan and seed and mulch the area.
  - Place fill and compact to proposed grades starting downhill working uphill.
  - The subgrade shall be rolled and the stone placed where shown on the plan for the driveway.
  - Begin house construction. Excavated material shall be placed on the subsoil stockpile, seeded, and mulched.
  - Begin installing the utilities using the following procedure. The utility lines may be installed simultaneously if desired by the O/RP:
    - o The sewer laterals.
    - o The water service line.
    - o The gas, electric, telephone and cable lines, if proposed, shall be installed. The open trenches shall be backfilled and stabilized at the end of each day.

42. Stabilize the disturbed areas on the site with a minimum of six inches of topsoil, permanently seed and mulch. A slope protection blanket shall be installed where shown on the plan.
43. No more than 15,000 square feet of disturbed area shall reach final grade before initiating seeding and mulching operations on areas proposed to be lawn areas.
44. Pavement areas shown on the plans and stabilize any disturbed areas any time after this step.
45. Install landscaping and trees in areas of lawn shown on the plans using light tracked equipment. Do not run equipment over areas of soil amendment to avoid compaction. Stabilize all disturbed areas with seed and mulch.

**Lot 5**

46. Install the Rock Construction Entrance, clear and grub as needed.
47. Install the Compost Filter Socks 10-15 in the locations shown on the plan.
48. Begin construction of the Sediment Trap 3 using the following procedure:
- Grub the Sediment Trap area.
  - The topsoil shall be stripped and be placed in the areas designated on the plan.
  - Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
  - CRITICAL STAGE. Install and backfill the outlet structure and outlet pipe from the end section to the outlet structure starting at the downstream end and working uphill. Immediately install the concrete cradle. The permanent outlet structure shall be installed in the Sediment trap. Joints shall be water tight. The underdrain shall not be installed at this time. A licensed Professional shall provide oversight during the backfilling of the outlet pipe.
  - Install the cleanout stake and mark the sediment cleanout elevation on the stake.
  - Stabilize the entire outside of the berm with amended soils and on the inside of the sediment trap above the cleanout elevation with topsoil.
  - Immediately apply the permanent seeding and mulch for the entire outside of the berm and above the sediment cleanout elevation on the inside of the basin. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1. The emergency spillway shall have the North American Green Blanket P300 installed.
49. Strip topsoil, stockpile and immediately stabilize with temporary seed and mulch.
50. Install the concrete washout area where shown on the Erosion Control Plans per the details for the Filtrrexx® Filter Ring prior to starting any concrete work on the site.

51. The house, driveway, and site grading may begin using the following procedure:
- The contractor shall ensure that the runoff from all possible earth disturbance activities shall constantly be directed towards compost filter socks.
  - Place the topsoil where shown on the plan and seed and mulch the area.
  - Place fill and compact to proposed grades starting downhill working uphill.
  - The subgrade shall be rolled and the stone placed where shown on the plan for the driveway.
  - Begin house construction. Excavated material shall be placed on the subsoil stockpile, seeded, and mulched.
  - Begin installing the utilities using the following procedure. The utility lines may be installed simultaneously if desired by the O/RP:
    - o The sewer laterals.
    - o The water service line.
    - o The gas, electric, telephone and cable lines, if proposed, shall be installed. The open trenches shall be backfilled and stabilized at the end of each day.

52. Stabilize the disturbed areas on the site with a minimum of six inches of topsoil, permanently seed and mulch. A slope protection blanket shall be installed where shown on the plan.
53. No more than 15,000 square feet of disturbed area shall reach final grade before initiating seeding and mulching operations on areas proposed to be lawn areas.
54. Pavement areas shown on the plans and stabilize any disturbed areas any time after this step.

55. CRITICAL STAGE. After upslope areas are stabilized (a minimum of 70% uniform perennial vegetative cover), install Rain Garden 4. A Licensed Professional Engineer shall be present for this step.
- o Any sediment entering the BMP shall be removed with light equipment. The underlying soil shall be scarified a minimum of twelve inches with a york rake, rototiller or other suitable equipment. A licensed professional shall provide oversight during the scarifying of the subgrade.

- o The topsoil shall be stripped and be placed where shown on the plan.
  - o Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
  - o CRITICAL STAGE. Install the underdrain. A licensed Professional shall provide oversight during the backfilling of the outlet pipe.
  - o Stabilize the entire outside of the berm and on the inside of the berm with topsoil.
  - o Immediately apply the permanent seeding and mulch for the entire area. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
  - o Install amended topsoil, per the procedure outlined on the plans, on the inside of the rain garden, permanently seeded and mulched. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
  - o Install rain garden plantings.
56. Install landscaping and trees in areas of lawn shown on the plans using light tracked equipment. Do not run equipment over areas of soil amendment to avoid compaction. Stabilize all disturbed areas with seed and mulch.

57. CRITICAL STAGE. After lots 1 and 2 are stabilized (a minimum of 70% uniform perennial vegetative cover), install Rain Garden 1. A Licensed Professional Engineer shall be present for this step.
- o Construction shall occur during dry weather only to prevent discharge from Rain Garden 2 from entering the trap during conversion. If wet conditions are unavoidable, discharge from Swale 1 shall be directed to temporarily bypass the trap and discharge into a stabilized area.
  - o CRITICAL STAGE. Any sediment entering the BMP shall be removed with light equipment. The underlying soil shall be scarified a minimum of twelve inches with a york rake, rototiller or other suitable equipment. A licensed professional shall provide oversight during the scarifying of the subgrade.
  - o The topsoil shall be stripped and be placed where shown on the plan.
  - o Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
  - o Stabilize the entire outside of the berm and on the inside of the berm with topsoil.
  - o Immediately apply the permanent seeding and mulch for the entire area. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
  - o Install amended topsoil, per the procedure outlined on the plans, on the inside of the rain garden, permanently seeded and mulched. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
  - o Install rain garden plantings.

58. CRITICAL STAGE. After upslope areas are stabilized (a minimum of 70% uniform perennial vegetative cover), install Rain Garden 3. A Licensed Professional Engineer shall be present for this step.
- o Any sediment entering the BMP shall be removed with light equipment. The underlying soil shall be scarified a minimum of twelve inches with a york rake, rototiller or other suitable equipment. A licensed professional shall provide oversight during the scarifying of the subgrade.
  - o The topsoil shall be stripped and be placed where shown on the plan.
  - o Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
  - o CRITICAL STAGE. Install the underdrain. A licensed Professional shall provide oversight during the backfilling of the outlet pipe.
  - o Stabilize the entire outside of the berm and on the inside of the berm with topsoil.
  - o Immediately apply the permanent seeding and mulch for the entire area. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
  - o Install amended topsoil, per the procedure outlined on the plans, on the inside of the rain garden, permanently seeded and mulched. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
  - o Install rain garden plantings.
59. When all of the disturbances on the site are completely stabilized (a minimum of 70% uniform perennial vegetative cover), all temporary BMPs should be removed from the site and any disturbance created when removing them shall immediately be permanently seeded and mulched. Compost filter socks shall be split open and the compost distributed in landscaped areas of the site. Stakes and castings shall be disposed of properly.

Upon permanent stabilization of earth disturbance activity under 25 Pa. Code § 102.12(a)(2) and installation of BMPs in accordance with the approved plan prepared and implemented in accordance with 25 Pa. Code § 102.4 and 102.5, the permittee and/or co-permittee shall submit a Notice of Termination (NOT) to the Department or authorized conservation district.

XI. 102.4(b)(5)(x) - A maintenance program which provides for inspection of BMPs on a weekly basis and after each measurable rainfall event, including the repair of the BMPs to ensure effective and efficient operation.

**Maintenance Program**

- The O/RP shall be responsible for the installation and maintenance of all erosion control facilities.
- All erosion control facilities shall be inspected after each rainfall event and weekly to ensure that they are in good repair and in working condition. Any damaged facility shall be repaired immediately.
- Seeded areas that have eroded shall be filled and graded as necessary and then reseeded and mulched.
- The inspections and maintenance shall continue after each sizable storm event until signs of erosion are gone. Inspections and necessary cleaning and maintenance shall be performed monthly thereafter.
- A log showing dates that E&S BMPs were inspected as well as any deficiencies found and the date they were corrected shall be maintained on the site and be made available to regulatory agency officials at the time of inspection.
- E&S BMPs shall remain functional as such until all areas tributary to them are permanently stabilized or until they are replaced by another BMP approved by the Montgomery County Conservation District.
- The silt that has accumulated shall be removed from the erosion control structure, allowed to dry and then it can be used as fill where needed on the site. Inspect the rock filter outlets and compost filter socks weekly and after each storm event. The filter material shall be cleaned and/or replaced if it is clogged.
- The vegetation shall be mowed as necessary to maintain a neat appearance and discourage weed growth. The local ordinances shall be followed.
- Any trash that is removed from the erosion control structures shall be disposed in accordance with local, state and federal regulations. The installation and maintenance of the temporary control facilities will be the responsibility of the O/RP. The temporary controls will be maintained in accordance with the Pennsylvania Department of Environmental Protection regulations.
- The Pennsylvania Department of Environmental Protection regulations require a 70% uniform erosion resistant perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated erosion over all disturbed areas be established before the site is considered permanently stabilized. Cut and fill slopes shall be capable of resisting failure due to slumping, sliding, or other movements. Until such time as the standard is achieved, interim stabilization and temporary erosion and sedimentation control measures and facilities that are used to treat the runoff shall remain in place.
- The O/RP is responsible for removing the temporary erosion controls after the site is permanently stabilized with vegetation. The O/RP shall stabilize any areas disturbed during the removal of the erosion control facilities.
- After the site is permanently stabilized, the property owner shall periodically check the graded areas and swales for any developing erosion problems. Any damaged areas shall be repaired immediately.

XII. 102.4(b)(5)(v) - Procedures which ensure that the proper measures for the recycling or disposal of materials associated with or from the project site will be undertaken in accordance with Department regulations.

The site will not be used to store any chemicals, solvents or other hazardous waste or materials with the potential to cause accidental pollution during earth disturbance activities. Project construction waste will be sediment from the site and associated construction building materials. Sediment removed from the erosion control measures/facilities shall be disposed of in landscaped areas outside of steep slopes, wetlands, floodplains and drainage swales and immediately stabilized or placed on topsoil stockpiles. Waste building materials will be removed from the site by a licensed hauler and either recycled or disposed of according to State and Federal Regulations.

No material may be removed from this project without an erosion control plan approved by the local conservation district for the disposal site. Temporary and permanent control measures and facilities must be maintained during the progress of the work at the site. This will be done by implementing a program of proper disposal of materials and frequent removal of solid materials from the erosion control facilities.

If the site will need to import or export material from the site, the responsibility for performing environmental due diligence and determination of clean fill will rest with the operator.

**Clean Fill** is defined as: uncontaminated, non-water soluble, non-decomposable, inert, solid material. The term includes soil, rock, stone, dredged material, used asphalt, and brick, block or concrete from construction and demolition activities that is separate from other waste and is recognizable as such. The term does not include materials placed in or on the waters of the Commonwealth unless otherwise authorized. (The term "used asphalt" does not include milled asphalt or asphalt that has been processed for re-use).

**Clean Fill affected by a spill or release of a regulated substance:** Fill materials affected by a spill or release of a regulated substance still qualifies as clean fill provided the testing reveals that the fill material contains concentrations of regulated substances that are below the residential limits in Tables FP-1a and FP-1b found in the Department's policy "Management of Fill".

Any person placing clean fill that has been affected by a spill or release of a regulated substance must use form FP-001 to certify the origin of the fill material and the results of the analytical testing to qualify the material as clean fill. Form FP-001 must be retained by the owner of the property receiving the fill.

**Environmental due diligence:** The applicant must perform environmental due diligence to determine if the fill materials associated with the project qualify as clean fill. Environmental due diligence is defined as: *investigative techniques, including, but not limited to, visual property inspections, electronic data base searches, review of property ownership, review of property use history, Sanborn maps, environmental questionnaires, transaction records, analytical testing, environmental assessments or audits. Analytical testing is not a required part of due diligence unless visual inspection and/or review of the past land use of the property indicates that the fill may have been subjected to a spill or release of regulated substance.* If the fill may have been affected by a spill or release of a regulated substance, it must be tested to determine if it qualifies as clean fill. Testing should be performed in accordance with Appendix A of the Department's policy "Management of Fill".

Fill material that does not qualify as clean fill is regulated fill. Regulated fill is waste and must be managed in accordance with the Department's municipal or residual waste regulations based on 25 Pa. Code Chapters 287 Residual Waste Management or 271 Municipal Waste Management, whichever is applicable. These regulations are available on-line at [www.egscdfc.com](http://www.egscdfc.com).

XIII. 102.4 (b)(5)(xii) Identification of the naturally occurring geologic formations or soil conditions that may have the potential to cause pollution during earth disturbance activities and include BMPs to avoid or minimize potential pollution and its impacts from the formations.


There are no naturally occurring geologic formations or soil conditions with the potential to cause pollution during earth disturbance. The soils have a potential for erosion, the erosion from the soils could potentially cause water pollution. To minimize this potential risk, the erosion and sediment control BMPs mentioned above are to be provided.

XIV. 102.4(b)(5)(xiii) Identification of potential thermal impacts to surface waters from the earth disturbance activity including BMPs to avoid, minimize or mitigate potential pollution from thermal impacts.



The potential for thermal impacts is present due to storm water flows over impervious areas. This impact is mitigated through directing stormwater to the rain gardens, vegetated areas, and across shaded and pervious areas.

NO.	REVISION	DATE	BY	APP.
13.	REVISED PER BMAA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BOB
12.	REVISED PER PENNDOT REVIEW LETTER DATED APRIL 21, 2023 AND MCPC LETTER DATED APRIL 18, 2023	2023-05-03	SSR	BOB
11.	REVISED PER PENNDOT REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN	2023-03-07	SSR	BOB
10.	REVISED PER MCOD EMAIL DATED MARCH 2, 2022	2023-03-02	SSR	BOB
9.	REVISED PER MCOD REVIEW LETTER DATED JANUARY 18, 2023	2023-01-20	SSR	BOB
8.	REVISED PER MCOD REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BOB
7.	REVISED PER MCOD REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BOB
6.	REVISED PER MCOD EMAIL DATED JULY 28, 2022	2022-07-29	JKL	BOB
5.	REVISED PER MCOD REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	BOB
4.	REVISED PER MCOD REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BOB
3.	REVISED PER MCOD REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BOB
2.	REVISED PER SDC REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BOB
1.	REVISED PER PENNDOT REVIEW LETTER DATED NOVEMBER 9, 2021 AND MCOD REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BOB

CLIENT		SUBJECT	
R.B. ASHLEY CUSTOMS, LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465		EROSION AND SEDIMENTATION CONTROL NARRATIVE	
SEAL		KELLY ACRES	
		DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA	
		PROJECT NO. 20-374A	
		DWG. NO. ES620374A	
DESIGN	BDB	CHKD. BY	BDB
DRAWN BY	WJD	CHKD. BY	
DATE	2020-09-04	SCALE	14 OF 23 NOT TO SCALE



P:\PROJECTS\20-374A\_Robins - Kelly\Lot\Site\PT120274A.dwg, 18-May-23 09:34:41



**LEGEND**

- EX. TRACT LINE
- EX. BOUNDARY
- EX. RIGHT-OF-WAY
- SETBACKS
- EX. STORMWATER PIPE
- EX. SANITARY
- EX. WATERLINE
- EX. MONUMENTATION
- EX. UTILITY POLE & GUY WIRE
- EX. OVERHEAD WIRES
- EX. SANITARY MANHOLE
- EX. FIRE HYDRANT
- EX. TREELINE
- EX. SOILS
- EX. CONTOURS
- PR. CONTOURS
- INFILTRATION TEST PIT
- PR. EDGE OF PAVING
- PR. BUILDING
- PR. WATER SERVICE
- PR. SEWER LATERAL
- PR. FORCE MAIN
- PR. SANITARY SEWER
- PR. STORMWATER PIPE
- PR. ROOF DRAINS
- PR. UNDERGROUND UTILITY
- PR. OVERHEAD UTILITY
- PR. TREELINE
- PR. SPILLWAY/CHANNEL LINING
- PR. RIP RAP
- PR. SEWER MANHOLE
- PR. SEWER CLEANOUT
- PR. SEWER SHUTOFF
- PR. WATER VALVE
- PR. TREES
- NPDES BOUNDARY
- LIMIT OF DISTURBANCE
- WATERSHED
- PR. ELEVATION
- AMENDED SOILS

**TEST PITS**

TEST PIT #	LIMITING ZONE ELEVATION	LIMITING ZONE SEPARATION (FT)
1	351.25	2.00
2	368.83	2.17
3	365.00	2.00
4	354.17	1.08
5	357.75	1.00

**RAIN GARDEN SCHEDULE**


SYMBOL	SPECIES	QUANTITY	SIZE	RG1	RG2	RG3	RG4	RG5
⊙	EASTERN REDBUD, CERIS CANADENSIS	68	MIN 2.5" CAL./B&B	24	11	10	11	12
⊙	FLOWERING DOGWOOD, CORNUS FLORIDA	68	MIN 2.5" CAL./B&B	24	11	10	11	12
⊙	INKBERRY HOLLY, ILEX GLABRA	319	MIN 18" HT	112	51	47	52	56

RAIN GARDEN PLANTING CALCULATIONS:  
300 TREES PER ACRE OF BMP BOTTOM AREA  
700 SHRUBS PER ACRE OF BMP BOTTOM AREA

LIMIT OF DISTURBANCE 4.23 ACRES  
AMENDED SOIL AREA 9192 SQ FT

**SOILS TABLE**

SYMBOL	NAME/DESC
P&B	PENN SILT LOAM, 3 TO 6 PERCENT SLOPES
K&B	KUHNISVILLE CHANNERY SILT LOAM, 3 TO 6 PERCENT SLOPES



CLIENT  
**R.B. ASHLEY CUSTOMS, LLC**  
1011 RIDGE ROAD  
POTTSTOWN, PA 19465

SUBJECT  
POST CONSTRUCTION STORMWATER MANAGEMENT PLAN  
**KELLY ACRES**  
DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA


SEAL

Boyer  
ENGINEERING LLC

PROJECT NO.	20-374A		
DWG. NO.	PC120374A		
SHEET NO.	15 OF 23		
DESIGN	BDB	CHKD. BY	BOB
DRAWN BY	WJD	CHKD. BY	
DATE	2020-09-04	SCALE	1"=40'

NO.	REVISION	DATE	BY	APP.
13	REVISED PER BMAA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BOB
12	REVISED PER PENNING REVIEW LETTER DATED APRIL 21, 2023 AND M&CPC LETTER DATED APRIL 18, 2023	2023-05-03	SSR	BOB
11	REVISED PER PENNING REVIEW LETTER DATED MARCH 9, 2023 AND FOR FINAL PLAN	2023-03-07	SSR	BOB
10	REVISED PER M&CPC EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BOB
9	REVISED PER M&CPC REVIEW LETTER DATED JANUARY 19, 2023	2023-01-20	SSR	BOB
8	REVISED PER M&CPC REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BOB
7	REVISED PER M&CPC REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BOB
6	REVISED PER M&CPC EMAIL DATED JULY 28, 2022	2022-07-29	JKL	BOB
5	REVISED PER M&CPC REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	BOB
4	REVISED PER M&CPC REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BOB
3	REVISED PER M&CPC REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BOB
2	REVISED PER SIDE REVIEW LETTER DATED JANUARY 24, 2022	2022-02-11	SSR	BOB
1	REVISED PER PENNING REVIEW LETTER DATED NOVEMBER 9, 2021 AND M&CPC REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BOB


P:\PROJECTS\20-374A\_Ridge.Rvt - R.B. Ashley Customs, LLC - 18-May-23 09:24:48




SEED SWALE AREA WITH ERNST SEED MIX  
ERNMX-183 (OR EQUAL) AT 15#/AC AND  
OVERSEED WITH ANNUAL RYE AT 30#/AC

**VEGETATED SWALE  
CROSS SECTION**  
NO SCALE

CHANNEL NO.	STATIONS	BOTTOM WIDTH B (FT)	DEPTH D (FT)	TOP WIDTH W (FT)	Z1 (FT)	Z2 (FT)	LINING *
1	N/A	2	2	10	2	2	N.A.G. S75
2	N/A	1.25	2	9.25	2	2	N.A.G. S75



SECTION VIEW



PROFILE VIEW


PA DEP EROSION CONTROL MANUAL TABLE 13.1  
MAXIMUM SPACING AND MATERIALS FOR TRENCH PLUGS

TRENCH SLOPE (%)	SPACING L (FT)	PLUG MATERIAL
< 5	1000	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
5 - 15	500	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
15 - 25	300	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
25 - 35	200	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
35 - 100	100	* CLAY, BENTONITE, OR CONCRETE FILLED SACKS
> 100	50	CEMENT BAGS (WETTED) OR MORTARED STONE


\* TOPSOIL MAY NOT BE USED TO FILL SACKS

NOTES:  
DIFFERENT TRENCH PLUGS ARE REQUIRED FOR ALL STREAM, RIVER, WETLAND, OR OTHER WATER BODY CROSSINGS.

**STANDARD CONSTRUCTION DETAIL #13-4  
TRENCH PLUG INSTALLATION**  
NOT TO SCALE



CROSS-SECTION AT OUTLET BARREL



CROSS-SECTION AT OUTLET BARREL


NOTES:  
A CONCRETE CRADLE MAY BE USED IN CONJUNCTION WITH ANTI-SEEP COLLARS AND/OR FILTER DIAPHRAGM.  
ANTI-SEEP COLLAR NUMBER, SIZE AND SPACING SHALL BE AS SHOWN ELSEWHERE IN PLAN.  
FILTER DIAPHRAGM LOCATION (L16) SHALL BE AS SHOWN IN FIGURE 7.8 OF THE PA DEP EROSION CONTROL MANUAL.

**STANDARD CONSTRUCTION DETAIL #7-17  
CONCRETE CRADLE FOR BASIN OR TRAP OUTLET BARREL**  
NOT TO SCALE


NOTES:  
ALL APRONS SHALL BE CONSTRUCTED TO THE DIMENSIONS SHOWN. TERMINAL WIDTHS SHALL BE ADJUSTED AS NECESSARY TO MATCH RECEIVING CHANNELS.  
ALL APRONS SHALL BE INSPECTED AT LEAST WEEKLY AND AFTER EACH RUNOFF EVENT. DISPLACED RIPRAP WITHIN THE APRON SHALL BE REPLACED IMMEDIATELY.

**STANDARD CONSTRUCTION DETAIL #9-1  
RIPRAP APRON AT PIPE OUTLET WITH FLARED END SECTION OR ENDWALL**  
NOT TO SCALE

OUTLET NO.	PIPE DIA Pd (IN)	RIPRAP SIZE R- (IN)	THICK. R1 (IN)	LENGTH L1 (FT)	INITIAL TERMINAL WIDTH Aw (FT)	WIDTH Atw (FT)
ESI	12	4	18	8	3	11
OFFSITE	12	4	18	8	3	11



PLAN VIEW



SECTION Y-Y




SECTION Z-Z


**NOTES**

- PREPARE BEDDING: BEDDING MATERIAL AROUND THE END SECTION MAY BE THE SAME AS THE MATERIAL AROUND THE PIPE. PLACE A FEW INCHES OF BEDDING MATERIAL IN THE TRENCH OR DITCH WHERE THE END SECTION WILL BE PLACED. COMPACT AND CONTOUR THIS MATERIAL TO GENERALLY MATCH THE END SECTION; EXCAVATE AN AREA IN THE BEDDING WHERE THE TOE TROUGH WILL SEAT SO THAT THE END SECTION WILL ALIGN TO PROPER GRADE IN THE FINISHED INSTALLATION.
- PLACE END SECTION ON PIPE: OPEN THE END SECTION COLLAR AND SEAT IT OVER THE LAST TWO PIPE CORRUGATIONS. ONCE THE END SECTION IS POSITIONED, CHECK TO MAKE SURE THE INVERT OF THE END SECTION MATCHES THE INVERT OF THE PIPE AND THAT THE END SECTION IS ALIGNED TO THE PROPER GRADE.
- SECURE THE END SECTION: SLIP THE STAINLESS STEEL ROD THROUGH THE PRE-DRILLED HOLES AT THE END OF THE PIPE. THE TOP OF THE COLLAR, THE ROD SHOULD BE BETWEEN THE CROWNS OF THE TWO CORRUGATIONS AT THE END OF THE PIPE. PLACE A WASHER ON EITHER END OF THE ROD; PLACE A NUT ON EITHER END OF THE ROD AND HAND TIGHTEN WITH A WRENCH UNTIL THE COLLAR IS TIGHT AROUND THE PIPE. DO NOT OVER-TIGHTEN.
- SECURE TOE TROUGH: TO PREVENT WASHOUTS FROM HIGH VELOCITY FLOW, IT IS RECOMMENDED THAT THE TOE TROUGH BE SECURED WITH CONCRETE. POUR CONCRETE IN THE TROUGH UP TO THE LEVEL OF THE TRENCH OR DITCH BOTTOM AND ALONG THE ENTIRE LENGTH OF THE TROUGH.
- FINISH BACKFILL: SHOVEL BACKFILL AROUND THE END SECTION IN 6-TO 9-INCH LAYERS EQUALLY ON BOTH SIDES. KNIFE IT IN TO ELIMINATE VOIDS. TAMP WITH A SMALL-FACED COMPACTOR OR OTHER EQUIPMENT SUITABLE FOR SMALL AREAS. CONTINUE PLACING, KNIFING AND COMPACTING BACKFILL MATERIAL IN LAYERS TO THE TOP OF THE END SECTION TO SEAT IT WELL INTO THE BACKFILL.


HDPE END SECTION PIPE DIAMETER, in.						
DIMENSION	10/12	15	18	24	30	36
A	42	41	49	59-1/2	88	88
B	14-1/2	19	22	28	36	43
C	33	34	43	48	63-1/2	66-1/2
D	6	6	6	6	6	6



TOP VIEW




SIDE VIEW




FRONT VIEW


**FLARED END SECTION**  
NO SCALE




**STORM SEWER TRENCH - TYP. BACKFILL DETAIL**  
NO SCALE



DIMENSIONS ARE FOR REFERENCE ONLY. ACTUAL DIMENSIONS MAY VARY. DIMENSIONS ARE IN INCHES. QUALITY MATERIALS SHALL CONFORM TO ASTM ASSESS GRADE TO SLOPE. PAINT CASTINGS ARE FURNISHED WITH A BLACK PAINT.



**8" INCH DOME GRATE ASSEMBLY**  
DWG NO. 701-116-197  
**8" NYLOPLAST 0899CGD**  
NO SCALE




SOIL AMENDMENT (75% WASHED SHARP SAND, 15% DOUBLE SHROUDED HARDWOOD MULCH, 10% COMPOST BY VOLUME). DEPTH VARIES (SEE RAIN GARDEN DETAIL). 18" DEPTH OUTSIDE BMPs.


UNCOMPACTED SUBGRADE (TILING OR SCARIFICATION PRIOR TO SOIL AMENDMENT)

CONSTRUCTION NOTES:  
1. SOIL AMENDMENT CAN CONSIST OF COMPOST, MULCH AND SAND.  
2. AMENDED SOILS SHALL NOT BE PLACED ON SLOPES GREATER THAN 4:1.  
3. AMENDED SOILS SHALL NOT BE CONSTRUCTED WITHIN THE DRIP LINE OF EXISTING TREES.  
4. PERMANENT PLANTING/SEEDING SHALL BE IMMEDIATELY INSTALLED ON THE SURFACE BY HAND TO MINIMIZE COMPACTION.

**SOIL AMENDMENT**  
NO SCALE



**DECIDUOUS TREE PLANTING DETAIL**  
NO SCALE




**SHRUB PLANTING DETAIL**  
BALLED OR BARE SHRUB-NO SCALE

CLIENT <b>R.B. ASHLEY CUSTOMS, LLC</b> 1011 RIDGE ROAD POTTSTOWN, PA 19465	SUBJECT POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS <b>KELLY ACRES</b> DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA
SEAL	PROJECT NO. <b>20-374A</b>
	DWG. NO. <b>PC220374A</b>
	SHEET NO. <b>16 OF 23</b>
DATE 2020-09-04	SCALE NOT TO SCALE


NO.	REVISION	DATE	BY	APP.
13	REVISED PER BHMA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BOB
12	REVISED PER PENNDOT REVIEW LETTER DATED APRIL 21, 2023 AND MDCP LETTER DATED APRIL 18, 2023	2023-05-03	SSR	BOB
11	REVISED PER PENNDOT REVIEW LETTER DATED MARCH 9, 2023 AND FOR FINAL PLAN	2023-03-07	SSR	BOB
10	REVISED PER MDCD EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BOB
9	REVISED PER MDCD REVIEW LETTER DATED JANUARY 19, 2023	2023-01-20	SSR	BOB
8	REVISED PER MDCD REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BOB
7	REVISED PER MDCD REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BOB
6	REVISED PER MDCD EMAIL DATED JULY 28, 2022	2022-07-28	JLK	BOB
5	REVISED PER MDCD REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	BOB
4	REVISED PER MDCD REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BOB
3	REVISED PER MDCD REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BOB
2	REVISED PER SDE REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BOB
1	REVISED PER PENNDOT REVIEW LETTER DATED NOVEMBER 9, 2021 AND MDCD REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BOB

P:\PROJECTS\20-374A\_Roadway - Kelly Acres\Drawings\20-374A.dwg, 18-May-23 09:34:47



RAIN GARDEN	TEST PIT	A	B	C	D	E	F	G	H	I	J	K	L	M	N	P	Q	R	S	T	U	V	
1	1	384.75	355.25	355.75	356.75	352.75	45	13.0	346.50	18	N/A	N/A	355.35	351.25	N/A	10	8	355.17	N/A	N/A	N/A	N/A	
2	2	372.50	372.50	373.50	374.00	370.50	40	6.3	368.00	18	N/A	N/A	372.67	369.83	N/A	10	8	372.61	N/A	N/A	N/A	N/A	
3	4	357.25	357.75	358.25	358.75	355.25	20	3.9	352.85	24	355.25	354.50	357.33	354.17	356.25	10	8	356.80	356.18	356.00	5	352.25	
4	5	360.75	361.15	361.75	362.25	358.75	40	6.8	356.03	24	358.75	357.00	359.65	357.75	359.75	10	8	359.61	359.82	358.00	15	355.15	
5	3	367.50	368.00	368.50	369.00	365.50	25	8.3	363.43	18	N/A	N/A	365.00	367.81	364.00	N/A	10	8	367.89	N/A	365.00	5	363.00

NOTES FOR RAIN GARDEN:  
 1. ALL BASIN EMBANKMENTS SHALL BE PLACED AT A MAXIMUM OF EIGHT (8") LIFTS TO A MINIMUM OF 95% OF MAXIMUM DRY DENSITY AS ESTABLISHED BY ASTM D-1557. PRIOR TO PROCEEDING TO THE NEXT LIFT, THE COMPACTION SHALL BE CHECKED BY THE TOWNSHIP ENGINEER. THE DEVELOPER'S CONTRACTOR SHALL OBTAIN THE SERVICES OF A QUALIFIED LABORATORY TECHNICIAN TO CONDUCT COMPACTION TESTS ON THE LEADING AND THE TRAILING EDGE OF THE BERM ALONG WITH THE TOP OF THE BERM. ALL TESTS SHALL BE FURNISHED TO THE TOWNSHIP FOR REVIEW.  
 2. A CLAY CORE SHALL BE PROVIDED FOR THE BERM WITH A TOP ELEVATION AT THE PRINCIPAL SPILLWAY ELEVATION, MINIMUM TOP WIDTH OF 2' AND SIDE SLOPE OF 1:1.  
 3. A KEY TRENCH SHALL BE PROVIDED UNDER TILL EMBANKMENTS. THE KEY TRENCH SHALL BE A MINIMUM OF 8" WIDE, 2' BELOW EXISTING GRADE, WITH SIDE SLOPES OF 1:1.  
 4. ALL JOINTS SHALL BE WATERTIGHT.  
 MAINTENANCE:  
 1. THE OVERLYING VEGETATION OF SUBSURFACE INFILTRATION FEATURES SHOULD BE MAINTAINED IN GOOD CONDITION, AND ANY BARE SPOTS RE-VEGETATED AS SOON AS POSSIBLE.  
 2. VEHICULAR ACCESS ON SUBSURFACE INFILTRATION AREAS SHOULD BE PROHIBITED, AND CARE SHOULD BE TAKEN TO AVOID EXCESSIVE COMPACTION BY MOWERS. IF ACCESS IS NEEDED, USE OF PERMEABLE, TURF REINFORCEMENT SHOULD BE CONSIDERED.





NOTES

- SPREADER IS TO BE 30' IN LENGTH.
- OUTFALL PIPE IS TO BE TERMINATED IN "TEE" COUPLING.
- YARD DRAIN BASINS OR INLINE COUPLINGS SHALL BE USED WITH SURFACE GRATES AT EACH OF THE PERFORATED PIPE TO THE SURFACE.

BMP	A	B
RAIN GARDEN 3	354.00	352.00
RAIN GARDEN 4	357.00	355.00
RAIN GARDEN 5	365.00	363.00

LEVEL SPREADER DETAIL (LS3, LS4, LS5)  
NO SCALE




NOTES

- SPREADER IS TO BE 30' IN LENGTH.
- OUTFALL PIPE IS TO BE TERMINATED IN "TEE" COUPLING.
- YARD DRAIN BASINS OR INLINE COUPLINGS SHALL BE USED WITH SURFACE GRATES AT EACH OF THE PERFORATED PIPE TO THE SURFACE.


BMP	A	B
RAIN GARDEN 3	354.00	352.00
RAIN GARDEN 4	357.00	355.00
RAIN GARDEN 5	365.00	363.00

LEVEL SPREADER DETAIL (LS3, LS4, LS5)  
NO SCALE



NYLOPLAST 18" INLINE DRAIN QUICK SPEC INSTALLATION DETAIL

GRATE OPTIONS	LOAD RATING	PART #	DRAWING #
PEDESTRIAN	MEETS 11-10	1299C2P	7001-110-202
STANDARD	MEETS 11-20	1299C2G	7001-110-201
SOLID COVER	MEETS 11-20	1299C2C	7001-110-204
PEDESTRIAN BRIDGE	N/A	1299C2B	7001-110-205
DOME	N/A	1299C2D	7001-110-206
DROP-IN GRATE	LIGHT DUTY	1291D	7001-110-021



NYLOPLAST 12" DRAIN BASIN QUICK SPEC INSTALLATION DETAIL

GRATE OPTIONS	LOAD RATING	PART #	DRAWING #
PEDESTRIAN	MEETS 11-10	1299C2P	7001-110-202
STANDARD	MEETS 11-20	1299C2G	7001-110-201
SOLID COVER	MEETS 11-20	1299C2C	7001-110-204
PEDESTRIAN BRIDGE	N/A	1299C2B	7001-110-205
DOME	N/A	1299C2D	7001-110-206
DROP-IN GRATE	LIGHT DUTY	1291D	7001-110-021

NOTES

- GRATE/COVER SHALL BE DUCTILE IRON PER ASTM A538 GRADE 70-60-06, WITH THE EXCEPTION OF THE BRONZE GRATE.
- FRAMES SHALL BE DUCTILE IRON PER ASTM A538 GRADE 70-60-06.
- DRAIN BASINS TO BE CUSTOM MANUFACTURED ACCORDING TO PLAN DETAILS. RISERS ARE NEEDED FOR BASINS OVER 18" DUE TO SHIPPING RESTRICTIONS. SEE DRAWING NO. 7001-110-022.
- DRAINAGE CONNECTION SUB JOINT TIGHTNESS SHALL CONFORM TO ASTM D2112 FOR CORRUGATED HDPE (ADS N-12 HANCOR DUAL WALL, N-12 HP, PVC SEWER).
- ADAPTERS CAN BE MOUNTED ON ANY ANGLE 0° TO 360° TO DETERMINE MINIMUM ANGLE BETWEEN ADAPTERS SEE DRAWING NO. 7001-110-012.

P:\PROJECTS\20-274\20-274\_R01.dwg - Kelly LaVine (T) 2023/04/05 10:34:48

NO.	REVISION	DATE	BY	APP.
13	REVISED PER BMAA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BOB
12	REVISED PER PENNONI REVIEW LETTER DATED APRIL 21, 2023 AND MOPC LETTER DATED APRIL 18, 2023	2023-05-03	SSR	BOB
11	REVISED PER PENNONI REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN	2023-03-07	SSR	BOB
10	REVISED PER MCOO EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BOB
9	REVISED PER MCOO REVIEW LETTER DATED JANUARY 19, 2023	2023-01-20	SSR	BOB
8	REVISED PER MCOO REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BOB
7	REVISED PER MCOO REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BOB
6	REVISED PER MCOO EMAIL DATED JULY 28, 2022	2022-07-29	JKL	BOB
5	REVISED PER MCOO REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	BOB
4	REVISED PER MCOO REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BOB
3	REVISED PER MCOO REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BOB
2	REVISED PER SIDE REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BOB
1	REVISED PER PENNONI REVIEW LETTER DATED NOVEMBER 5, 2021 AND MCOO REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BOB

CLIENT	SUBJECT
R.B. ASHLEY CUSTOMS, LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS
SEAL	KELLY ACRES DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA
	PROJECT NO. 20-374A
	DWG. NO. PC320374A
	DESIGN CHKD. BY
	DRAWN BY CHKD. BY
DATE 2020-09-04	SCALE NOT TO SCALE
	SHEET NO. 17 OF 23

**NPDES PERMIT NOTES**

- UPON REDUCTION, LOSS OR FAILURE OF THE BMP, THE PERMITTEE AND CO-PERMITTEE SHALL TAKE IMMEDIATE ACTION TO RESTORE THE BMPS OR PROVIDE AN ALTERNATIVE METHOD OF TREATMENT.
- WHERE E&S BMPS ARE FOUND TO BE INOPERATIVE OR INEFFECTIVE DURING AN INSPECTION, OR ANY OTHER TIME, THE PERMITTEE AND CO-PERMITTEE SHALL IMMEDIATELY CONTACT THE MONTGOMERY COUNTY CONSERVATION DISTRICT, BY PHONE OR PERSONAL CONTACT, FOLLOWED BY THE SUBMISSION OF A WRITTEN REPORT WITHIN 5 DAYS OF THE INITIAL CONTACT.
- PERMITTEES REQUESTING A RENEWAL OF COVERAGE UNDER GENERAL PERMIT MUST SUBMIT TO THE MONTGOMERY COUNTY CONSERVATION DISTRICT AN ADMINISTRATIVELY COMPLETE AND ACCEPTABLE NOI, AT LEAST 90 DAYS PRIOR TO THE EXPIRATION DATE OF THE COVERAGE.
- NOTICE OF TERMINATION. WHERE ALL STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY THAT ARE AUTHORIZED BY THIS PERMIT ARE ELIMINATED, AND BMPS IDENTIFIED IN THE POST CONSTRUCTION STORM WATER MANAGEMENT (PCSM) PLAN HAVE BEEN INSTALLED, THE PERMITTEE OR CO-PERMITTEE OF THE FACILITY MUST SUBMIT A NOTICE OF TERMINATION (NOT) FORM THAT IS SIGNED IN ACCORDANCE WITH PART B.1.C (SIGNATORY REQUIREMENTS) OF THIS PERMIT TO THE MONTGOMERY COUNTY CONSERVATION DISTRICT.

**OPERATION AND MAINTENANCE NOTES:**

- RAIN GARDEN**
  - WHILE VEGETATION IS BEING ESTABLISHED, PRUNING AND WEEDING MAY BE REQUIRED.
  - ONCE EVERY 2 TO 3 YEARS THE ENTIRE AREA SHALL BE MULCHED.
  - RETENTION AREAS SHALL BE INSPECTED TWICE A YEAR FOR EROSION, INVASIVE SPECIES, SEDIMENT BUILDUP, AND VEGETATIVE CONDITIONS. IF FOUND, THE PROBLEM SHALL BE CORRECTED IMMEDIATELY.
  - DURING PERIODS OF EXTENDED DROUGHT, THE RAIN GARDENS SHALL BE WATERED.
  - TREES AND SHRUBS SHALL BE INSPECTED TWICE PER YEAR BY A PROFESSIONAL FOR HEALTH AND REPLACED IF NECESSARY.
  - IF INSPECTIONS FIND STANDING WATER LONGER THAN 72 HOURS AFTER THE END OF THE RAINFALL EVENT, THE OWNER MAY FIND IT DESIRABLE TO CONTACT A PROFESSIONAL TO EVALUATE THE BMP AND DETERMINE A COURSE OF ACTION TO REMEDY STANDING WATER. THE WATER MAY BE PUMPED THROUGH A FILTER BAG OR SIMILAR DEVICE TO DEWATER THE RAIN GARDEN.
  - THE BASIN, BERM AND OUTLET STRUCTURE SHALL BE INSPECTED EVERY TWO YEARS BY AN APPROPRIATELY LICENSED PROFESSIONAL FOR PROPER OPERATION AND STRUCTURAL STABILITY.
  - BASIN REMEDIATION MAY INCLUDE SOIL REPLACEMENT, TREE AND SHRUB PLANTINGS, SLOW-RELEASE DEVICES OR ANY OTHER APPROVED TECHNIQUE.
  - INSPECTIONS SHALL OCCUR 72 HOURS AFTER THE RAINFALL EVEN AND INCLUDE A LOG OF DAILY DEWATERING MEASUREMENTS.
- VEGETATED SWALE**
  - INSPECT AND CORRECT EROSION PROBLEMS, DAMAGE TO VEGETATION AND SEDIMENT AND DEBRIS ACCUMULATION.
  - MOW AND TRIM VEGETATION TO ENSURE SAFETY, AESTHETICS, PROPER SWALE OPERATION OR TO SUPPRESS WEEDS. MOW ONLY WHEN SWALE IS DRY TO AVOID RUTS AND REMOVE LITTER AND DEBRIS PRIOR TO MOWING.
  - WATER DURING DROUGHT CONDITIONS, RESEED BARE AREAS AND CLEAR DEBRIS AND BLOCKAGES.
  - REMEDIATION MAY INCLUDE SOIL REPLACEMENT, TREE AND SHRUB PLANTINGS, SLOW RELEASE DEVICES OR ANY OTHER APPROVED TECHNIQUE.
  - INSPECTIONS SHALL OCCUR 72 HOURS AFTER THE RAINFALL EVENT AND INCLUDE A LOG OF DAILY DEWATERING MEASUREMENTS.
- SOIL AMENDMENT AREAS**
  - THE OVERLYING VEGETATION OF THE AMENDED FEATURES SHOULD BE MAINTAINED IN GOOD CONDITION, BARE SPOTS SHALL BE SEEDED IMMEDIATELY.
  - VEHICULAR ACCESS ON AMENDED AREAS SHOULD BE PROHIBITED, AND CARE SHOULD BE TAKEN TO AVOID EXCESSIVE COMPACTION BY MOWERS. IF ACCESS IS NEEDED, USE OF PERMEABLE, TURF REINFORCEMENT SHOULD BE CONSIDERED.
  - THE AMENDED AREAS SHALL BE INSPECTED EVERY TWO YEARS BY AN APPROPRIATELY LICENSED PROFESSIONAL FOR COMPACTION.
  - ADDITIONAL AMENDMENT MAY BE NECESSARY TO MITIGATE COMPACTION.

**STREAM INTEGRITY PRESERVATION SECTION 102.8(B)(1)**

THE PROPOSED BMPS AS PART OF THE POST CONSTRUCTION STORMWATER MANAGEMENT PLAN HAVE BEEN PLANNED AND PROVIDED IN ORDER TO PRESERVE THE INTEGRITY OF STREAM CHANNELS, AND TO MAINTAIN AND PROTECT THE PHYSICAL, BIOLOGICAL AND CHEMICAL QUALITIES OF THE RECEIVING STREAM.

PREVENT STORMWATER RUNOFF RATE INCREASE SECTION 102.8(B)(2)

THE PROPOSED POST CONSTRUCTION STORMWATER MANAGEMENT PLAN WILL PREVENT AN INCREASE IN STORMWATER RUNOFF THROUGH THE USE OF BMPS AND BY MAINTAINING EXISTING VEGETATION.

MINIMIZE STORMWATER RUNOFF VOLUME INCREASE SECTION 102.8(B)(3)

THE PROPOSED POST CONSTRUCTION STORMWATER MANAGEMENT PLAN WILL MINIMIZE AN INCREASE IN STORMWATER RUNOFF VOLUME THROUGH THE USE OF BMPS AND BY MAINTAINING EXISTING VEGETATION FOR THE 2-YEAR 24-HOUR STORM EVENT.

MINIMIZE IMPERVIOUS AREAS SECTION 102.8(B)(4)

THE EXISTING DRAINAGE FEATURES AND VEGETATION SHALL BE PROTECTED TO THE MAXIMUM EXTENT PRACTICAL. TO ACHIEVE THIS GOAL, THE AREAS ON SITE OUTSIDE OF THE LIMITS OF DISTURBANCE ARE SUBJECT TO THE FOLLOWING CRITERIA:

- AREAS SHALL NOT BE SUBJECT TO GRADING OR MOVEMENT OF EXISTING SOIL.
- EXISTING VEGETATION IN A HEALTHY CONDITION MAY NOT BE REMOVED.
- INVASIVE NON-NATIVE VEGETATION MAY BE REMOVED.
- PRUNING OR OTHER REQUIRED MAINTENANCE OF VEGETATION IS PERMITTED. ADDITIONAL PLANTING IS PERMITTED.
- AREAS SHALL BE PROTECTED AND DELINEATED IN THE FIELD.
- THE AREAS NOT SUBJECT TO GRADING ARE ALSO DELINEATED ON THE POST CONSTRUCTION STORMWATER MANAGEMENT PLAN. IF ANY FUTURE GRADING OR DISTURBANCE OF THESE AREAS OCCURS, SUBSEQUENT STORMWATER MANAGEMENT MUST BE PROVIDED TO ADDRESS DISTURBANCE.

MINIMIZE LAND CLEARING AND GRADING SECTION 102.8(B)(6)

IN ORDER TO MINIMIZE LAND CLEARING AND GRADING, THE AREAS BETWEEN TREE PROTECTION FENCING AND PROPERTY BOUNDARIES ARE SUBJECT TO THE FOLLOWING CRITERIA:

- AREAS SHALL NOT BE SUBJECT TO GRADING OR MOVEMENT OF EXISTING SOIL.
- EXISTING VEGETATION IN A HEALTHY CONDITION MAY NOT BE REMOVED.
- INVASIVE NON-NATIVE VEGETATION MAY BE REMOVED.
- PRUNING OR OTHER REQUIRED MAINTENANCE OF VEGETATION IS PERMITTED. ADDITIONAL PLANTING IS PERMITTED.
- AREAS SHALL BE PROTECTED AND DELINEATED IN THE FIELD.
- THE AREAS NOT SUBJECT TO GRADING ARE ALSO DELINEATED ON THE POST CONSTRUCTION STORMWATER MANAGEMENT PLAN. IF ANY FUTURE GRADING OR DISTURBANCE OF THESE AREAS OCCURS, SUBSEQUENT STORMWATER MANAGEMENT MUST BE PROVIDED TO ADDRESS DISTURBANCE.

MINIMIZE SOIL COMPACTION SECTION 102.8(B)(7)

THE LIMITS OF DISTURBANCE HAVE BEEN DELINEATED AS THE MINIMUM PRACTICAL AREA AND ALL OTHER AREAS SHALL NOT BE DISTURBED AND ARE SUBJECT TO THE FOLLOWING CRITERIA:

- AREAS SHALL NOT BE SUBJECT TO GRADING OR MOVEMENT OF EXISTING SOIL.
- EXISTING VEGETATION IN A HEALTHY CONDITION MAY NOT BE REMOVED.
- INVASIVE NON-NATIVE VEGETATION MAY BE REMOVED.
- PRUNING OR OTHER REQUIRED MAINTENANCE OF VEGETATION IS PERMITTED. ADDITIONAL PLANTING IS PERMITTED.
- AREAS SHALL BE PROTECTED AND DELINEATED IN THE FIELD.
- THE AREAS NOT SUBJECT TO GRADING ARE ALSO DELINEATED ON THE POST CONSTRUCTION STORMWATER MANAGEMENT PLAN. IF ANY FUTURE GRADING OR DISTURBANCE OF THESE AREAS OCCURS, SUBSEQUENT STORMWATER MANAGEMENT MUST BE PROVIDED TO ADDRESS DISTURBANCE.

- AREAS SHALL NOT BE SUBJECT TO GRADING OR MOVEMENT OF EXISTING SOIL.
- EXISTING VEGETATION IN A HEALTHY CONDITION MAY NOT BE REMOVED.
- INVASIVE NON-NATIVE VEGETATION MAY BE REMOVED.
- PRUNING OR OTHER REQUIRED MAINTENANCE OF VEGETATION IS PERMITTED. ADDITIONAL PLANTING IS PERMITTED.
- AREAS SHALL BE PROTECTED AND DELINEATED IN THE FIELD.
- THE AREAS NOT SUBJECT TO GRADING ARE ALSO DELINEATED ON THE POST CONSTRUCTION STORMWATER MANAGEMENT PLAN. IF ANY FUTURE GRADING OR DISTURBANCE OF THESE AREAS OCCURS, SUBSEQUENT STORMWATER MANAGEMENT MUST BE PROVIDED TO ADDRESS DISTURBANCE.

- AREAS SHALL NOT BE SUBJECT TO GRADING OR MOVEMENT OF EXISTING SOIL.
- EXISTING VEGETATION IN A HEALTHY CONDITION MAY NOT BE REMOVED.
- INVASIVE NON-NATIVE VEGETATION MAY BE REMOVED.
- PRUNING OR OTHER REQUIRED MAINTENANCE OF VEGETATION IS PERMITTED. ADDITIONAL PLANTING IS PERMITTED.
- AREAS SHALL BE PROTECTED AND DELINEATED IN THE FIELD.
- THE AREAS NOT SUBJECT TO GRADING ARE ALSO DELINEATED ON THE POST CONSTRUCTION STORMWATER MANAGEMENT PLAN. IF ANY FUTURE GRADING OR DISTURBANCE OF THESE AREAS OCCURS, SUBSEQUENT STORMWATER MANAGEMENT MUST BE PROVIDED TO ADDRESS DISTURBANCE.

**MAINTENANCE PROGRAM SECTION 102.8(F)(10)**

- THE PERMITTEE IS TO PROVIDE PROOF BY THE DESIGN ENGINEER OR ON-SITE INSPECTOR THAT MAJOR DRAINAGE STRUCTURES AND CONTROLS HAVE BEEN CONSTRUCTED AS DESIGNED.
  - THE PERMITTEE IS ULTIMATELY RESPONSIBLE FOR ALL EROSION AND SEDIMENTATION POLLUTION CONTROL AND SITE STABILIZATION. THE PERMITTEE MAY DELEGATE AUTHORITY FOR IMPLEMENTING AND MAINTAINING THE CONTROLS TO INDIVIDUAL LANDOWNERS OR CONTRACTORS. THE ULTIMATE RESPONSIBILITY FOR PROPER INSTALLATION AND MAINTENANCE IS THE PERMITTEE'S.
  - UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT BMP'S MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENT CONTROL BMP'S AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGARDING, RESEEDING, REMULCHING, AND RETENITING, MUST BE DONE IMMEDIATELY. IF EROSION AND SEDIMENT CONTROL BMP'S FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMP'S, OR MODIFICATIONS TO THOSE INSTALLED WILL BE REQUIRED.
  - SEDIMENT SHALL BE REMOVED FROM STORMWATER BMP'S WHEN IT HAS ACCUMULATED TO A DEPTH OF 6 INCHES. COLLECTED SEDIMENT SHALL BE SPREAD ELSEWHERE (IN AREAS UNDER CONSTRUCTION) DURING CONSTRUCTION AND STABILIZATION. SEEDING AND MULCHING OF SLOPES SHALL CONFORM TO THE RECOMMENDATIONS WITHIN OR APPROVED EQUAL TOPSOIL (MINIMUM 6 INCHES) SHALL BE PLACED PRIOR TO SEEDING.
  - THE STORMWATER BMP'S AND WATER QUALITY FEATURES ARE TO BE MAINTAINED AND THE OUTLET STRUCTURES CHECKED AND REPAIRED IF NECESSARY.
  - MAINTENANCE OF THE STORMWATER BMP'S AND OTHER FACILITIES SHALL BE THE RESPONSIBILITY OF THE OWNER OF RECORD. THE OWNER OF RECORD MAY DELEGATE AUTHORITY FOR MAINTAINING THE MAINTENANCE TO OTHER INDIVIDUALS OR CONTRACTORS BUT THE ULTIMATE RESPONSIBILITY FOR PROPER MAINTENANCE IS THE OWNER OF RECORD.
  - VEGETATION SHALL BE MOWED WHENEVER NECESSARY TO MAINTAIN A PLEASING APPEARANCE AND DISCOURAGE WEED GROWTH. ALL LOCAL REGULATIONS WILL BE COMPLIED WITH.
  - AREAS THAT CONTAIN SOD SHALL BE CHECKED VERY CAREFULLY TO ENSURE THAT JOINTS BETWEEN THE SOD STRIPS ARE TIGHT AND SECURE. WHERE JOINT SEPARATION IS IN EVIDENCE, A CAREFUL INSPECTION OF EACH STRIP SHALL BE MADE TO DETERMINE WHETHER UNDERMINING OF THE STRIPS IS OCCURRING. IF IT IS, THE STRIPS SHALL BE ROLLED UP, THE SUBSURFACE SHALL BE FILLED AND GRADED AS REQUIRED AND THE SOD STRIPS SHALL BE RE-LAID WITH TIGHT JOINTS AND PEGGING.
  - SEEDED AREAS THAT HAVE WASHED AWAY SHALL BE FILLED AND GRADED AS NECESSARY AND THEN RESEDED. A BURLAP OR STRAW COVER WILL BE APPLIED AT A RATE OF 3 TONS/ACRE TO RETAIN THE SEED UNTIL IT HAS A CHANCE TO ROOT PROPERLY.
  - THE ABOVE PROCEDURE SHALL BE REPEATED AFTER EACH SIZEABLE STORM UNTIL NO MORE SIGNS OF EROSION ARE EVIDENT. AT WEEKLY INTERVALS THEREAFTER, INSPECTION AND NECESSARY CLEANING WILL BE DONE. PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, AND RESEEDING AFTER EVERY MAJOR RAINFALL EVENT.
  - INSPECTIONS SHALL BE LOGGED ONTO DEP FORM 3800-FM-BCW027D REV. 12/2019 AND KEPT ONSITE AT ALL TIMES.
- EXISTING/ PROPOSED RIPARIAN BUFFER
- \*THERE ARE NO RIPARIAN BUFFERS REGULATED BY CHAPTER 102 PRESENT OR PROPOSED AT THIS SITE BY THIS PROJECT.
- EXISTING/ PROPOSED RIPARIAN FOREST BUFFERS SECTION 102.8 (F)(14)
- \*THERE ARE NO RIPARIAN FOREST BUFFERS REGULATED BY CHAPTER 102 PRESENT OR PROPOSED AT THIS SITE BY THIS PROJECT. MINISTER CREEK AND UNT TO MINISTER CREEK ARE IMPAIRED BY SILTATION.

**RAIN GARDEN CONSTRUCTION SEQUENCE:**

- ANY SEDIMENT ENTERING THE BMP SHALL BE REMOVED WITH LIGHT EQUIPMENT. THE UNDERLYING SOIL SHALL BE SCARIFIED A MINIMUM OF TWELVE INCHES WITH A YORK RAKE, ROTOTILLER OR OTHER SUITABLE EQUIPMENT. A LICENSED PROFESSIONAL SHALL PROVIDE OVERSIGHT DURING THE SCARIFYING OF THE SUBGRADE.
  - THE TOPSOIL AND SUBSURFACE SOIL SHALL BE STRIPPED AND BE PLACED WHERE SHOWN ON THE PLAN.
  - EXCAVATE THE BERM, REMOVE THE TEMPORARY OUTLET STRUCTURE AND PIPE, AND PLACE AND COMPACT THE FILL FOR THE BERM. THE STRUCTURAL SOIL SHALL BE PLACED WHERE SHOWN ON THE PLAN.
  - INSTALL THE PERMANENT OUTLET STRUCTURE AND OUTLET PIPE. A LICENSED PROFESSIONAL SHALL PROVIDE OVERSIGHT DURING THE BACKFILLING OF THE OUTLET PIPE.
  - STABILIZE THE ENTIRE OUTSIDE OF THE BERM AND ON THE INSIDE OF THE BERM WITH TOPSOIL.
  - IMMEDIATELY APPLY THE PERMANENT SEEDING AND MULCH FOR THE ENTIRE AREA. A SLOPE PROTECTION BLANKET SHALL BE INSTALLED WHERE SHOWN ON THE PLAN AND ALL SLOPES GREATER THAN 3:1.
  - AMENDED TOPSOIL PER THE PROCEDURE OUTLINED ON THE PLANS SHALL BE INSTALLED ON THE INSIDE OF THE RAIN GARDEN, PERMANENTLY SEEDED AND MULCHED. A SLOPE PROTECTION BLANKET SHALL BE INSTALLED WHERE SHOWN ON THE PLAN AND ALL SLOPES GREATER THAN 3:1.
- RAIN GARDEN/MRC CONSTRUCTION SEQUENCE:
- ANY SEDIMENT ENTERING THE BMP SHALL BE REMOVED WITH LIGHT EQUIPMENT. THE UNDERLYING SOIL SHALL BE SCARIFIED A MINIMUM OF TWELVE INCHES WITH A YORK RAKE, ROTOTILLER OR OTHER SUITABLE EQUIPMENT. A LICENSED PROFESSIONAL SHALL PROVIDE OVERSIGHT DURING THE SCARIFYING OF THE SUBGRADE.
  - THE TOPSOIL AND SUBSURFACE SOIL SHALL BE STRIPPED AND BE PLACED WHERE SHOWN ON THE PLAN.
  - EXCAVATE THE BERM, REMOVE THE TEMPORARY OUTLET STRUCTURE AND PIPE, AND PLACE AND COMPACT THE FILL FOR THE BERM. THE STRUCTURAL SOIL SHALL BE PLACED WHERE SHOWN ON THE PLAN.
  - INSTALL THE PERFORATED UNDERDRAIN PIPE.
  - INSTALL THE PERMANENT OUTLET STRUCTURE AND OUTLET PIPE. A LICENSED PROFESSIONAL SHALL PROVIDE OVERSIGHT DURING THE BACKFILLING OF THE OUTLET PIPE.
  - STABILIZE THE ENTIRE OUTSIDE OF THE BERM AND ON THE INSIDE OF THE BERM WITH TOPSOIL.
  - IMMEDIATELY APPLY THE PERMANENT SEEDING AND MULCH FOR THE ENTIRE AREA. A SLOPE PROTECTION BLANKET SHALL BE INSTALLED WHERE SHOWN ON THE PLAN AND ALL SLOPES GREATER THAN 3:1.
  - AMENDED TOPSOIL PER THE PROCEDURE OUTLINED ON THE PLANS SHALL BE INSTALLED ON THE INSIDE OF THE RAIN GARDEN, PERMANENTLY SEEDED AND MULCHED. A SLOPE PROTECTION BLANKET SHALL BE INSTALLED WHERE SHOWN ON THE PLAN AND ALL SLOPES GREATER THAN 3:1.

**RECYCLING PROCEDURES SECTION 102.8(F)(11)**

THE POTENTIAL OR ANTICIPATED POST CONSTRUCTION WASTES FOR THIS PROJECT INCLUDE THOSE THAT ARE INCIDENTAL TO YARD MAINTENANCE, SUCH AS LAWN TRIMMINGS AND LEAVES, AS WELL AS THOSE ASSOCIATED WITH STORMWATER EVENTS, SUCH AS FALLEN BRANCHES.

ALL POST CONSTRUCTION WASTES, GRASS TRIMMINGS, LEAVES, BRANCHES, ROOTS, SOIL, AND ANY MATERIALS DEEMED UNUSABLE SHALL BE DISPOSED OF. THE OPERATOR/RESPONSIBLE PERSON SHALL REMOVE FROM THE SITE, RECYCLE, OR DISPOSE OF ALL MATERIALS AND WASTES IN ACCORDANCE WITH THE PA DEP'S SOLID WASTE REGULATIONS (25 PA CODE 260.1 ET SEQ., 271.1 ET SEQ., AND 287.1 ET SEQ.) AND/OR ANY ADDITIONAL LOCAL, STATE OR FEDERAL REGULATIONS. WASTE MATERIALS (USED OR UNUSED) SHALL NOT ILLEGALLY BE BURNED, BURIED, DUMPED OR DISCHARGED AT THE SITE.

**POTENTIAL POLLUTION IDENTIFICATION SECTION 102.8(F)(12)**

THE GEOLOGICAL FORMATIONS ON-SITE ARE SUCH THAT THE POLLUTION POTENTIAL IS POSSIBLE AND APPROPRIATE ACTIONS ARE REQUIRED. THE SOILS HAVE A POTENTIAL FOR EROSION. THE EROSION FROM THE SOILS COULD POTENTIALLY CAUSE WATER POLLUTION AND TO MINIMIZE THIS POTENTIAL THE EROSION AND SEDIMENT CONTROL BMPS MENTIONED ABOVE ARE TO BE PROVIDED.

**OTHER CONTROLS TO MINIMIZE RUNOFF SECTION 102.8(B)(8)**

NO OTHER MEASURES AND CONTROLS SHALL BE UTILIZED TO PREVENT OR MINIMIZE THE GENERATION OF ADDITIONAL STORMWATER.

**UTILITY LINE NOTES:**

- TRENCH PLUGS SHALL BE INSTALLED ALONG UTILITY LINES THAT ARE ADJACENT TO STORMWATER BMPS.
- APPROPRIATE TRENCHING EQUIPMENT SHALL BE USED TO INSTALL UNDERGROUND UTILITY WIRES WITHIN WOODED AREA TO PREVENT ANY TREE REMOVAL.

**BMP CRITICAL STAGES:**

- PRECONSTRUCTION MEETING
- DURING THE SCARIFICATION OF THE UNDERLYING SOIL
- DURING CONCRETE CRADLE, OUTLET STRUCTURE, AND PIPE INSTALLATION
- DURING SOIL AMENDMENT INSTALLATION.

**ANTICIPATED BMP INSTALLATION SEQUENCE**

- RAIN GARDEN 2
- RAIN GARDEN 3
- RAIN GARDEN/MRC 5
- RAIN GARDEN/MRC 4
- RAIN GARDEN 1

**BMP 6.7.3 SOIL AMENDMENT & RESTORATION**

- SUB-SOILING TO RELIEVE COMPACTION BEFORE THE TIME THE COMPOST IS PLACED OR PREFERABLY WHEN EXCAVATION IS COMPLETED, THE SUBSOIL SHALL BE IN A LOOSE, FRIABLE CONDITION TO A DEPTH OF 20 INCHES BELOW FINAL TOPSOIL GRADE AND THERE SHALL BE NO EROSION RILLS OR WASHOUTS IN THE SUBSOIL SURFACE EXCEEDING 3/16 INCHES IN DEPTH. TO ACHIEVE THIS CONDITION, SUBSOILING, RIPPING, OR SCARIFICATION OF THE SUBSOIL WILL BE REQUIRED AS DIRECTED BY THE OWNER'S REPRESENTATIVE, WHEREVER THE SUBSOIL HAS BEEN COMPACTED BY EQUIPMENT OPERATION OR HAS BECOME DRIED OUT AND CRUSTED, AND WHERE NECESSARY TO OBLITERATE EROSION RILLS. SUB-SOILING SHALL BE REQUIRED TO REDUCE SOIL COMPACTION IN ALL AREAS WHERE PLANT ESTABLISHMENT IS PLANNED. SUB-SOILING SHALL BE PERFORMED BY THE PRIME OR EXCAVATING CONTRACTOR AND SHALL OCCUR BEFORE COMPOST PLACEMENT.
  - SUBSOILED AREAS SHALL BE LOOSENEED TO LESS THAN 1400 KPA (200 PSI) TO A DEPTH OF 20 INCHES BELOW FINAL TOPSOIL GRADE. WHEN DIRECTED BY THE OWNER'S REPRESENTATIVE, THE CONTRACTOR SHALL VERIFY THAT THE SUB-SOILING WORK CONFORMS TO THE SPECIFIED DEPTH.
  - SUB-SOILING SHALL FORM A TWO-DIRECTIONAL GRID. CHANNELS SHALL BE CREATED BY A COMMERCIALY AVAILABLE MULTI-SHANKED, PARALLELOGRAM IMPLEMENT (SOLID-SHANK RIPPER). THE EQUIPMENT SHALL BE CAPABLE OF EXERTING A PENETRATION FORCE NECESSARY FOR THE SITE. NO DISC CULTIVATORS CHISEL PLOWS, OR SPRING-LOADED EQUIPMENT WILL BE ALLOWED. THE GRID CHANNELS SHALL BE SPACED A MINIMUM OF 12 INCHES TO A MAXIMUM OF 36 INCHES APART, DEPENDING ON EQUIPMENT, SITE CONDITIONS, AND THE SOIL MANAGEMENT PLAN. THE CHANNEL DEPTH SHALL BE A MINIMUM OF 20 INCHES OR AS SPECIFIED IN THE SOIL MANAGEMENT PLAN. IF SOILS ARE SATURATED, THE CONTRACTOR SHALL DELAY OPERATIONS UNTIL THE SOIL WILL NOT HOLD A BALL WHEN SQUEEZED. ONLY ONE PASS SHALL BE PERFORMED ON ERODIBLE SLOPES GREATER THAN 1 VERTICAL TO 3 HORIZONTAL. WHEN ONLY ONE PASS IS USED, WORK SHOULD BE AT RIGHT ANGLES TO THE DIRECTION OF SURFACE DRAINAGE, WHENEVER PRACTICAL.
  - EXCEPTIONS TO SUB-SOILING INCLUDE AREAS WITHIN THE DRIP LINE OF ANY EXISTING TREES, OVER UTILITY INSTALLATIONS WITHIN 30 INCHES OF THE SURFACE, WHERE TRENCHING/DRAINAGE LINES ARE INSTALLED, WHERE COMPACTION IS BY DESIGN (ABUTMENTS, FOOTINGS, OR IN SLOPES), AND ON INACCESSIBLE SLOPES, AS APPROVED BY THE OWNER'S REPRESENTATIVE. IN CASES WHERE EXCEPTIONS OCCUR, THE CONTRACTOR SHALL OBSERVE A MINIMUM SETBACK OF 20 FEET OR AS DIRECTED BY THE OWNER'S REPRESENTATIVE. ARCHAEOLOGICAL CLEARANCES MAY BE REQUIRED IN SOME INSTANCES.
- COMPOST SOIL AMENDMENT INSTALLATION
  - SPREAD 2-3 INCHES OF APPROVED COMPOST ON EXISTING SOIL. TILL ADDED SOIL INTO EXISTING SOIL WITH A ROTARY TILLER THAT IS SET TO A DEPTH OF 6 INCHES. ADD AN ADDITIONAL 4 INCHES OF APPROVED COMPOST TO BRING THE AREA UP TO GRADE.
  - AFTER PERMANENT PLANTING/SEEDING, 2-3 INCHES OF COMPOST


**SOIL AMENDMENT AND RESTORATION:**

SOIL AMENDMENT AND RESTORATION SHALL BE DONE BY MIXING THE STOCKPILED EXISTING ON-SITE TOPSOIL WITH COMPOST BEFORE REDISTRIBUTING THE TOPSOIL. THE RATIO SHALL BE 2 PARTS TOPSOIL AND 1 PART COMPOST. THE COMPOST SHALL MEET THE STANDARDS IN TABLE 4.2:

TABLE 4.2 - COMPOST STANDARDS	
ORGANIC MATTER CONTENT (WEIGHT BASIS)	25%-100% (DRY ELONGATED)
ORGANIC PORTION	FIBROUS AND
pH	5.5 - 8.5
MOISTURE CONTENT	30% - 60%
PARTICLE SIZE THROUGH 3/8" SIEVE	30% - 50% PASS
SOLUBLE SALT CONCENTRATION (mmhos/cm) MAXIMUM	5.0 dS/m

NO.	REVISION	DATE	BY	APP.
13	REVISED PER BHMA EMAIL DATED MAY 17, 2023	2023-05-18	SSR	BOB
12	REVISED PER PENNING REVIEW LETTER DATED APRIL 21, 2023 AND MCPC LETTER DATED APRIL 18, 2023	2023-05-03	SSR	BOB
11	REVISED PER PENNING REVIEW LETTER DATED MARCH 9, 2022 AND FOR FINAL PLAN	2023-03-07	SSR	BOB
10	REVISED PER MCDD EMAIL DATED MARCH 2, 2023	2023-03-02	SSR	BOB
9	REVISED PER MCDD REVIEW LETTER DATED JANUARY 19, 2023	2023-01-20	SSR	BOB
8	REVISED PER MCDD REVIEW LETTER DATED NOVEMBER 15, 2022	2022-12-09	SSR	BOB
7	REVISED PER MCDD REVIEW LETTER DATED SEPTEMBER 9, 2022	2022-09-22	SSR	BOB
6	REVISED PER MCDD EMAIL DATED JULY 28, 2022	2022-07-29	JAK	BOB
5	REVISED PER MCDD REVIEW LETTER DATED JUNE 29, 2022	2022-06-30	SSR	BOB
4	REVISED PER MCDD REVIEW LETTER DATED APRIL 14, 2022	2022-05-24	SSR	BOB
3	REVISED PER MCDD REVIEW LETTER DATED JANUARY 18, 2022	2022-03-03	SSR	BOB
2	REVISED PER SDC REVIEW LETTER DATED JANUARY 24, 2022	2022-02-01	SSR	BOB
1	REVISED PER PENNING REVIEW LETTER DATED NOVEMBER 9, 2021 AND MCDD REVIEW LETTER DATED OCTOBER 19, 2021	2021-12-11	SSR	BOB

CLIENT		SUBJECT	
R.B. ASHLEY CUSTOMS, LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465		POST CONSTRUCTION STORMWATER MANAGEMENT NARRATIVE	
SEAL		KELLY ACRES	
		DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA	
		PROJECT NO.	20-374A
		DWG. NO.	PC420374A
		SHEET NO.	18 OF 23
		DESIGN	BOB
		CHKD. BY	BOB
		DRAWN BY	WJD
		CHKD. BY	
		DATE	2020-09-04
		SCALE	NOT TO SCALE



**Construction Sequence Notes**

- 1. All earth disturbances, including clearing and grubbing as well as cuts and fills, be done in accordance with the approved E&S plan. A copy of the approved drawings (stamped, signed, and dated by the Montgomery County Conservation District) must be available at the project site at all times. The Montgomery County Conservation District shall be notified of any changes to the approved plan prior to implementation of those changes. The Montgomery County Conservation District may require a written submittal of those changes for review.
2. Each stage shall be completed in compliance with Chapter 102 regulations before any following stage is initiated. Clearing and grubbing shall be limited only to those areas described in each stage.
3. At least seven (7) days before starting any earth disturbance activities, the O/RP shall invite all contractors involved in that activity, the landowner, all appropriate municipal officials, the erosion and sediment control plan designer and the Montgomery County Conservation District to a pre-construction meeting.
4. At least three (3) days before starting any earth disturbance activity, all O/RPs involved in that activity shall notify the Pennsylvania One Call System Inc. at 1-800-242-1776 to determine underground utilities' locations.
5. All earth disturbance activities shall proceed in accordance with the sequence provided on the plan drawings. Deviation from that sequence must be approved in writing from the Montgomery County Conservation District.
6. Clearing, grubbing, and topsoil stripping shall be limited to those areas described in each stage of construction sequence. General site clearing, grubbing, and topsoil stripping may not commence in any stage or phase of the project until the E&S BMPs specified by the BMP sequence for that stage or phase have been installed and are functioning as described in this E&S plan.
7. Upon temporary cessation or completion of an earth disturbance activity or any stage or phase of an activity where a cessation of earth disturbance activities exceeds 4 days, the operator shall immediately seed and mulch or otherwise protect the site from accelerated erosion and sedimentation pending further earth disturbance activities. During non-germinating periods, mulch must be applied at the specified rates. Disturbed areas which are not at finished grade and which will be re-disturbed within 1 year may be stabilized in accordance with temporary seeding specifications. Disturbed areas, which are either at finished grade or will not be re-disturbed within 1 year, must be stabilized in accordance with permanent seeding specifications.
8. All building material and wastes must be removed from the site and recycled in accordance with DEP's Solid Waste Regulations (25 PA Code 260.1, et seq., 271.1 et seq. and 287.1 et seq.), and/or any additional local, state, or federal regulations. No building materials (used or unused) or waste materials shall be burned, buried, dumped, or discharged at the site.
9. Before disposing of soil or receiving borrow for the site, the operator must assure that each spoil or borrow area has an erosion and sediment control plan approved by the local County Conservation District or the Department of Environmental Protection, and which is fully implemented and maintained according to Chapter 102 regulations prior to being activated. The operator shall also notify the Montgomery County Conservation District in writing of all receiving spoil and borrow areas when they have been identified.
10. The operator is responsible for ensuring that any material brought to the site is clean fill. Form FP-001 must be retained by the property owner for any fill material affected by a spill or release of a regulated substance but qualifying as clean fill due to analytical testing.
The general sequence of construction is as follows. If any modifications are necessary or desired by the O/RP, they must be approved by the Montgomery County Conservation District prior to implementing the changes.

- 1. The limit of disturbance (LOD) and extent of protected sensitive features including woods, steep slopes, floodplain, minimized disturbance and reduced grading shall be marked with survey stakes, posts and rope, construction fence or some other acceptable material prior to disturbance activities. The protected sensitive feature areas shown on the PCSM plans shall not be disturbed during construction except for temporary impacts for mitigation and restoration efforts.
2. Clear, grub, and install the Rock Construction Entrance area on Lot 4 for staging area.
3. Install tree and infiltration/BMP area protection fencing at the locations shown on the plan. The area of the infiltration basin BMP's shall not be compacted or receive excessive heavy equipment traffic. The area shall be protected by using tape, fencing or other suitable method.
4. Any areas of tree canopy protections shall not be compacted or receive excessive heavy equipment traffic. The area shall be protected by using tape, fencing or other suitable method.
5. Clear trees to be removed along Buchert Road and install the compost filter socks immediately after clearing in the locations shown on the plan for all disturbed areas. Clear trees only, no grubbing shall occur during this step until the downslope socks are in place.
6. Install offsite rip rap apron. The apron may only be installed with hand tools to prevent disturbance.

Upon the installation or stabilization of all perimeter sediment control BMP's and at least 3 days prior to proceeding with the bulk earth disturbance activities, the permittee or co-permittee shall provide notification to the Montgomery County Conservation District.

- 7. Install the sewer line.
8. Begin construction of the Sediment Trap 1 using the following procedure:
• Install Compost Filter Socks
• Grub the Sediment Trap area.
• The topsoil shall be stripped and be placed in the areas designated on the plan.
• Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
• Install and backfill the outlet structure and outlet pipe from the end section to the outlet structure starting at the downstream end and working uphill. Immediately install the concrete cradle. The permanent outlet structure shall be installed in the Sediment trap. Joints shall be water tight. Outlet shall be capped while sediment trap is in operation. A Licensed Professional Engineer shall provide oversight during the backfilling of the outlet pipe.
• Stabilize the cleanout stake and mark the sediment cleanout elevation on the stake.
• Stabilize the entire outside of the berm with amended soils and on the inside of the sediment trap above the cleanout elevation with topsoil.
• Immediately apply the permanent seeding and mulch for the entire outside of the berm and above the sediment cleanout elevation on the inside of the basin. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1. The emergency spillway shall have the North American Green Blanket P300 installed.
9. Construction of each lot may begin at this time. They may be constructed in any order.

**Lot 1**

- 10. Install the Rock Construction Entrance, clear and grub as needed.
11. Install the Compost Filter Sock 1 in the location shown on the plan.
12. Clear and grub for all disturbed areas.
13. Strip topsoil, stockpile and immediately stabilize with temporary seed and mulch.
14. Install the concrete washout area where shown on the Erosion Control Plans per the details for the Filtrrex® Filter Ring prior to starting any concrete work on the site.
15. The house, driveway, and site grading may begin using the following procedure:
• The contractor shall ensure that the runoff from all possible earth disturbance activities shall constantly be directed towards compost filter socks.
• Remove and grub the root material.
• Strip the topsoil from the proposed disturbed area.
• Place the topsoil where shown on the plan and seed and mulch the area.
• Place fill and compact to proposed grades starting downhill working uphill.
• The subgrade shall be rolled and the stone placed where shown on the plan for the driveway.
• Begin house construction. Excavated material shall be placed on the subsoil stockpile, seeded, and mulched.
• Begin installing the utilities using the following procedure. The utility lines may be installed simultaneously if desired by the O/RP:
o The sewer laterals.
• The water service line.
• The gas, electric, telephone and cable lines, if proposed, shall be installed. The open trenches shall be backfilled and stabilized at the end of each day.

- 16. Stabilize the disturbed areas on the site with a minimum of six inches of topsoil, permanently seed and mulch. A slope protection blanket shall be installed where shown on the plan.
17. No more than 15,000 square feet of disturbed area shall reach final grade before initiating seeding and mulching operations on areas proposed to be lawn areas.
18. Pave areas shown on the plans and stabilize any disturbed areas any time after this step.
19. Install landscaping and tress in areas of lawn shown on the plans using light tracked equipment. Do not run equipment over areas of soil amendment to avoid compaction. Stabilize all disturbed areas with seed and mulch.

**Lot 2**

- 20. Install the Rock Construction Entrance, clear and grub as needed.
21. Install the Compost Filter Socks 2 and 18 in the locations shown on the plan.
22. Clear and grub for all disturbed areas.
23. Strip topsoil, stockpile and immediately stabilize with temporary seed and mulch.
24. Install the concrete washout area where shown on the Erosion Control Plans per the details for the Filtrrex® Filter Ring prior to starting any

- concrete work on the site.
25. Install Vegetated Swale 1 and permanently stabilize. Rock filter and rip rap apron shall be installed during Sediment Trap 1 operation.
26. The house, driveway, and site grading may begin using the following procedure:
• The contractor shall ensure that the runoff from all possible earth disturbance activities shall constantly be directed towards compost filter socks.
• Remove and grub the root material.
• Strip the topsoil from the proposed disturbed area.
• Place the topsoil where shown on the plan and seed and mulch the area.
• Place fill and compact to proposed grades starting downhill working uphill.
• The subgrade shall be rolled and the stone placed where shown on the plan for the driveway.
• Begin house construction. Excavated material shall be placed on the subsoil stockpile, seeded, and mulched.
• Begin installing the utilities using the following procedure. The utility lines may be installed simultaneously if desired by the O/RP:
o The sewer laterals.
• The water service line.
• The gas, electric, telephone and cable lines, if proposed, shall be installed. The open trenches shall be backfilled and stabilized at the end of each day.
27. Stabilize the disturbed areas on the site with a minimum of six inches of topsoil, permanently seed and mulch. A slope protection blanket shall be installed where shown on the plan.
28. No more than 15,000 square feet of disturbed area shall reach final grade before initiating seeding and mulching operations on areas proposed to be lawn areas.
29. Pave areas shown on the plans and stabilize any disturbed areas any time after this step.
30. After upslope areas are stabilized (a minimum of 70% uniform perennial vegetative cover), install Rain Garden 2. A Licensed Professional Engineer shall be present for this step.
• Any sediment entering the BMP shall be removed with light equipment. The underlying soil shall be scarified a minimum of twelve inches with a york rake, rototiller or other suitable equipment. A Licensed professional shall provide oversight during the scarifying of the subgrade.
• The topsoil shall be stripped and be placed where shown on the plan.
• Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
• Install the outlet structure and outlet pipe. A Licensed Professional shall provide oversight during the backfilling of the outlet pipe.
• Stabilize the entire outside of the berm and on the inside of the berm with topsoil.
• Immediately apply the permanent seeding and mulch for the entire area. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
• Install amended topsoil, per the procedure outlined on the plans, on the inside of the infiltration basin, permanently seeded and mulched. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
• Install rain garden plantings.

**Lot 3**

- 1. Install the Rock Construction Entrance, clear and grub as needed.
2. Install the Compost Filter Socks 3, 4, 5, 16, and 17 in the locations shown on the plan.
3. Clear and grub for all disturbed areas.
4. Strip topsoil, stockpile and immediately stabilize with temporary seed and mulch.
5. Install the concrete washout area where shown on the Erosion Control Plans per the details for the Filtrrex® Filter Ring prior to starting any concrete work on the site.
6. Install Vegetated Swale 2 and permanently stabilize. Rock filter and rip rap apron shall be installed during Sediment Trap 2 operation.
7. The house, driveway, and site grading may begin using the following procedure:
• The contractor shall ensure that the runoff from all possible earth disturbance activities shall constantly be directed towards compost filter socks.
• Remove and grub the root material.
• Strip the topsoil from the proposed disturbed area.
• Place the topsoil where shown on the plan and seed and mulch the area.
• Place fill and compact to proposed grades starting downhill working uphill.
• The subgrade shall be rolled and the stone placed where shown on the plan for the driveway.
• Begin house construction. Excavated material shall be placed on the subsoil stockpile, seeded, and mulched.
• Begin installing the utilities using the following procedure. The utility lines may be installed simultaneously if desired by the O/RP:
o The sewer laterals.
• The water service line.
• The gas, electric, telephone and cable lines, if proposed, shall be installed. The open trenches shall be backfilled and stabilized at the end of each day.
8. Stabilize the disturbed areas on the site with a minimum of six inches of topsoil, permanently seed and mulch. A slope protection blanket shall be installed where shown on the plan.
9. No more than 15,000 square feet of disturbed area shall reach final grade before initiating seeding and mulching operations on areas proposed to be lawn areas.
10. Pave areas shown on the plans and stabilize any disturbed areas any time after this step.

- 11. After upslope areas are stabilized (a minimum of 70% uniform perennial vegetative cover), install Rain Garden 3. A Licensed Professional Engineer shall be present for this step.
• Any sediment entering the BMP shall be removed with light equipment. The underlying soil shall be scarified a minimum of twelve inches with a york rake, rototiller or other suitable equipment. A Licensed professional shall provide oversight during the scarifying of the subgrade.
• The topsoil shall be stripped and be placed where shown on the plan.
• Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
• Install the outlet structure, outlet pipe, and concrete cradle. A Licensed Professional shall provide oversight during the backfilling of the outlet pipe.
• Stabilize the entire outside of the berm and on the inside of the berm with topsoil.
• Immediately apply the permanent seeding and mulch for the entire area. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
• Install amended topsoil, per the procedure outlined on the plans, on the inside of the infiltration basin, permanently seeded and mulched. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
• Install rain garden plantings.

**Lot 4**

- 42. Install the Rock Construction Entrance, clear and grub as needed.
43. Install the Compost Filter Socks 6-9 in the locations shown on the plan.
44. Clear and grub for all disturbed areas.
45. Strip topsoil, stockpile and immediately stabilize with temporary seed and mulch.
46. Install the concrete washout area where shown on the Erosion Control Plans per the details for the Filtrrex® Filter Ring prior to starting any concrete work on the site.
47. The house, driveway, and site grading may begin using the following procedure:
• The contractor shall ensure that the runoff from all possible earth disturbance activities shall constantly be directed towards compost filter socks.
• Remove and grub the root material.
• Strip the topsoil from the proposed disturbed area.
• Place the topsoil where shown on the plan and seed and mulch the area.
• Place fill and compact to proposed grades starting downhill working uphill.
• The subgrade shall be rolled and the stone placed where shown on the plan for the driveway.
• Begin house construction. Excavated material shall be placed on the subsoil stockpile, seeded, and mulched.
• Begin installing the utilities using the following procedure. The utility lines may be installed simultaneously if desired by the O/RP:
o The sewer laterals.
• The water service line.
• The gas, electric, telephone and cable lines, if proposed, shall be installed. The open trenches shall be backfilled and stabilized at the end of each day.
48. Stabilize the disturbed areas on the site with a minimum of six inches of topsoil, permanently seed and mulch. A slope protection blanket shall be installed where shown on the plan.
49. No more than 15,000 square feet of disturbed area shall reach final grade before initiating seeding and mulching operations on areas proposed to be lawn areas.
50. Pave areas shown on the plans and stabilize any disturbed areas any time after this step.
51. Install landscaping and tress in areas of lawn shown on the plans using light tracked equipment. Do not run equipment over areas of soil amendment to avoid compaction. Stabilize all disturbed areas with seed and mulch.

**Lot 5**

- 52. Install the Rock Construction Entrance, clear and grub as needed.
53. Install the Compost Filter Socks 10-15 in the locations shown on the plan.
54. Clear and grub for all disturbed areas.
55. Begin construction of the Sediment Trap 3 using the following procedure:
• Grub the Sediment Trap area.
• The topsoil shall be stripped and be placed in the areas designated on the plan.

- Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
• Install and backfill the outlet structure and outlet pipe from the end section to the outlet structure starting at the downstream end and working uphill. Immediately install the concrete cradle. The permanent outlet structure shall be installed in the Sediment trap. Joints shall be water tight. Outlet shall be capped while Sediment Trap 3 is in operation. The underdrain shall not be installed at this time. A Licensed Professional shall provide oversight during the backfilling of the outlet pipe.
• Stabilize the entire outside of the berm with amended soils and on the inside of the sediment trap above the cleanout elevation with topsoil.
• Immediately apply the permanent seeding and mulch for the entire outside of the berm and above the sediment cleanout elevation on the inside of the basin. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1. The emergency spillway shall have the North American Green Blanket P300 installed.
56. Strip topsoil, stockpile and immediately stabilize with temporary seed and mulch.
57. Install the concrete washout area where shown on the Erosion Control Plans per the details for the Filtrrex® Filter Ring prior to starting any concrete work on the site.
58. The house, driveway, and site grading may begin using the following procedure:
• The contractor shall ensure that the runoff from all possible earth disturbance activities shall constantly be directed towards compost filter socks.
• Remove and grub the root material.
• Strip the topsoil from the proposed disturbed area.
• Place the topsoil where shown on the plan and seed and mulch the area.
• Place fill and compact to proposed grades starting downhill working uphill.
• The subgrade shall be rolled and the stone placed where shown on the plan for the driveway.
• Begin house construction. Excavated material shall be placed on the subsoil stockpile, seeded, and mulched.
• Begin installing the utilities using the following procedure. The utility lines may be installed simultaneously if desired by the O/RP:
o The sewer laterals.
• The water service line.
• The gas, electric, telephone and cable lines, if proposed, shall be installed. The open trenches shall be backfilled and stabilized at the end of each day.

- 61. Stabilize the disturbed areas on the site with a minimum of six inches of topsoil, permanently seed and mulch. A slope protection blanket shall be installed where shown on the plan.
62. No more than 15,000 square feet of disturbed area shall reach final grade before initiating seeding and mulching operations on areas proposed to be lawn areas.
63. Pave areas shown on the plans and stabilize any disturbed areas any time after this step.
64. After upslope areas are stabilized (a minimum of 70% uniform perennial vegetative cover), install MRC 5. A Licensed Professional Engineer shall be present for this step.
• Any sediment entering the BMP shall be removed with light equipment. The underlying soil shall be scarified a minimum of twelve inches with a york rake, rototiller or other suitable equipment. A Licensed professional shall provide oversight during the scarifying of the subgrade.
• The topsoil shall be stripped and be placed where shown on the plan.
• Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
• Install the underdrain. A Licensed Professional shall provide oversight during the backfilling of the outlet pipe.
• Stabilize the entire outside of the berm and on the inside of the berm with topsoil.
• Immediately apply the permanent seeding and mulch for the entire area. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
• Install amended topsoil, per the procedure outlined on the plans, on the inside of the infiltration basin, permanently seeded and mulched. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
• Install Rain Garden plantings.
• Install landscaping and tress in areas of lawn shown on the plans using light tracked equipment. Do not run equipment over areas of soil amendment to avoid compaction. Stabilize all disturbed areas with seed and mulch.


- 65. After Lots 1 and 2 are stabilized (a minimum of 70% uniform perennial vegetative cover), install Rain Garden 1. A Licensed Professional Engineer shall be present for this step.
• Any sediment entering the BMP shall be removed with light equipment. The underlying soil shall be scarified a minimum of twelve inches with a york rake, rototiller or other suitable equipment. A Licensed professional shall provide oversight during the scarifying of the subgrade.
• The topsoil shall be stripped and be placed where shown on the plan.
• Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
• Stabilize the entire outside of the berm and on the inside of the berm with topsoil.
• Immediately apply the permanent seeding and mulch for the entire area. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
• Install amended topsoil, per the procedure outlined on the plans, on the inside of the infiltration basin, permanently seeded and mulched. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
• Install Rain Garden plantings.
67. After Lots 3 and 4 are stabilized (a minimum of 70% uniform perennial vegetative cover), install MRC 4. A Licensed Professional Engineer shall be present for this step.
• Any sediment entering the BMP shall be removed with light equipment. The underlying soil shall be scarified a minimum of twelve inches with a york rake, rototiller or other suitable equipment. A Licensed professional shall provide oversight during the scarifying of the subgrade.
• The topsoil shall be stripped and be placed where shown on the plan.
• Excavate the berm and place and compact the fill for the berm. The structural soil shall be placed where shown on the plan.
• Install the underdrain. A Licensed Professional shall provide oversight during the backfilling of the outlet pipe.
• Stabilize the entire outside of the berm and on the inside of the berm with topsoil.
• Immediately apply the permanent seeding and mulch for the entire area. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
• Install amended topsoil, per the procedure outlined on the plans, on the inside of the infiltration basin, permanently seeded and mulched. A slope protection blanket shall be installed where shown on the plan and all slopes greater than 3:1.
• Install Rain Garden plantings

68. When all of the disturbances on the site are completely stabilized (a minimum of 70% uniform perennial vegetative cover), all temporary BMP's should be removed from the site and any disturbance created when removing them shall immediately be permanently seeded and mulched. Compost filter socks shall be split open and the compost distributed in landscaped areas of the site. Casing and status shall be disposed of properly.

Upon permanent stabilization of earth disturbance activity under 25 Pa. Code § 102.22(a)(2) and installation of BMPs in accordance with the approved plan prepared and implemented in accordance with 25 Pa. Code § 102.4 and 102.8, the permittee and/or co-permittee shall submit a Notice of Termination (NOT) to the Department of authorized conservation district.


Table with 4 columns: NO., REVISION, DATE, BY, APP. containing revision history for the document.

CLIENT: R.B. ASHLEY CUSTOMS, LLC
SUBJECT: POST CONSTRUCTION STORMWATER MANAGEMENT SEQUENCE
KELLY ACRES
DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA
1860 WEAVERTOWN ROAD, SUITE 100 DOUGLASSVILLE, PA 19518
PROJECT NO. 20-374A
PC520374A
SHEET NO. 19 OF 23




**LEGEND**

EX. TRACT LINE	—————
EX. BOUNDARY	—————
EX. TREELINE	~~~~~
EX. SOILS	.....
EX. CONTOURS	—————
PRE DEVELOPED DRAINAGE	—————
WATERSHED	.....




CLIENT		SUBJECT	
RB ASHLEY CUSTOMS LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465		PREDEVELOPED DRAINAGE AREA RATE  KELLY ACRES  DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA	
SEAL		PROJECT NO. 20-374A	
DESIGN BDB		CHKD. BY	DWG. NO. DA120374A
DRAWN BY SSR		CHKD. BY BDB	SHEET NO. 20 OF 23
DATE 2021-06-03		SCALE 1"=40'	

P:\PROJECTS\20-374A\_Riviera - Kelly Acres\Drawings\2021\6-3-21\20210603.dwg, 18-May-23 09:34:33  
 BOYER ENGINEERING LLC  
 1860 WEAVERTOWN ROAD, SUITE 100  
 DOUGLASSVILLE, PA 19518  
 PHONE: 610-689-6021  
 FAX: 610-689-4538




P:\PROJECTS\20-374A\_RbAshley - Kelly Acres\2021\2021.dwg, 18-May-23 09:24:59  
 BOYER ENGINEERING L.L.C.




**LEGEND**

EX. TRACT LINE	—————
EX. BOUNDARY	—————
EX. TREELINE	~~~~~
EX. SOILS	.....
EX. CONTOURS	—————
PRE DEVELOPED DRAINAGE	—————
WATERSHED	.....




CLIENT		SUBJECT	
RB ASHLEY CUSTOMS LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465		PREDEVELOPED DRAINAGE AREA VOLUME	
SEAL		KELLY ACRES	
BOYER ENGINEERING L.L.C.		DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA	
1860 WEAVERTOWN ROAD, SUITE 100 DOUGLASSVILLE, PA 19518 PHONE: 610-689-8021 FAX: 610-689-4538		PROJECT NO.	20-374A
DESIGN	BDB	CHKD. BY	DA320374A
DRAWN BY	SSR	CHKD. BY	BDB
DATE	2021-06-03	SCALE	1"=40'
		SHEET NO.	22 OF 23

P:\PROJECTS\20-374A\_Robin - Kelly Acres\2021\2021.dwg, 18-May-23 09:34:08




**LEGEND**

- EX. TRACT LINE
- EX. BOUNDARY
- EX. TREELINE
- EX. SOILS
- EX. CONTOURS
- PR. CONTOURS
- PR. EDGE OF PAVING
- PR. BUILDING
- POST DEVELOPED DRAINAGE WATERSHED



CLIENT		SUBJECT	
RB ASHLEY CUSTOMS LLC 1011 RIDGE ROAD POTTSTOWN, PA 19465		POSTDEVELOPED DRAINAGE AREA VOLUME	
SEAL		KELLY ACRES	
1860 WEAVERTOWN ROAD, SUITE 100 DOUGLASSVILLE, PA 19518 PHONE: 610-689-8021 FAX: 610-689-4538		DOUGLASS TOWNSHIP, MONTGOMERY COUNTY, PENNSYLVANIA	
DESIGN BDB		CHKD. BY	PROJECT NO. 20-374A
DRAWN BY SSR		CHKD. BY BDB	DWG. NO. DA420374A
DATE 2021-06-03		SCALE 1"=40'	SHEET NO. 23 OF 23



PROJECTS 20-374A, Revision - Kelly, Lot Utility (P) 100374A.dwg, 18-May-23, 09:35:00